SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ST. CLAIR COUNTY											
			80% FED. 20% STATE URBAN	ROADWAY I-70	BRIDGE I-70	RET. WALL I-70	CULVERT I-70								
				CONSTRUCTION TYPE CODE											
				J000-2A	X571-2A	Y007	Y007								
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	388	388											
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	318	318											
20100500	TREE REMOVAL, ACRES	ACRE	8.5	8.5											
20101200	TREE ROOT PRUNING	EACH	25	25											
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	40	40											
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	20	20											
20200100	EARTH EXCAVATION	CU YD	2,820	2,820											
20200300	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	1,712	1,712											
20200410	EARTH EXCAVATION (SPECIAL)	CU YD	5,000	5,000											
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	3,651	3,651											
20400800	FURNISHED EXCAVATION	CU YD	104,340	104,340											
20600200	GRANULAR EMBANKMENT, SPECIAL	CU YD	3,919			3,919									
20800150	TRENCH BACKFILL	CU YD	3,385	3,385											
25000312	SEEDING, CLASS 4A	ACRE	9.25	9.25											
25000314	SEEDING, CLASS 4B	ACRE	0.50	0.50											
25000350	SEEDING, CLASS 7	ACRE	29.00	29.00											
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	2,610	2,610											
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	2,610	2,610											
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2,610	2,610											
25100115	MULCH, METHOD 2	ACRE	72.00	72.00											
25100630	EROSION CONTROL BLANKET	SQ YD	26,942	26,942											
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	17,366	17,366											
28000305	TEMPORARY DITCH CHECKS	FOOT	112	112											
28000400	PERIMETER EROSION BARRIER	FOOT	10,655	10,655											
28000510	INLET FILTERS	EACH	9	9											
28001000	AGGREGATE (EROSION CONTROL)	TON	30	30											
28100107	STONE RIPRAP, CLASS A4	SQ YD	240	240											
28200200	FILTER FABRIC	SQ YD	330	330											
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,621	2,621											
40701811	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 6 1/2"	SQ YD	5,041	5,041											
44001980	CONCRETE BARRIER REMOVAL	FOOT	625	625											

• DENOTES SPECIALTY ITEMS

Rev.

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED - JB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION I-70 CONNECTION	SUMMARY OF QUANTITIES 1	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - JB	REVISED -			998	82-2-1HVB	ST. CLAIR	285	4
TENG TENG & ASSOCIATES, INC. ENGINEERS/ARCHITECTS/PLANNERS CHICAGO, ILLINOIS	PLOT SCALE = $SCALE$	CHECKED - ACL	REVISED -			CONTRACT NO. 76C44				
	PLOT DATE = $DATE$	DATE - 06/04/10	REVISED -		SCALE: N.T.S. SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

...\DBCONN-05-BORDER.DGN ...\DBCONN-05-SCD.DGN ...\DBCONN-99-MOTIF.DGN ...\DBCONN-05-LEGEND.DGN ...\DBCONN-05-MOTIF.DGN
BONDHUD \\FS-0244\AM\VAULT\D-TRANS.07\2282\238888-001\CIVIL\CAD\99 ALL CONTRACTS\CONN\SHEETS CONTRACT 05\DBCONN-05-SHT-SUMMARY1.DGN
5-03-2010,14:32:24