STEEL PLATE BEAM GUARD RAIL, TYPE B (SPECIAL) — TOTAL 475 FOOT

LOCATION	FROM STA.	OFF.	TO STA.	OFF.	SUBTOTALS
DARLING ACCESS RD.	1000+82.21	11.75' RT	1005+62.11	11.75' RT	479

TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT — TOTAL 1 EACH

LOCATION	STA.	TO STA.	SUBTOTALS
DARLING ACCESS	1005+62.11	1006+12.11	1

STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS) — TOTAL 62.5 FOOT

LOCATION	FROM STA.	OFF.	TO STA.	OFF.	SUBTOTALS
DARLING ACCESS RD.	1000+37.51	44.90' RT	1000+82.21	11.75' RT	59

CHAIN LINK FENCE, 6' — TOTAL 6,943 FOOT

LOCATION	FROM STA.	OFF.	TO STA.	OFF	LENGTH (FT)	SUBTOTALS
I-70	127+11.61	-100.0	132+81.00	-44.5	652	652
I-70	127+11.61	-100.0	128+01.45	53.0	200	200
I-70	128+06.13	76.6	132+81.00	44.5	505	528
I-70	136+70.48	-100.0	501+24.26	-8.4	407	456
I-70	136+70.48	-100.0	501+24.26	8.2	431	431
I-70	140+56.00	-82.0	1019+92.13	-12.2	1938	1,938
I-70	1019+93.33	11.8	1019+65.86	-161.0	255	255
I-70	140+61.23	70.0	10+35.94	85.4	766	766
AC RD 5	400+94.79	4.5	400+94.79	12.5	8	7
I-70	10+25.60	99.5	161+67.51	182.2	1421	1,421
I-70	39+51.45	109.1	42+34.08	45.2	289	289

CHAIN LINK GATES, 6' X 16' DOUBLE — TOTAL 1 EACH

LOCATION	STA.	SUBTOTALS
ACCESS RD 6	501+24.26	1

CHAIN LINK GATES, 6' X 24' DOUBLE — TOTAL 4 EACH

LOCATION	STA.	SUBTOTALS
ACCESS ROAD 4	201+02.15	1
DARLING ACCESS ROAD	1000+73.80	1
DARLING ACCESS ROAD	1019+92.13	1
INDUSTRIAL DRIVE	10+36.54	1

CHAIN LINK FENCE REMOVAL — TOTAL 302 FOOT

LOCATION	FROM STA.	OFF.	TO STA.	OFF	SUBTOTALS
EXCHANGE	39+51	109' RT	41+00	62' RT	164
EXCHANGE	41+00	62' RT	42+38	46' RT	138

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS — TOTAL 14 EACH

LOCATION	STATION	OFFSET (FT)	RT/LT	SUBTOTALS
I-70	127+11.61	100.00	LT	1
I-70	127+75.16	87.28	RT	1
I-70	127+84.04	133.29	RT	1
I-70	129+14.77	288.32	RT	1
I-70	132+67.29	100.00	LT	1
I-70	132+01.28	100.00	RT	1
I-70	136+55.23	133.40	RT	1
I-70	136+68.70	103.41	LT	1
I-70	136+70.48	100.00	LT	1
I-70	136+78.68	121.38	RT	1
I-70	137+16.15	91.55	LT	1
I-70	137+89.36	100.00	RT	1
I-70	141+48.68	91.55	LT	1
I-70	142+84.50	370.44	RT	1

SIGN PANEL - TYPE 1 — TOTAL 18 SQ FT
WOOD SIGN SUPPORT — TOTAL 48 FOOT

LOCATION	STATION	OFFSET (FT)	SIZE	SIGN PANEL - TYPE 1 MUTCD I.D.	SIGN PANEL - TYPE 1 SUBTOTALS	WOOD SIGN SUPPORT SUBTOTALS
ACCESS ROAD 4	205+65	0 RT	24" x 24"	OM4-1	4	12
ACCESS ROAD 5	412+40	0 RT	24" x 24"	OM4-1	4	12
ACCESS ROAD 6	499+97	0 RT	24" x 24"	OM4-1	4	12
DARLING	1000+29	16 LT	30" x 30"	R1-1	6.25	12

GUARDRAIL MARKERS, TYPE A — TOTAL 7 EACH

LOCATION	FROM STA.	OFF.	TO STA.	OFF.	LENGTH (FT)	SPACING (FT)	COLOR	SUBTOTALS
DARLING ACCESS ROAD	1000+04.81	48.12 RT	1005+62.11	11.96 RT.	525	80	CRYSTAL MONO DIRECTIONAL	7

BARRIER WALL MARKERS, TYPE C — TOTAL 64 EACH

LOCATION	FROM STA.	TO STA.	LENGTH (FT)	SPACING (FT)	COLOR	SUBTOTALS
I-70	127+81	140+64	1283	80	AMBER	16.0
I-70	127+81	140+64	1283	80	CRYSTAL	16.0
I-70	127+81	140+64	1283	80	AMBER	16.0
I-70	127+81	140+64	1283	80	CRYSTAL	16.0