

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE		SUMMARY OF QUANTITIES				CONSTRUCTION TYPE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	STP	HSIP	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	STP	HSIP
				1000 80% FED 20% STATE	SFTY-2A 90% FED 10% STATE					1000 80% FED 20% STATE	SFTY-2A 90% FED 10% STATE
20200100	EARTH EXCAVATION	CU YD	515	369	146	54001012	BOX CULVERT END SECTION, CULVERT NO.12	EACH	2	2	
28100105	STONE RIPRAP, CLASS A3	SQ YD	1471	1471		54213459	END SECTIONS 24"	EACH	4	4	
35600724	HOT-MIX ASPHALT BASE COURSE WIDENING, 12"	SQ YD	1852	1852		54213465	END SECTIONS 30"	EACH	2	2	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	59.9	59.9		542A5479	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	73	73	
40600300	AGGREGATE (PRIME COAT)	TON	287	287		542A5485	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 30"	FOOT	65	65	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	4018	4018		542C0220	PIPE CULVERTS, CLASS C, TYPE 1 15"	FOOT	154	154	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1123	1123		60600095	CLASS SI CONCRETE (OUTLET)	CU YD	30.1	30.1	
40600990	TEMPORARY RAMP	SQ YD	732	732		60602500	CONCRETE GUTTER, TYPE A	FOOT	5555.0	5555.0	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	8051	8051		*63000003	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9 FOOT POSTS	FOOT	1650	1650	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	92	92		*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	10	10	
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	95356	95356		63200310	GUARDRAIL REMOVAL	FOOT	708.5	708.5	
44000400	GUTTER REMOVAL	FOOT	5555	5555		64200105	SHOULDER RUMBLE STRIP	FOOT	1977		1977
44200120	PAVEMENT PATCHING, TYPE II, 10 INCH	SQ YD	106	106		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
44200124	PAVEMENT PATCHING, TYPE III, 10 INCH	SQ YD	58	58		67100100	MOBILIZATION	L SUM	1	1	
44200126	PAVEMENT PATCHING, TYPE IV, 10 INCH	SQ YD	2134	2134		70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SQ YD	423	423		70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
44200160	PAVEMENT PATCHING, TYPE III, 13 INCH	SQ YD	278	278		70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
44200162	PAVEMENT PATCHING, TYPE IV, 13 INCH	SQ YD	2768	2768		70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	66602	66602		70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	2617	2617		70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9323	9323	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	848	189	659	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	105975	105975	
50105220	PIPE CULVERT REMOVAL	FOOT	270	270		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1040	1040	
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	2	2		*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	105975	105975	
54001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	2	2		*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	427	427	
54001003	BOX CULVERT END SECTION, CULVERT NO. 3	EACH	2	2		*78200410	GUARDRAIL MARKERS, TYPE A	EACH	19	19	
54001004	BOX CULVERT END SECTION, CULVERT NO. 4	EACH	2	2		*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	10	10	
54001005	BOX CULVERT END SECTION, CULVERT NO. 5	EACH	2	2		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	427	427	
54001006	BOX CULVERT END SECTION, CULVERT NO. 6	EACH	2	2							
54001007	BOX CULVERT END SECTION, CULVERT NO. 7	EACH	2	2							
54001008	BOX CULVERT END SECTION, CULVERT NO. 8	EACH	1	1							
54001009	BOX CULVERT END SECTION, CULVERT NO. 9	EACH	2	2							
54001010	BOX CULVERT END SECTION, CULVERT NO. 10	EACH	2	2							
54001011	BOX CULVERT END SECTION, CULVERT NO. 11	EACH	2	2							

~~70100600 TRAFFIC CONTROL AND PROTECTION, L SUM~~  
~~STANDARD 701336~~  
 @Z0076600 TRAINEEES      HOUR 1000 1000

@Y080      \*Specialty Items      Rev.

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -			329	20RS-4(20-2,19)RS-3	RANDOLPH	19	3	
		CHECKED -	REVISED -			CONTRACT NO. 76D36					
		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					