

RESURFACING SCHEDULE

LOCATION			HMA SURFACE REMOVAL, 1"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	LEVELING BINDER, N70, 3.25"	H.M.A. SURFACE COURSE MIX D, 1.5"	STRIP REFLECTIVE CRACK CONTROL TREATMENT	AGGREGATE WEDGE SHOULDER, TYPE B, 3' WIDE
M.S.	TO	M.S.	SQ YD	TON	TON	TON	TON	FOOT	TON
0.026	0.072		647.68	0.41	1.94	27.20	60.47	485.76	
0.072	0.149		1174.51	0.74	3.52	49.33	99.16	813.12	35.57
0.149	0.276	BRIDGE OMISSION							
0.276	0.456		2428.80	1.59	7.60	106.44	213.36	1900.80	
0.456	0.900		6772.48	4.24	20.32	284.44	568.89	4688.64	205.12
0.900	0.994		1268.37	0.83	3.97	55.59	111.18	992.64	
0.994	1.199		3126.93	1.96	9.38	131.33	262.66	2164.80	94.70
1.199	1.373		2654.08	1.74	8.36	117.07	234.14	1837.44	80.38
1.373	1.532		2145.44	1.40	6.72	94.03	188.05	1679.04	
1.532	1.915		5842.03	3.66	17.53	245.37	490.73	4044.48	176.94
1.915	2.123		3172.69	1.99	9.52	133.25	266.51	2196.48	64.06
2.123	2.670		8343.57	5.22	25.03	350.43	700.86	5776.32	252.70
2.670	2.844		2654.08	1.66	7.96	111.47	222.94	1837.44	80.38
2.844	2.963		1815.15	1.14	5.45	76.24	152.98	1256.64	54.97
2.963	3.003	BRIDGE OMISSION							
3.003	3.284		4286.19	2.68	12.86	180.02	360.55	2967.36	129.81
3.284	3.453		2577.81	1.61	7.73	108.27	216.54	1784.64	78.07
3.453	4.486		15756.69	9.86	47.27	661.78	1323.56	10908.48	477.22
4.486	4.579		1254.88	0.82	3.93	55.00	109.99	982.08	
4.579	5.597		15527.89	9.72	46.58	652.17	1304.34	10750.08	470.29
5.597	5.797		3050.67	1.91	9.15	128.13	256.26	2112.00	92.39
5.797	6.021		3416.75	2.14	10.25	143.50	287.01	2365.44	103.48
6.021	6.270		3798.08	2.38	11.39	159.52	319.04	2629.44	115.03
6.270	6.500		3508.27	2.20	10.52	147.35	301.27	2428.80	106.25
TOTAL			95223.04	59.87	286.99	4017.93	8050.48	66601.92	2617.39

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SURFACE SCHEDULE			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN -	REVISED -					329	20RS-4(20-2,19)RS-3	RANDOLPH	19	4
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 76036
	PLOT DATE = #DATE#	DATE -	REVISED -									