

SUMMARY OF QUANTITIES

RURAL - PERRY COUNTY HBP FUNDING 80% FEDERAL; 20% STATE CONSTRUCTION TYPE CODE X028-2A SN 073-2007			
CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY
20200100	EARTH EXCAVATION	CU YD	586
20300100	CHANNEL EXCAVATION	CU YD	157
20700110	POROUS GRANULAR EMBANKMENT	TON	753
20800150	TRENCH BACKFILL	CU YD	54
25000200	SEEDING, CLASS 2	ACRE	0.3
25000350	SEEDING, CLASS 7	ACRE	0.3
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	27
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	27
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	27
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.6
25100115	MULCH, METHOD 2	ACRE	0.06
25100630	EROSION CONTROL BLANKET	SQ YD	695
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	60
28000305	TEMPORARY DITCH CHECKS	FOOT	24
28000400	PERIMETER EROSION BARRIER	FOOT	653
28100109	STONE RIPRAP, CLASS A5	SQ YD	134
28200200	FILTER FABRIC	SQ YD	134
40200500	AGGREGATE SURFACE COURSE, TYPE A 6"	SQ YD	64
42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	160
42001300	PROTECTIVE COAT	SQ YD	160
44000100	PAVEMENT REMOVAL	SQ YD	86
44004250	PAVED SHOULDER REMOVAL	SQ YD	313
48203037	HOT - MIX ASPHALT SHOULDERS, 10"	SQ YD	819
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
50105220	PIPE CULVERT REMOVAL	FOOT	50
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	35150
50800515	BAR SPLICERS	EACH	174
50900200	STEEL RAILING, TYPE 2399	FOOT	57
51500100	NAME PLATES	EACH	1
54003000	CONCRETE BOX CULVERTS	CU YD	163.1

RURAL - PERRY COUNTY HBP FUNDING 80% FEDERAL; 20% STATE CONSTRUCTION TYPE CODE X028-2A SN 073-2007			
CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY
54215565	METAL END SECTIONS 30"	EACH	2
542D1075	PIPE CULVERTS, CLASS D, TYPE 2 30"	FOOT	50
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6' ^{FOOT} POSTS	FOOT	137.5
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3
63200310	GUARDRAIL REMOVAL	FOOT	463
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	2
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70106700	TEMPORARY RUMBLE STRIP	EACH	6
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1
70300100	SHORT - TERM PAVEMENT MARKING	FOOT	6
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	904
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	304
70400100	TEMPORARY CONCRETE BARRIER	FOOT	275
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	263
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	904
* 78200405	GUARDRAIL MARKERS	EACH	8
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4
78300100	PAVEMENT MARKING REMOVAL	SQ FT	302
86200300	UNINTERRUPTIBLE POWER SUPPLY, EXTENDED	EACH	1
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	288
X6330103	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL, TANGENT	EACH	1
X7050167	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	1
Z0030250	IMPACT ATTENUATORS, TEMP ^{ORARY} (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2

FILE NAME : c:\pwork\pwork\corneil\m\me438\7\28051.sht.msc.dgn

USER NAME = corneil1m	DESIGNED -
	DRAWN -
PLOT SCALE = 50.0000 "/td> <td>CHECKED -</td>	CHECKED -
PLOT DATE = 4/29/2010	DATE -

REVISED -	REVISED -
	REVISED -
	REVISED -
	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
S.N. 073-0016**

SHEET NO. OF SHEETS

**Specialty Items*

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
841	108B-1	PERRY	27	3
CONTRACT NO. 78059				
ILLINOIS FED. AID PROJECT				