

IL 13 WESTBOUND PAVEMENT MARKING SCHEDULE

STATION TO STATION				PERFORMED PLASTIC PAVEMENT MARKING, TY. B						TEMPORARY PAVEMENT MARKING				SHORT-TERM	NOTES
				LEFT 4 INCH WHITE (EDGE LINE)	RIGHT 4 INCH YELLOW (EDGE LINE)	4 INCH WHITE (TURN LANE)	5 INCH (SKIP-DASH)	24 INCH (STOP BAR)	LETTERS AND SYMBOLS	4 INCH	5 INCH	24 INCH	LETTERS AND SYMBOLS	5 INCH	
				FOOT		FOOT	FOOT	FOOT	SO FT	FOOT	FOOT	FOOT	SO FT	FOOT	
IL 13 WBL MAINLINE: Sta. 99+20 to Sta. 513+64															
LT	99+20.0	TO	99+30.0	10								10			
RT	99+20.0	TO	99+86.0		66							66		4	DIAGONALS ON SHLD. (NOTE 1)
LT	100+00.0							22							
LT	100+22.0							12							
LT	101+01.0	TO	180+00.0	7899								7899		316	DIAGONALS ON SHLD. (NOTE 1)
LT	101+61.0							12							RTL STOP BAR
LT	100+61.0	TO	101+01.0		130							130		12	LEFT PAINTED ISLAND
LT	101+01.0	TO	103+89.0		288							288		35	RTL @ IL 166
LT	103+43.0								15.6					15.6	RIGHT TURN ARROW
LT	103+71.0								20.8					20.8	ONLY
	100+61.0							28						28	THRU LANE STOP BAR
	99+20.0	TO	477+37.0				9454						9454		4538
RT	100+61.0							12						12	LTL STOP BAR
RT	100+61.0	TO	100+93.0		52							52		4	RIGHT PAINTED ISLAND
RT	100+93.0	TO	103+96.0		303							303		36	LTL @ IL 166
RT	103+50.0								15.6					15.6	LEFT TURN ARROW
RT	103+78.0								20.8					20.8	ONLY
RT	100+93.0	TO	153+28.0		5235							5,235		209	DIAGONALS ON SHLD. (NOTE 1)
RT	154+70.0	TO	156+73.0		203							203		24	LTL @ DAVIS PRAIRIE RD.
RT	156+27.0								15.6					15.6	LEFT TURN ARROW
RT	156+55.0								20.8					20.8	ONLY
RT	154+70.0	TO	179+75.0		2505							2,505		100	DIAGONALS ON SHLD. (NOTE 1)
LT	180+50.0							22						22	
LT	181+00.0	TO	264+50.0	8,350								8,350		334	DIAGONALS ON SHLD. (NOTE 1)
LT	181+00.0	TO	183+05.0		205							205		25	RTL @ STILLEY'S MILL RD.
LT	182+59.0								15.6					15.6	RIGHT TURN ARROW
LT	182+87.0								20.8					20.8	ONLY
RT	181+25.0	TO	203+26.0		2201							2,201		88	DIAGONALS ON SHLD. (NOTE 1)
RT	204+30.0	TO	207+73.0		343							343		41	LTL @ W. CRAB ORCHARD RD.
RT	207+27.0								15.6					15.6	LEFT TURN ARROW
RT	207+55.0								20.8					20.8	ONLY
RT	204+77.0	TO	239+16.0		3439							3,439		138	DIAGONALS ON SHLD. (NOTE 1)
RT	240+40.0	TO	242+92.0		252							252		30	LTL @ BARBARA KAY RD.
RT	242+44.0								15.6					15.6	LEFT TURN ARROW
RT	242+72.0								20.8					20.8	ONLY
RT	240+45.0	TO	264+70.0		2425							2,425		97	DIAGONALS ON SHLD. (NOTE 1)
LT	264+90.0							22						22	
LT	265+33.0							12						12	
LT	265+60.0	TO	269+48.0		388							388		47	RTL @ PAULTON RD.
LT	269+02.0								15.6					15.6	RIGHT TURN ARROW
LT	269+30.0								20.8					20.8	ONLY
LT	266+10.0	TO	400+40.0	13430								13,430		537	DIAGONALS ON SHLD. (NOTE 1)

NOTE 1: QUANTITY UNDER SHORT-TERM PAVEMENT MARKING.

* 16-1RS-216-3,6-2,7-1,7-3RS-1

FILE NAME =	USER NAME = mcoordkr	DESIGNED -	REVISD -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE - IL 13 WBL HMA AND AGGREGATE SHOULDERS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ca:\pw\work\VPWIDOT\MCCORDKR\08186822\shp\lprf.dgn		DRAWN -	REVISD -			331		WILLIAMSON	27	17	
PLOT SCALE = 100,0000' / IN.		CHECKED -	REVISD -			SCALE: SHEET NO. OF SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT			
PLOT DATE = 4/15/2018		DATE -	REVISD -					CONTRACT NO. 78190			