

IL 13 WESTBOUND PAVEMENT MARKING SCHEDULE

(CONTINUED)

STATION TO STATION				PERFORMED PLASTIC PAVEMENT MARKING, TY. B					TEMPORARY PAVEMENT MARKING				SHORT-TERM	NOTES	
				LEFT 4 INCH WHITE (EDGE LINE)	RIGHT 4 INCH YELLOW (EDGE LINE)	4 INCH WHITE (TURN LANE)	5 INCH (SKIP-DASH)	24 INCH (STOP BAR)	LETTERS AND SYMBOLS	4 INCH	5 INCH	24 INCH	LETTERS AND SYMBOLS		5 INCH
				FOOT		FOOT	FOOT	FOOT	SO FT	FOOT	FOOT	FOOT	SO FT		FOOT
IL 13 WBL MAINLINE: Sta. 99+20 to Sta. 513+64															
LT	400+90.0						22			22					
LT	401+25.0						12			12					
LT	401+52.0	TO	404+33.0			281			281			34		RTL @ ANGELVILLE RD. RIGHT TURN ARROW ONLY	
LT	400+87.0						15.6				15.6				
LT	401+15.0						20.8				20.8				
LT	401+97.0	TO	477+37.0	7540					7,540			302		DIAGONALS ON SHLD. (NOTE 1)	
RT	401+55.0	TO	403+95.0			240			240			29		LTL @ ANGELVILLE RD. LEFT TURN ARROW ONLY	
RT	403+49.0						15.6				15.6				
RT	403+77.0						20.8				20.8				
RT	401+55.0	TO	477+37.0		7582				7,582			303		DIAGONALS ON SHLD. (NOTE 1)	
SN 100-0068 Omission - Sta. 477+37 to Sta. 479+45															
LT	479+45.0	TO	498+00.0	1855					1,855			74		DIAGONALS ON SHLD. (NOTE 1)	
RT	479+45.0	TO	497+65.0		1820				1,820			73		DIAGONALS ON SHLD. (NOTE 1)	
LT	498+34.0						22				22				
LT	498+90.0	TO	513+64.0	1474					1,474			59		DIAGONALS ON SHLD. (NOTE 1)	
RT	498+55.0	TO	513+64.0		1509				1,509			60		DIAGONALS ON SHLD. (NOTE 1)	
	479+45.0	TO	513+64.0			855				855		274			
SUBTOTALS				40,558	40,171	3278	10,309	198	400.4	84,007	10,309	198	400.4	8,429	
IL 13 WBL TOTALS					84,007		10,309	198	400.4	84,007	10,309	198	400.4	8,429	

NOTE 1: QUANTITY UNDER SHORT-TERM PAVEMENT MARKING.

* 16-11RS-216-3.6-2.7-1.7-31RS-1

FILE NAME =	USER NAME = mccordk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE - IL 13 WBL HMA AND AGGREGATE SHOULDERS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\p\work\FW100T\MCCOROKR\d0186822\sh	plnprf.dgn	DRAWN -	REVISED -			331		WILLIAMSON	27	18
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -			SCALE: _____ SHEET NO. _____ OF _____ SHEETS STA. _____ TO STA. _____		CONTRACT NO. 18190		ILLINOIS FED. AID PROJECT
PLOT DATE = 4/15/2010		DATE -	REVISED -							