July 12, 2021

SUBJECT: Route MUN 0001A (Weathersfield Way)

Section 17-00129-00-PV (Schaumburg)

Cook County

Contract No. 61H07

Item 009

July 30, 2021 Letting

Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised sheet 2 of the Plans.
- 2. Revised the Table of Contents to the Special Provisions.
- 3. Revised page 32 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Jack A. Elston, P.E.

Bureau Chief, Design and Environment

TABLE OF CONTENTS

	PROJECT LOCATION	1
	PROJECT DESCRIPTION	1
	MAINTENANCE OF ROADWAYS	1
	TRAFFIC CONTROL PLAN	2
	ADJUSTMENTS AND RECONSTRUCTIONS	3
	PUBLIC CONVENIENCE AND SAFETY (DIST 1)	4
	DRAINAGE AND INLET PROTECTION UNDER TRAFFIC (DISTRICT 1)	
	FRICTION AGGREGATE (D-1)	7
	HOT-MIX ASPHALT BINDER AND SURFACE COURSE (D-1)	10
	AGGREGATE SUBGRADE IMPROVEMENT (D-1)	
	HAMBURG WHEEL AND TENSILE STRENGTH RATIO TESTING (D-1)	22
	STATUS OF UTILITIES (D-1)	24
	AVAILABLE REPORTS	26
	CONSTRUCTION SCHEDULE (VOS)	27
	UTILITY LOCATION (VOS)	
	CONSTRUCTION OPERATIONS (VOS)	
	ROOT PRUNING, SHRUB AND TREE TRIMMING (VOS)	30
	INSPECTION (VOS)	30
	DUST CONTROL (VOS)	
	STREET SWEEPING (VOS)	30
	PROTECTION OF EXISTING DRAINAGE FACILITIES DURING CONSTRUCTION (VOS)	31
	SAWING PAVEMENT, DRIVEWAY PAVEMENT, SIDEWALK, AND CURB (VOS)	31
	SAWING PAVEMENT, DRIVEWAY PAVEMENT, SIDEWALK, AND CURB (VOS)	32
د	SEWER CONNECTIONS (VOS)	32
	FRAMES, LIDS, CATCH BASINS, MANHOLE, INLET, DRAINAGE STRUCTURE, AND VAL	.VE
	VAULT CONSTRUCTION, ADJUSTMENT AND RECONSTRUCTION (VOS)	
	BITUMINOUS MATERIALS – TRACKLESS TACK COAT (VOS)	
	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT (VOS)	
	PORTLAND CEMENT CONCRETE SIDEWALK (VOS)	
	DRIVEWAY PAVEMENT REMOVAL (VOS)	
	COMBINATION CURB AND GUTTER REMOVAL / COMBINATION CONCRETE CURB ANI GUTTER (VOS)	
	SIDEWALK REMOVAL (VOS)	37
	CLASS D PATCHES (VOS)	37
	STORM SEWERS (VOS)	
	TRAFFIC CONTROL AND PROTECTION (VOS)	
	SEDIMENT CONTROL, DRAINAGE STRUCTURE, INLET FILTER (VOS)	
	SODDING (VOS)	41
	DETECTABLE WARNINGS (VOS)	41

FAU 0001 (WEATHERSFIELD WAY) SECTION 17-00129-00-PV CONTRACT: 61H07 SCHAUMBURG

	COOK COUNTY
MATERIAL INSPECTION (VOS)	$\stackrel{\checkmark}{\sim}$
	\prec
	3
	2
	\langle
	\prec

SEWER CONNECTIONS (VOS)

This work shall consist of the work necessary to rebuild the sewer connections at all locations where the existing structures have been reconstructed or removed and replaced with new structures as well as any coring needed to connect into existing structures where described within the plans or as directed by the Engineer or representative of the Engineer. The connection shall be made with the same size and type of materials as the existing pipe, or as directed by the Engineer or representative of the Engineer. If a tight connection cannot be obtained with normal connection procedures, or other means of mechanical coupling approved by the Engineer or representative of the Engineer will be used.

Excavation of trenches shall be performed according to the applicable requirements of Article 550.04. Backfill of trenches shall be performed according to the applicable requirements of Article 550.07

New storm sewer installations will be measured for payment in place in feet of the type specified. When the storm sewer enters a manhole, inlet, or catch basin, the measurement will end at the inside wall of the manhole, inlet or catch basin.

No payment for storm sewer will be made through a manhole, inlet or catch basin where the manhole, inlet or catch basin is paid for as a separate item. However, when the storm sewer is continuous and the manhole, inlet or catch basin is constructed on top of the storm sewer, the measurement will be from end to end of storm sewer with a deduction made for the tee section which is paid for separately.

Removal of the existing storm sewers will not be measured for payment, but shall be considered as included in the cost of the new storm structure as specified.

This work shall be included in the cost of the manhole, inlet, catch basin and pipe items and shall include all labor, materials, and equipment necessary to complete this work in accordance with the plans and specifications, unless otherwise specified.