

ENTRANCES/SIDEROADS

| LOCATION | | | | CENTERLINE TO ROW | WIDTH AT SHOULDER | SHOULDER TO THROAT | THROAT WIDTH | THROAT TO TERMINI | TERMINI WIDTH | AREA | 40600290 | 40800050 | 44000157 | |
|-----------------|-----|---------|---------|---------------------|-------------------|--------------------|--------------|-------------------|---------------|-------|----------------------------------|-----------------------------|------------------------------------|-------|
| | | | | | | | | | | | BITUMINOUS MATERIALS (TACK COAT) | INCIDENTAL HMA SURFACING 2" | HOT-MIX ASPHALT SURFACE REMOVAL 2" | |
| STA | STA | RT/LT | REMARKS | FOOT | FOOT | FOOT | FOOT | FOOT | FOOT | SQ YD | POUND | TONS | SQYD | |
| RURAL EB | | | | | | | | | | | | | | |
| 1341+83 | - | 1342+80 | RT | 31th ST | - | 77.0 | 27.0 | 26.0 | 1.0 | 1.0 | 156.0 | 70.2 | 17.5 | 156.0 |
| 1358+99 | - | 1360+11 | RT | PE / MB | - | 70.0 | 19.0 | 28.0 | 1.0 | 1.0 | 105.1 | 47.3 | 11.8 | - |
| 1379+56 | - | 1379+98 | RT | CE | - | 42.0 | 19.0 | 28.0 | 1.0 | 1.0 | 75.5 | 34.0 | 8.5 | - |
| 1386+05 | - | 1387+36 | RT | FE | - | 63.0 | 18.0 | 37.0 | 1.0 | 1.0 | 102.1 | 46.0 | - | - |
| 1391+95 | - | 1394+41 | RT | FE | - | 112.0 | 42.0 | 57.0 | 1.0 | 1.0 | 397.6 | 178.9 | - | - |
| 1405+04 | - | 1406+16 | LT | PE | - | 42.0 | 14.0 | 35.0 | 1.0 | 1.0 | 61.9 | 27.9 | 6.9 | - |
| 1407+84 | - | 1408+99 | LT | PE / MB | - | 40.0 | 14.0 | 40.0 | 1.0 | 1.0 | 64.5 | 29.0 | 7.2 | - |
| 1406+85 | - | 1407+98 | RT | RIDGEWOOD RD | - | 177.0 | 37.0 | 90.0 | 45.0 | 46.0 | 888.8 | 400.0 | 99.5 | 888.8 |
| 1409+71 | - | 1410+22 | LT | PE | - | 65.0 | 17.0 | 34.0 | 1.0 | 1.0 | 95.4 | 43.0 | 10.7 | - |
| 1410+39 | - | 1411+41 | LT | 12th ST | - | 80.0 | 42.0 | 26.0 | 1.0 | 1.0 | 248.8 | 112.0 | 27.9 | 248.8 |
| 1413+76 | - | 1414+81 | LT | 11th ST | - | 72.0 | 44.0 | 27.0 | 1.0 | 1.0 | 243.6 | 109.6 | 27.3 | 243.6 |
| 1414+81 | - | 1415+58 | LT | PE / MB | - | 43.0 | 24.0 | 35.0 | 1.0 | 1.0 | 106.0 | 47.7 | 11.9 | - |
| 1415+82 | - | 1416+87 | LT | PE / MB | - | 41.0 | 27.0 | 26.0 | 1.0 | 1.0 | 102.0 | 45.9 | 11.4 | - |
| 1417+07 | - | 1418+01 | LT | 10th ST N | - | 64.0 | 34.0 | 24.0 | 1.0 | 1.0 | 167.6 | 75.4 | 18.8 | 167.6 |
| 1417+05 | - | 1417+67 | RT | 10th ST S | - | 36.0 | 8.0 | 33.0 | 1.0 | 1.0 | 32.6 | 14.7 | 3.6 | 32.6 |
| 1418+60 | - | 1419+70 | LT | CE | - | 43.0 | 20.0 | 28.0 | 1.0 | 1.0 | 80.5 | 36.2 | 9.0 | - |
| 1420+35 | - | 1421+26 | LT | 9th ST | - | 88.0 | 39.0 | 30.0 | 1.0 | 1.0 | 257.4 | 115.8 | 28.8 | 257.4 |
| 1425+80 | - | 1426+29 | LT | ROCK ISLAND CO. OFC | - | 59.0 | 33.0 | 22.0 | 1.0 | 1.0 | 149.8 | 67.4 | 16.8 | - |
| 1427+75 | - | 1428+50 | LT | PE | - | 53.0 | 21.0 | 27.0 | 1.0 | 1.0 | 94.9 | 42.7 | 10.6 | - |
| 1427+63 | - | 1428+77 | RT | 8 1/2th ST | - | 62.0 | 25.0 | 28.0 | 1.0 | 1.0 | 126.6 | 57.0 | 14.2 | 126.6 |
| 1430+45 | - | 1431+28 | LT | CE | - | 55.0 | 34.0 | 19.0 | 1.0 | 1.0 | 140.9 | 63.4 | 15.8 | - |
| 1431+46 | - | 1432+61 | LT | CE | - | 46.0 | 24.0 | 25.0 | 1.0 | 1.0 | 96.1 | 43.3 | 10.8 | - |
| 1432+94 | - | 1434+02 | LT | CE | - | 49.0 | 31.0 | 25.0 | 1.0 | 1.0 | 128.9 | 58.0 | 14.4 | - |
| 1433+34 | - | 1433+93 | RT | PE | - | 45.0 | 17.0 | 27.0 | 1.0 | 1.0 | 69.6 | 31.3 | 7.8 | - |
| 1435+34 | - | 1435+79 | RT | PE | - | 25.0 | 22.0 | 18.0 | 1.0 | 1.0 | 53.6 | 24.1 | 6.0 | - |
| 1435+79 | - | 1436+54 | RT | 6th ST N | - | 61.0 | 32.0 | 32.0 | 1.0 | 1.0 | 167.2 | 75.2 | 18.7 | 167.2 |
| 1435+86 | - | 1436+88 | LT | 6th ST S | - | 87.0 | 26.0 | 38.0 | 1.0 | 1.0 | 182.7 | 82.2 | 20.5 | 182.7 |
| 1438+14 | - | 1438+80 | LT | PE | - | 17.0 | 15.0 | 17.0 | 11.0 | 1.0 | 39.3 | 17.7 | 4.4 | - |
| 1438+66 | - | 1439+29 | RT | CE | - | 46.0 | 19.0 | 43.0 | 1.0 | 1.0 | 96.4 | 43.4 | 10.8 | - |
| 1439+48 | - | 1439+94 | LT | PE | - | 35.0 | 20.0 | 12.0 | 1.0 | 1.0 | 52.9 | 23.8 | 5.9 | - |
| 1440+62 | - | 1441+65 | LT | CE | - | 33.0 | 19.0 | 23.0 | 1.0 | 1.0 | 60.4 | 27.2 | 10.2 | - |
| 1442+02 | - | 1443+02 | RT | CE | - | 37.0 | 17.0 | 34.0 | 1.0 | 1.0 | 69.0 | 31.1 | 15.5 | - |
| 1442+08 | - | 1443+25 | LT | CE | - | 90.0 | 38.0 | 58.0 | 1.0 | 1.0 | 315.7 | 142.1 | 88.4 | - |
| 1443+43 | - | 1444+05 | LT | CE | - | 58.0 | 38.0 | 37.0 | 1.0 | 1.0 | 202.7 | 91.2 | 68.1 | - |
| TOTAL | | | | | | | | | | | 2,355 | 640 | 2,472 | |



MODEL: Default
 FILE: \\nrcs-pix\pub\lancorn.dwg
 PROJECTS\6491\Program_Development\Schedules & Plans\Design\CADD\CAD\Sheet102_6491_sch-schedule_REF.dwg

REVISED SHEET 7/16/2021

| | | |
|-------------------------------------|------------------|------------------------------|
| USER NAME = romerore | DESIGNED - _____ | REVISED - 07/15/2021 R.E.R. |
| | DRAWN - _____ | REVISED - _____ |
| PLOT SCALE = 100,0000' / in. | CHECKED - _____ | REVISED - _____ |
| PLOT DATE = Jul-15-2021 05:02:04 PM | DATE - _____ | REVISED - _____ |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

| | | | |
|-------------------------------------|---------------|------|--------|
| ENTRANCE /SIDEROADS SCHEDULE | | | |
| SCALE: _____ | SHEET 1 | OF 1 | SHEETS |
| STA. _____ | TO STA. _____ | | |

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------------|------------------|-------------|--------------|-----------|
| 599 | (48MFT, 62MFT)RS | ROCK ISLAND | 45 | 24 |
| CONTRACT NO. 64N91 | | | | |
| ILLINOIS FED. AID PROJECT | | | | |