

SIDEWALK			
LOCATION	SIDEWALK REM (SQ FT)	PC CONC SIDEWALK 4 SP (SQ FT)	DETECTABLE WARNINGS (SQ FT)
VISITOR CENTER (FLAGPOLE)	268	268	
15+24.86, 84.08L LT	100	100	20
MONK STA 80+61.87 TO STA 91+17.01		5276	
WALL STA 100+00 TO STA 104+74.97		2375	
SOUTH STA 202+50 TO STA 211+75.50		4628	
TOTAL =	288	12,646	20

EROSION CONTROL		
LOCATION	INLET & PIPE PROTECT (EACH)	TEMP DITCH CHECKS (EACH)
STA. 14+50, 14.62' LT	1	
STA. 14+95.52, 57.09' LT	1	
STA. 15+35.76, 22.50' LT	1	
STA. 42+43, 17.53' RT		1
TOTAL =	3	1

REMOVAL SCHEDULE		
LOCATION	FIELD ENTRANCE REMOVAL (L SUM)	PIPE CULVERT REMOVAL (FOOT)
COLLINS STREET STA. 42+93.07, 16.27' RT	1	
STA. 42+20.00		10
STA. 42+88.06, 16.03' RT TO STA. 42+98.08, 16.52' RT		10
TOTAL =	1	20

PAVEMENT MARKING SCHEDULE					
LOCATION	PT PVT MK LTRS & SYMB (SQ. FT.)	PAINT PVT MK LINE 4 (FOOT)	PAINT PVT MK LINE 6 (FOOT)	PAINT PVT MK LINE 24 (FOOT)	REM REIN PARKING BLKS (EACH)
RAMEY STREET					
13+30.00 TO 28+93.56 C		391			
13+30.00, 12' RT TO 28+93.56, 12' RT		1564			
14+18.00, 28' LT	6.5				
14+44.00, 56' LT	25.9				
15+43.00, 54' LT	25.9				
15+94.00, 27' LT	6.5				
18+86.15, 12' LT TO 28+93.56, 12' LT		1007			
28+44.00, TO 28+66.00 (ISLAND)		80			
28+45.00, 28' RT TO 28+54, 20' RT				12	
28+56.00, 0' RT TO 28+56.00, 12' RT				12	
COLLINS STREET					
40+28.00, TO 43+62.00 C		84			
40+28.00 TO 43+62.00, 12' RT		334			
40+28.00 TO 44+63.00, 12' LT		435			
40+36.00, 0' LT TO 40+36.00, 19' LT				19	
PARKING LOT STRIPING	4.6		270		
MONKS MOUND PARKING LOT					50
TOTAL =	69.4	3895	270	43	50

NOTE: LETTERS AND SYMBOLS  
SMALL DIRECTIONAL ARROW = 6.5 SQ FT  
HANDICAP SYMBOL = 4.6 SQ FT

MISCELLANEOUS							
LOCATION	VALVE BOX FRAMES ADJ. (EACH)	PIPE BOL REM. + REPL. (EACH)	PARK BENCHES (EACH)	STEEL EDGING (FOOT)	CONCRETE SLAB (SQ YD)	BRICK SGN AND FOUND REM (L SUM)	FLAG-POLES (EACH)
RAMEY STREET							
VISITOR CENTER						1	3
STA. 14+92.18, 34.13' LT							
STA. 22+74.30, 15.00' LT		1					
STA. 22+76.62, 13.50' LT		1					
STA. 22+83.03, 13.50' LT		1					
STA. 28+09.17, 12.00' LT	1						
STA. 28+36.60, 28.00' LT	1						
STA. 28+38.29, 28.00' LT	1						
STA. 28+41.62, 28.00' LT	1						
STA. 28+48.49, 18.00' LT	1						
STA. 80+50.77, 116.36' LT				10			
STA. 80+54.29, 190.00' LT			1		7.8		
STA. 80+62.62, 116.22' LT				10			
STA. 80+75.29, 440.00' LT			1		7.8		
STA. 84+02.33, 2.40' LT			1		7.8		
STA. 202+50.84, 9.21' LT			1				
TOTAL =	5	3	4	20	23.4	1	3

\*REMOVAL ONLY

SIGNING SCHEDULE						
LOCATION	MESSAGE	MUTCD NO.	SIGN REMOVAL (EACH)	SIGN PANELS T-1 (SQ FT)	SIGN PANEL T-3 SPECIAL (SQ. FT.)	MINOR SIGN COMPLETE (EACH)
COLLINS STREET 45+50, 50' LT	FINE SIGN	R 7-I 101		0.5		
STA. 80+47.48, 6.34' LT			1			1
STA. 80+54.25, 181.88' LT						1
STA. 80+67.21, 4.92' LT			1			1
STA. 80+77, 437' LT						1
STA. 83+99.65, 2.5' LT						1
STA. 91+06, 5.25' LT			1			1
STA. 91+13, 6' LT			1			1
STA. 101+13, 4' LT			1			1
STA. 202+60.80, 13.60' RT	INTERPRETIVE				24	
STA. 300+50, 2.5' LT						1
STA. 305+00, 2.5' RT						1
STA. 315+55, 2.5' LT						1
STA. 320+25, 2.5' LT						1
STA. 324+38, 2.5' LT						1
STA. 404+50, 2.5' RT						1
STA. 411+00, 2.5' RT						1
TOTAL =			5	0.5	24	15

NOTE: ALL POST UNLESS OTHERWISE NOTED SHALL MEET THE REQUIREMENTS OF SECTION 728 OF THE STANDARD SPECIFICATIONS. EACH POST SHALL ALSO INCLUDE A 2 1/4" x 2 1/4" x 4' BASE DRIVEN INTO THE GROUND EXCEPT THE LAST 3".

ALL POST SHALL BE OFFSET FROM EDGE OF THE PAVEMENT BY 6'. SEE STANDARD DRAWINGS FOR POST IN PAVEMENT.

SUMMARY OF QUANTITIES			
CODE #	PAY ITEM	UNITS	TOTAL
20200600	EXCAVATING AND GRADING EXISTING SHOULDERS	UNIT	24.1
20800150	TRENCH BACKFILL	CU YD	46
* 21101600	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	SO YD	2716
21400100	GRADING AND SHAPING DITCHES	FOOT	131
* 25000100	SEEDING, CLASS 1	ACRE	0.71
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	65
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	65
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	65
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	1.42
28000300	TEMPORARY DITCH CHECK	EACH	1
28000500	INLET AND PIPE PROTECTION	EACH	3
28000720	MULCH, METHOD 2	ACRE	0.71
35102200	AGGREGATE BASE COURSE TYPE B, 10"	SO YD	85
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	294
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,859
40600300	AGGREGATE (PRIME COAT)	TON	20
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	525
40600990	TEMPORARY RAMP	SO YD	337
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	7
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	716
42000300	PORTLAND CEMENT CONCRETE PAVEMENT, 8"	SO YD	5.3
42001200	PAVEMENT FABRIC	SO YD	5.3
42400420	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH, SPECIAL	SO FT	12,646
42400800	DETECTABLE WARNINGS	SO FT	20
44000100	PAVEMENT REMOVAL	SO YD	5.3
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	5,196
44000400	GUTTER REMOVAL	FOOT	249
44000600	SIDEWALK REMOVAL	SO FT	288
44212899	PAVEMENT PATCHING (FULL DEPTH)	SO YD	177
48101200	AGGREGATE SHOULDERS, TYPE B	TON	89
48203013	HOT-MIX ASPHALT SHOULDERS, 4"	SO YD	829
50105220	PIPE CULVERTS REMOVAL	FOOT	20
54200433	PIPE CULVERTS, TYPE 1 RCCP, 18"	FOOT	4
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1
550A0050	STORM SEWER, CLASS A, TYPE 1 12"	FOOT	84
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	1
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	1
60300405	VALVE BOX FRAMES TO BE ADJUSTED	EACH	5
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	271
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
* 72000100	SIGN PANEL - TYPE 1	SO FT	0.5
* 72000305	SIGN PANEL - TYPE 3 (SPECIAL)	SO FT	24
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	69.4
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3,895
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	270
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	43
* K1005582	STEEL EDGING	FOOT	20
XX004357	FIELD ENTRANCE REMOVAL	L SUM	1
XX004603	CONCRETE SLAB	SO YD	23.4
XX005644	MINOR SIGN COMPLETE	EACH	15
XX006091	PIPE BOLLARD REMOVAL AND REPLACEMENT	EACH	3
XX006582	BRICK SIGN AND CONCRETE FOUNDATION REMOVAL	L SUM	1
X0300019	REMOVE AND REINSTALL PARKING BLOCKS	EACH	50
X0321158	PARK BENCHES	EACH	4
X0323407	FLAGPOLES	EACH	3
X0325372	SURFACE REMOVAL VARIABLE DEPTH (HAND METHOD)	SO YD	765
X0974300	SIGN REMOVAL	EACH	5
X4020500	AGGREGATE SURFACE COURSE, TYPE B 6"	SO YD	104

\*Specialty Items

FILE NAME =	USER NAME = #USER#	DESIGNED - T.T.P.	REVISED -
#FILE#		DRAWN - S.D.K.	REVISED -
	PLOT SCALE = #SCALE#	CHECKED - R.H.D.	REVISED -
	PLOT DATE = #DATE#	DATE - 5/8/09	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY / SCHEDULE OF QUANTITIES  
CAHOKIA MOUNDS STATE HISTORIC SITE

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		ST. CLAIR	12	3
CONTRACT NO. 46060				
SCALE:	SHEET NO. 3 OF 12 SHEETS	STA. TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	