

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) I-11	WILL	176	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID	PROJECT	

URBAN  
98% FED.  
10% STATE

SPEC. ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		STRUCT.	SIGNING
					1000	Y220		
	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	92	92			
	54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2	2			
	54215424	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 24"	EACH	1	1			
	55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	713	713			
	55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	448	448			
	55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18"	FOOT	37	37			
	55022000	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 24"	FOOT	8	8			
	55035300	STORM SEWERS, TYPE 2, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 23, RISE 14	FOOT	8	8			
	60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	92	92			
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	4971.5	4971.5			
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	470	470			
	63200310	GUARDRAIL REMOVAL	FOOT	179	179			
	63302700	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2			
	66400105	CHAIN LINK FENCE, 4'	FOOT	266	266			
	66410300	CHAIN LINK FENCE REMOVAL	FOOT	11872	11872			
	66500105	WOVEN WIRE FENCE, 4'	FOOT	180	180			
	66502300	WOVEN WIRE FENCE REMOVAL	FOOT	4767	4767			
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	18	18			
	67100100	MOBILIZATION	L SUM	1	1			
	70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1			
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	14	14			
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	237.5	237.5			
	72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	2				2
	72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	2				2
	72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	2793				2793
	73400100	CONCRETE FOUNDATIONS	CU YD	7.6				7.6
	73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	4				4
	78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	38	38			
*	80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1			
*	81400200	HEAVY-DUTY HANDHOLE	EACH	1	1			
*	89502380	REMOVE EXISTING HANDHOLE	EACH	1	1			
*	A2000114	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	17	17			
*	A2002374	TREE, BETULA NIGRA (RIVER BIRCH), 10' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	10	10			
*	A2002920	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	40	40			
*	A2005020	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	15	15			

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
FAI ROUTE 55 (BLACK ROAD TO U.S. ROUTE 30)  
NOISE ABATEMENT WALLS

**SUMMARY OF QUANTITIES  
II**

SCALE: N.T.S.  
DATE 02/06/09

DRAWN BY AG  
CHECKED BY DDH

**TENG**

TENG & ASSOCIATES, INC.  
ENGINEERS/ARCHITECTS/PLANNERS  
CHICAGO, ILLINOIS

PLOT DATE = #DATE#  
 FILE NAME = #FILE#  
 PLOT SCALE = #SCALE#  
 USER NAME = #USER#  
 \\B0191A021LDN... \S0121A021LDN... \S0121A021LDN  
 K:\NF\TMR S:\DOCUMENT 02\36569\1\CIVIL\LOG\50121A021.SHT  
 2-06-2009 11:38:47