

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) 1-11	WILL	176	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

URBAN
90% FED
10% STATE

SPEC. ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		STRUCT.	SIGNING
					I000	Y220		
*	A2006514	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	15	15			
*	A2006714	TREE, QUERCUS MACROCARPA (BUR OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	60	60			
*	A2007064	TREE, MALUS PRAIRIE ROSE (PRAIRIE ROSE CRABAPPLE), 1-1/2" CALIPER, LOW-BRANCHED, BALLED AND BURLAPPED	EACH	15	15			
*	B2001664	TREE, CRATAEGUS CRUSGALLI INERMIS (THORN LESS COCKSPUR HAWTHORN), 5' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	30	30			
*	C2C06024	SHRUB, RHUS TYPHINA (STAGHORN SUMAC), 2' HEIGHT, CONTAINER	EACH	80	80			
*	D2001560	EVERGREEN, JUNIPERUS VIRGINIANA (EASTERN RED CEDAR), 5' HEIGHT, BALLED AND BURLAPPED	EACH	150	150			
*	D2002160	EVERGREEN, PICEA PUNGENS (COLORADO SPRUCE), 5' HEIGHT, BALLED AND BURLAPPED	EACH	10	10			
*	E20200G1	VINE-PARTHENOCISSUS QUINQUEFOLIA (VIRGINIA CREEPER), 1-GALLON POT	EACH	11590	11590			
*	K0036120	MULCH PLACEMENT 4"	SQ YD	160	160			
	X0301423	NOISE ABATEMENT WALL, GROUND MOUNTED	SQ FT	282390		282390		
*	X0322324	WEED CONTROL, TEASEL	POUND	0.36	0.36			
*	X0322859	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	115.2	115.2			
	X0322939	RELOCATE EXISTING FLARED END SECTION	EACH	2	2			
	X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	1531	1531			
	X0324013	NOISE ABATEMENT WALL, STRUCTURE MOUNTED	SQ FT	505		505		
	X2010300	TREE REMOVAL (UNDER 6 UNITS DIAMETER)	UNIT	78	78			
	X6050700	REMOVE INLET BOX	EACH	1	1			
*	X6330190	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL	EACH	2	2			
	X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1			
	XX006367	INLET AND OUTLET PROTECTION	EACH	13	13			
*	XX007763	TEMPORARY FENCE (SPECIAL)	FOOT	17264	17264			
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			
*	Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 2	EACH	2	2			
	Z0064800	SELECTIVE CLEARING	UNIT	90	90			
⊙	Z0076600	TRAINEES	HOUR	1500	1500			
*	X0324397	RELOCATE ELECTRIC SERVICE	EACH	1	1			

PLOT DATE = #DATE#
FILE NAME = #FILE#
PLOT SCALE = #SCALE#
USER NAME = #USER#

⊙ 1080
* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55 (BLACK ROAD TO U.S. ROUTE 30)
NOISE ABATEMENT WALLS

**SUMMARY OF QUANTITIES
III**

SCALE: N.T.S. DRAWN BY AG
DATE 02/06/09 CHECKED BY DDH

TENG
TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
CHICAGO, ILLINOIS

Rev.