CONTRACT NO. 60B03

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) I-11	WILL	176	11
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

EARTHWORK SCHEDULE OF QUANTITIES

STA FROM	TO STA	20200100 EARTH EXCAVATION	20201200 REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU YD	CU YD	CU YD	CU YD	CU YD
I-55 NOISE WALL 3 - BEFORE SUNNLYLAND DRAIN						
324+54.04	324+70.00	0.0	2.9	0.0	4.2	-4.2
324+70.00	325+00.00	0.0	11.1	0.0	17.1	-17.1
325+00.00	326+00.00	0.0	35.1	0.0	49.4	-49.4
326+00.00	327+00.00	0.0	33.4	0.0	42.0	-42.0
327+00.00	328+00.00	0.0	33.4	0.0	42.6	-42.6
328+00.00	329+00.00	0.0	31.9	0.0	37.1	-37.1
329+00.00	330+00.00	0.0	31.4	0.0	33.4	-33.4
330+00.00	331+00.00	0.0	33.5	0.0	38.6	-38.6
331+00.00	332+00.00	0.0	39.9	0.0	57.5	-57.5
332+00.00	333+00.00	0.0	41.0	0.0	58.9	-58.9
333+00.00	334+00.00	0.0	36.3	0.0	48.6	-48.6
334+00.00	335+00.00	0.0	35.2	0.0	50.2	-50.2
335+00.00	336+00.00	0.0	36.6	0.0	54.9	-54.9
336+00.00	337+00.00	0.0	38.7	0.0	62.7	-62.7
337+00.00	338+00.00	0.0	40.3	0.0	67.3	-67.3
338+00.00	339+00.00	0.0	39.9	0.0	62.4	-62.4
339+00.00	340+00.00	0.0	39.5	0.0	58.1	-58.1
340+00.00	341+00.00	0.0	39.6	0.0	57.3	-57.3
341+00.00	342+00.00	0.0	38.2	0.0	57.8	-57.8
342+00.00	343+00.00	0.0	36.5	0.0	54.9	-54.9
343+00.00	344+00.00	0.0	37.4	0.0	54.1	-54.1
344+00.00	345+00.00	0.0	39.7	0.0	57.0	-57.0
345+00.00	346+00.00	0.0	42.3	0.0	60.5	-60.5
346+00.00	347+00.00	0.0	43.9	0.0	66.0	-66.0
347+00.00	348+00.00	0.0	44.5	0.0	64.6	-64.6
348+00.00	349+00.00	0.0	51.4	0.0	84.8	-84.8
349+00.00	350+00.00	0.0	60.8	0.0	116.4	-116.4
350+00.00	351+00.00	0.0	62.6	0.0	118.6	-118.6
351+00.00	352+00.00	0.0	57.6	0.0	104.5	-104.5
352+00.00	353+00.00	0.0	53.0	0.0	87.1	-87.1
353+00.00	354+00.00	0.0	51.8	0.0	84.9	-84.9
354+00.00	355+00.00	0.0	50.8	0.0	83.9	-83.9
355+00.00	356+00.00	0.0	49.2	0.0	76.8	-76.8
356+00.00	357+00.00	0.0	48.5	0.0	75.2	-75.2
357+00.00	358+00.00	0.0	52.7	0.0	82.2	-82.2
358+00.00	359+00.00	0.0	53.7	0.0	79.1	-79.1
359+00.00	360+00.00	0.0	43.0	0.0	48.7	-48.7
360+00.00	361+00.00	0.0	36.1	0.0	40.8	-40.8
361+00.00	362+00.00	0.0	37.3	0.0	53.3	-53.3
362+00.00	363+00.00	0.0	38.9	0.0	59.9	-59.9
363+00.00	364+00.00	0.0	38.6	0.0	61.4	-61.4
364+00.00	365+00.00	0.0	39.4	0.0	67.5	-67.5
365+00.00	366+00.00	0.0	41.1	0.0	78.2	-78.2
366+00.00	367+00.00	0.0	40.8	0.0	68.3	-68.3
367+00.00	368+00.00	0.0	43.1	0.0	73.4	-73.4
368+00.00	369+00.00	0.0	47.1	0.0	95.5	-95.5
369+00.00	370+00.00	0.0	48.3	0.0	97.1	-97.1
370+00.00	371+00.00	0.0	44.1	0.0	76.9	-76.9
371+00.00	372+00.00	0.0	36.6	0.0	49.6	-49.6

STA FROM	TO STA	20200100 EARTH EXCAVATION	20201200 REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU YD	CU YD	CU YD	CU YD	CU YD
I-55 NOISE WALL 3 - BEFORE SUNNYLAND DRAIN (CONTINUED)						
372+00.00	373+00.00	0.0	34.9	0.0	45.2	-45.2
373+00.00	374+00.00	0.0	40.9	0.0	61.5	-61.5
374+00.00	375+00.00	0.0	44.6	0.0	70.7	-70.7
375+00.00	376+00.00	0.0	48.9	0.0	86.3	-86.3
376+00.00	377+00.00	0.0	53.5	0.0	101.2	-101.2
377+00.00	378+00.00	0.0	53.9	0.0	105.3	-105.3
378+00.00	379+00.00	0.0	52.7	0.0	108.6	-108.6
379+00.00	380+00.00	0.0	48.9	0.0	97.3	-97.3
380+00.00	381+00.00	0.0	47.3	0.0	90.6	-90.6
381+00.00	382+00.00	0.0	45.9	0.0	83.2	-83.2
382+00.00	383+00.00	0.0	41.7	0.0	67.0	-67.0
383+00.00	384+00.00	0.0	38.9	0.0	56.0	-56.0
384+00.00	385+00.00	0.0	41.1	0.0	64.2	-64.2
385+00.00	386+00.00	0.0	42.1	0.0	69.3	-69.3
386+00.00	387+00.00	0.0	38.6	0.0	53.4	-53.4
387+00.00	388+00.00	0.0	34.8	0.0	44.0	-44.0
388+00.00	389+00.00	0.0	32.5	0.0	42.0	-42.0
389+00.00	390+00.00	0.0	33.9	0.0	43.3	-43.3
390+00.00	391+00.00	2.9	29.7	2.4	39.8	-37.4
391+00.00	391+24.41	1.3	6.0	1.1	8.8	-7.6
391+24.41	391+64.74	1.1	5.2	0.9	7.8	-6.9
391+64.74	END	0.0	0.0	0.0	0.0	0.0
	SUBTOTAL	5.3	2824.7	4.5	4466.8	-4462.4
I-55 NOISE WALL 3 - AFTER SUNNLYLAND DRAIN						
392+14.74	392+51.00	1.9	4.6	1.6	3.7	-2.0
392+51.00	393+00.00	4.5	12.0	3.8	11.0	-7.2
393+00.00	394+00.00	3.8	28.4	3.2	28.9	-25.7
394+00.00	395+00.00	0.0	31.0	0.0	31.5	-31.5
395+00.00	396+00.00	0.0	28.5	0.0	27.0	-27.0
396+00.00	397+00.00	4.3	47.6	3.7	28.2	-24.5
397+00.00	398+00.00	13.0	65.7	11.1	30.7	-19.6
398+00.00	399+00.00	11.9	65.4	10.1	31.2	-21.1
399+00.00	400+00.00	3.2	64.7	2.8	35.8	-33.1
400+00.00	401+00.00	0.0	47.9	0.0	36.9	-36.9
401+00.00	402+00.00	0.0	31.0	0.0	29.9	-29.9
402+00.00	403+00.00	0.0	29.3	0.0	25.6	-25.6
403+00.00	404+00.00	0.0	31.3	0.0	33.6	-33.6
404+00.00	405+00.00	0.0	34.0	0.0	41.8	-41.8
405+00.00	406+00.00	0.0	40.1	0.0	55.7	-55.7
406+00.00	407+00.00	0.0	34.7	0.0	42.1	-42.1
407+00.00	408+00.00	0.0	52.4	0.0	97.9	-97.9
408+00.00	408+26.26	0.0	0.0	0.0	0.0	0.0
408+26.26	END	0.0	0.0	0.0	0.0	0.0
	SUBTOTAL	42.7	648.7	36.3	591.7	-555.4
I-55 NOISE WALL 4						
492+18.81	492+35.00	0.0	2.5	0.0	4.0	-4.0
492+35.00	493+00.00	0.0	27.3	0.0	32.4	-32.4
493+00.00	494+00.00	0.0	40.8	0.0	36.2	-36.2
494+00.00	495+00.00	0.0	34.3	0.0	25.4	-25.4

STA FROM	TO STA	20200100 EARTH EXCAVATION	20201200 REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU YD	CU YD	CU YD	CU YD	CU YD
I-55 NOISE WALL 4 (CONTINUED)						
495+00.00	496+00.00	2.9	52.9	2.4	28.4	-26.0
496+00.00	497+00.00	5.4	65.7	4.5	26.7	-22.2
497+00.00	498+00.00	5.1	65.1	4.3	25.7	-21.4
498+00.00	499+00.00	10.3	60.3	8.7	24.3	-15.6
499+00.00	500+00.00	7.6	53.3	6.5	31.6	-25.1
500+00.00	501+00.00	0.0	42.6	0.0	33.6	-33.6
501+00.00	502+00.00	0.0	36.3	0.0	30.1	-30.1
502+00.00	503+00.00	0.0	34.6	0.0	35.5	-35.5
503+00.00	504+00.00	0.0	32.1	0.0	37.6	-37.6
504+00.00	505+00.00	0.4	44.1	0.3	58.0	-57.7
505+00.00	506+00.00	0.4	43.8	0.3	54.9	-54.5
506+00.00	507+00.00	0.0	25.4	0.0	19.4	-19.4
507+00.00	508+00.00	0.0	19.6	0.0	11.2	-11.2
508+00.00	508+50.00	0.0	11.2	0.0	8.5	-8.5
508+50.00	508+58.51	0.0	1.0	0.0	0.8	-0.8
508+58.51	END	0.0	0.0	0.0	0.0	0.0
	SUBTOTAL	32.0	693.0	27.2	524.5	-497.2
I-55 NOISE WALL 5						
509+96.85	510+00.00	0.0	0.5	0.0	0.3	-0.3
510+00.00	511+00.00	0.0	34.3	0.0	37.2	-37.2
511+00.00	512+00.00	0.0	51.9	0.0	82.9	-82.9
512+00.00	513+00.00	0.4	65.2	0.3	103.9	-103.5
513+00.00	514+00.00	0.4	49.1	0.3	66.0	-65.7
514+00.00	515+00.00	0.0	31.3	0.0	33.9	-33.9
515+00.00	516+00.00	0.0	29.8	0.0	33.5	-33.5
516+00.00	517+00.00	3.3	36.4	2.8	27.6	-24.8
517+00.00	518+00.00	10.6	44.9	9.1	22.3	-13.3
518+00.00	519+00.00	13.9	54.0	11.9	31.6	-19.7
519+00.00	520+00.00	6.6	45.9	5.6	40.2	-34.6
520+00.00	521+00.00	0.0	29.9	0.0	35.6	-35.6
521+00.00	522+00.00	0.0	30.0	0.0	33.8	-33.8
522+00.00	523+00.00	0.0	32.6	0.0	43.7	-43.7
523+00.00	524+00.00	0.0	34.6	0.0	51.7	-51.7
524+00.00	525+00.00	0.0	35.1	0.0	49.3	-49.3
525+00.00	526+00.00	0.1	37.5	0.1	45.9	-45.8
526+00.00	527+00.00	0.4	39.5	0.4	38.6	-38.3
527+00.00	528+00.00	0.9	37.2	0.8	29.8	-29.0
528+00.00	529+00.00	1.4	35.8	1.2	27.4	-26.3
529+00.00	530+00.00	0.9	37.5	0.8	31.1	-30.3
530+00.00	531+00.00	0.7	36.8	0.6	31.3	-30.7
531+00.00	532+00.00	0.7	35.4	0.6	28.9	-28.3

CONTINUED ON SHEET 12

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55 (BLACK ROAD TO U.S. ROUTE 30)
NOISE ABATEMENT WALLS

SCHEDULE OF QUANTITIES
I

SCALE: N.T.S. DRAWN BY AG
DATE 02/06/09 CHECKED BY DDH

TENG
TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
CHICAGO, ILLINOIS

PLOT DATE = $DATE$
FILE NAME = $FILEL$
PLOT SCALE = $SCALE$
USER NAME = $USER$
..\B2491A08.DGN,..\SG121A002.DGN,..\SG121A002.DGN,..\SG121A002.DGN
2-04-2009,16:32:25 SHAFIAJF S:\DOCUMENT\02381E01\CIVIL\DGN\SG121A004.SHT