

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (I&2) I-11	WILL	176	12
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

**EARTHWORK SCHEDULE OF QUANTITIES**

CONTINUED FROM SHEET 11

STA FROM	TO STA	20200100 EARTH EXCAVATION	20201200 REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU YD	CU YD	CU YD	CU YD	CU YD
I-55 NOISE WALL 5 (CONTINUED)						
532+00.00	533+00.00	0.5	35.2	0.5	28.0	-27.6
533+00.00	534+00.00	0.7	37.6	0.6	33.6	-33.0
534+00.00	535+00.00	1.1	41.6	1.0	43.0	-42.0
535+00.00	536+00.00	0.9	44.7	0.7	44.0	-43.3
536+00.00	537+00.00	1.2	43.1	1.0	36.2	-35.1
537+00.00	538+00.00	1.4	39.4	1.2	34.5	-33.3
538+00.00	539+00.00	1.4	38.9	1.1	37.1	-36.0
539+00.00	540+00.00	2.2	36.3	1.9	27.5	-25.6
540+00.00	541+00.00	2.0	36.8	1.7	27.4	-25.7
541+00.00	542+00.00	1.7	40.6	1.4	36.4	-34.9
542+00.00	543+00.00	1.9	44.0	1.6	46.7	-45.1
543+00.00	544+00.00	1.9	45.3	1.6	56.3	-54.7
544+00.00	545+00.00	1.5	43.4	1.2	53.9	-52.6
545+00.00	546+00.00	1.1	42.9	1.0	53.9	-53.0
546+00.00	547+00.00	1.0	43.2	0.8	54.3	-53.5
547+00.00	548+00.00	0.7	42.3	0.6	51.8	-51.2
548+00.00	549+00.00	0.8	41.2	0.6	46.2	-45.5
549+00.00	550+00.00	1.1	41.3	0.9	43.1	-42.2
550+00.00	551+00.00	1.6	40.5	1.4	40.4	-39.0
551+00.00	552+00.00	2.2	40.0	1.9	38.2	-36.3
552+00.00	553+00.00	2.3	38.9	1.9	36.3	-34.4
553+00.00	554+00.00	2.4	36.0	2.1	28.6	-26.6
554+00.00	555+00.00	2.5	37.1	2.1	31.1	-29.0
555+00.00	556+00.00	2.0	42.5	1.7	44.8	-43.1
556+00.00	557+00.00	1.5	44.8	1.3	53.2	-51.9
557+00.00	558+00.00	1.5	43.8	1.3	51.8	-50.5
558+00.00	559+00.00	2.0	42.6	1.7	44.9	-43.2
559+00.00	560+00.00	2.1	40.0	1.8	36.1	-34.3
560+00.00	561+00.00	2.2	37.7	1.9	32.0	-30.1
561+00.00	562+00.00	2.5	36.9	2.1	28.6	-26.5
562+00.00	563+00.00	2.3	37.2	1.9	25.8	-23.9
563+00.00	564+00.00	2.6	38.2	2.2	29.3	-27.1
564+00.00	565+00.00	2.7	39.8	2.3	38.3	-36.0
565+00.00	566+00.00	2.2	40.5	1.8	40.8	-38.9
566+00.00	567+00.00	1.1	35.7	0.9	43.6	-42.7
567+00.00	568+00.00	0.0	48.7	0.0	56.6	-56.6
568+00.00	569+00.00	0.6	60.0	0.5	68.1	-67.6
569+00.00	570+00.00	2.0	56.6	1.7	63.8	-62.1
570+00.00	571+00.00	1.4	46.1	1.2	49.9	-48.7
571+00.00	572+00.00	0.0	41.7	0.0	55.5	-55.5
572+00.00	573+00.00	0.4	52.3	0.3	73.6	-73.3
573+00.00	574+00.00	1.5	61.2	1.2	83.1	-81.9
574+00.00	575+00.00	4.1	67.3	3.5	83.8	-80.3
575+00.00	576+00.00	4.4	65.3	3.7	84.2	-80.5
576+00.00	577+00.00	3.7	46.0	3.2	64.1	-61.0
577+00.00	578+00.00	4.6	27.7	3.9	42.2	-38.3
578+00.00	579+00.00	4.7	25.3	4.0	35.8	-31.9
579+00.00	580+00.00	4.9	34.8	4.2	56.5	-52.3
580+00.00	581+00.00	2.4	34.3	2.1	49.1	-47.0

STA FROM	TO STA	20200100 EARTH EXCAVATION	20201200 REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL	EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
		CU YD	CU YD	CU YD	CU YD	CU YD
I-55 NOISE WALL 5 (CONTINUED)						
581+00.00	582+00.00	0.0	19.4	0.0	9.3	-9.3
582+00.00	583+00.00	0.0	19.7	0.0	8.5	-8.5
583+00.00	584+00.00	0.1	19.6	0.1	7.7	-7.6
584+00.00	585+00.00	0.1	16.7	0.1	3.7	-3.5
585+00.00	586+00.00	0.0	16.7	0.0	4.9	-4.9
586+00.00	586+03.08	0.0	0.3	0.0	0.1	-0.1
586+03.08	END	0.0	0.0	0.0	0.0	0.0
SUBTOTAL		134.1	3035.1	114.0	3224.8	-3110.9
TOTAL		214.0	7201.4	181.9	8807.8	-8625.8

PLOT DATE = #DATE#  
 FILE NAME = #FILE#  
 PLOT SCALE = #SCALE#  
 USER NAME = #USER#  
 ..\BPP\14801.DGN...SCE\14802.DGN...SCE\14803.DGN...SCE\14804.DGN...SCE\14805.SHT  
 2-07-2009, 10:36:58 SHIP\TAUF 38 DOCUMENT\02361601\CIVIL\14805.DGN\14805.SHT

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 FAI ROUTE 55 (BLACK ROAD TO U.S. ROUTE 30)  
 NOISE ABATEMENT WALLS

**SCHEDULE OF QUANTITIES  
 II**

SCALE: N.T.S. DRAWN BY AG  
 DATE 02/06/09 CHECKED BY DDH

**TENG**  
 TENG & ASSOCIATES, INC.  
 ENGINEERS/ARCHITECTS/PLANNERS  
 CHICAGO, ILLINOIS