

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) I-II	WILL	176	15
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTINUED FROM PREVIOUS SHEET				TOTAL
LOCATION	STA	DESCRIPTION	Subtotals	FOOT
44000500 COMBINATION CURB AND GUTTER REMOVAL				924
FRONTAGE ROAD 3				
	401+93.00	AT NEW CATCH BASIN	12	
	403+21.00	AT NEW CATCH BASIN	12	
	404+49.00	AT NEW CATCH BASIN	12	
FRONTAGE ROAD 4				
	492+82.00	AT NEW CATCH BASIN	12	
	494+01.00	AT NEW CATCH BASIN	12	
	495+10.00	AT NEW CATCH BASIN	12	
	495+82.60	AT EX CURB CUT	5	
	496+19.00	AT NEW CATCH BASIN	12	
	497+28.00	AT NEW CATCH BASIN	12	
	498+45.00	AT NEW CATCH BASIN	12	
	499+00.00	AT CULVERT CROSSING	10	
	499+57.00	AT NEW CATCH BASIN	12	
	500+67.00	AT NEW CATCH BASIN	12	
	501+82.00	AT NEW CATCH BASIN	12	
	502+92.00	AT NEW CATCH BASIN	12	
	504+32.00	AT NEW CATCH BASIN	12	
	505+07.00	AT NEW CATCH BASIN	12	
FRONTAGE ROAD 5				
	513+78.00	AT NEW CATCH BASIN	12	
	515+60.00	AT NEW CATCH BASIN	12	
	516+41.00	AT NEW CATCH BASIN	12	
	519+28.00	AT NEW CATCH BASIN	12	
	522+35.00	AT NEW CATCH BASIN	12	
	524+81.00	AT NEW CATCH BASIN	12	
	567+06.30	AT EX CURB CUT	5	
	568+00.00	AT NEW CATCH BASIN	12	
	569+36.00	AT NEW CATCH BASIN	12	
	570+61.00	AT NEW CATCH BASIN	12	
	571+36.00	AT NEW CATCH BASIN	12	
	572+36.00	AT NEW CATCH BASIN	12	
	573+86.00	AT NEW CATCH BASIN	12	
	575+11.00	AT CULVERT CROSSING AND NEW CATCH BASIN	28	

CONTINUED FROM PREVIOUS COLUMN		TOTAL
LOCATION	Subtotals	FOOT
334+65.00 12.0		
335+94.00 12.0		
337+19.00 12.0		
338+34.00 12.0		
339+68.00 12.0		
342+11.00 12.0		
344+51.00 12.0		
346+66.00 12.0		
348+73.00 12.0		
350+01.00 12.0		
352+99.00 12.0		
355+57.00 12.0		
356+86.00 12.0		
358+14.00 12.0		
359+86.00 12.0		
361+93.00 12.0		
365+51.00 12.0		
366+78.00 12.0		
368+70.00 12.0		
370+71.00 12.0		
371+78.00 12.0		
373+28.00 12.0		
374+78.00 12.0		
376+28.00 12.0		
377+78.00 12.0		
378+78.00 12.0		
379+78.00 12.0		
380+95.00 12.0		
382+24.00 12.0		
383+53.00 12.0		
384+81.00 12.0		
386+10.00 12.0		
387+39.00 12.0		
388+68.00 12.0		
389+96.00 12.0		
395+49.00 12.0		
396+78.00 12.0		
398+07.00 12.0		
399+36.00 12.0		
400+65.00 12.0		
401+93.00 12.0		
403+21.00 12.0		
404+49.00 12.0		

60605000 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24				TOTAL
FROM STA	TO STA	Subtotals	FOOT	
FRONTAGE ROAD 5				
REPLACE C&G				5
	567+06.30		12	
	568+00.00		12	
	569+36.00		12	
	570+61.00		12	
	571+36.00		12	
	572+36.00		12	
	573+86.00		12	
	574+89.00		28	
NEW C&G				
	576+35.00	576+45.44	10.44	
	576+45.44	578+01.57	156.13	
	578+01.57	580+00.00	198.43	

63200310 GUARDRAIL REMOVAL				TOTAL
LOCATION	FROM STA	TO STA	Subtotals	FOOT
FRONTAGE ROAD 3				
	330+69.66	331+09.97	40.3	
	351+73.61	352+00.00	26.4	
	355+45.97	355+74.27	28.3	
	366+98.94	367+52.68	53.7	
	386+45.86	386+76.01	30.2	

63302700 REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 6				TOTAL
LOCATION	FROM STA	TO STA	Subtotals	EACH
Frontage Road 3 @ Sunnlyland Drain, South End				1
Frontage Road 3 @ Sunnlyland Drain, North End				1

66400105 CHAIN LINK FENCE, 4'						TOTAL
LOCATION	FROM STA	OFFSET	TO STA	OFFSET	Subtotals	FOOT
FRONTAGE ROAD 3	406+60.38	-18.00	406+60.38	-36.60	18.6	
FRONTAGE ROAD 5	511+50.00	16.00	511+50.00	36.27	20.3	
FRONTAGE ROAD 5	580+00.00	18.00	580+00.00	25.18	7.2	
FRONTAGE ROAD 5	580+00.00	18.00	582+20.00	18.00	220.0	

66410300 CHAIN LINK FENCE REMOVAL						TOTAL
LOCATION	FROM STA	TO STA	Subtotals	FOOT		
FRONTAGE ROAD 3 357+58.00 406+60.00						4902.0
FRONTAGE ROAD 5 511+50.00 582+20.00						7070.0

66500105 WOVEN WIRE FENCE, 4'						TOTAL
LOCATION	FROM STA	OFFSET	TO STA	OFFSET	Subtotals	FOOT
FRONTAGE ROAD 3	323+70.00	-19.50	325+00.00	-18.00	130.0	
FRONTAGE ROAD 4	492+01.50	17.90	492+35.00	16.50	33.5	
FRONTAGE ROAD 4	505+80.00	16.50	505+80.00	32.76	16.3	

66502300 WOVEN WIRE FENCE REMOVAL				TOTAL
LOCATION	FROM STA	TO STA	Subtotals	FOOT
FRONTAGE ROAD 3 323+70.00 357+58.00				3388.0
FRONTAGE ROAD 4 492+01.50 505+80.00				1378.5

70400100 TEMPORARY CONCRETE BARRIER				TOTAL
LOCATION	FROM STA	TO STA	Subtotals	FOOT
FRONTAGE ROAD 3 @ SUNNLYLAND DRAIN 390+76.00 393+12.50				236.5

Checked:
Date:

X0301423 NOISE ABATEMENT WALL, GROUND MOUNTED					TOTAL
FROM STA	TO STA	LENGTH FT	Subtotals	SO FT	
FRONTAGE RD 3 / NOISE WALL 3					
	324+70.00	327+00.00	230.00		3029
	327+00.00	342+00.00	1500.00		23361
	342+00.00	357+00.00	1500.00		17620
	357+00.00	372+00.00	1500.00		21693
	372+00.00	387+00.00	1500.00		22999
	387+00.00	389+71.30	271.30		3341
	389+71.30	390+71.31	100.01		1284
	390+71.31	391+64.74	93.43		1275
	392+14.74	393+08.58	93.84		1247
	393+08.58	394+08.58	100.00		1247
	394+08.58	402+00.00	791.42		6670
	402+00.00	405+90.09	390.09		3213
	405+90.09	407+29.08	138.99		1223
	407+29.08	408+00.00	70.92		707

FRONTAGE RD 4 / NOISE WALL 4					TOTAL
FROM STA	TO STA	LENGTH FT	Subtotals	SO FT	
	492+35.00	493+29.52	94.52		1251
	493+29.52	502+00.00	870.48		14026
	502+00.00	504+75.90	275.90		4489
	504+75.90	506+90.51	214.61		3651
	506+90.51	508+50.00	159.49		2458

FRONTAGE RD 5 / NOISE WALL 5					TOTAL
FROM STA	TO STA	LENGTH FT	Subtotals	SO FT	
	510+00.00	512+61.67	261.67		4852
	512+61.67	517+00.00	438.33		9170
	517+00.00	518+00.00	100.00		2084
	518+00.00	519+00.00	100.00		2003
	519+00.00	525+31.74	631.74		12667
	525+31.74	526+32.00	100.26		2007
	526+32.00	532+00.00	568.00		11297
	532+00.00	547+00.00	1500.00		29533
	547+00.00	556+16.22	916.22		18202
	556+16.22	562+00.00	583.78		11753
	562+00.00	565+87.00	387.00		7837
	565+87.00	566+87.21	100.21		1985
	566+87.21	575+51.95	864.74		16893
	575+51.95	577+00.00	148.05		2974
	577+00.00	586+00.00	900.00		14349

TOTAL WALL LENGTH = 17495.00 17598.25

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55 (BLACK ROAD TO U.S. ROUTE 30)
NOISE ABATEMENT WALLS

SCHEDULE OF QUANTITIES
V

SCALE: N.T.S. DRAWN BY JFS
DATE 04/21/09 CHECKED BY DDH

TENG
TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
CHICAGO, ILLINOIS

PLOT DATE = 04/21/09
 FILE NAME = #FILES#
 PLOT SCALE = #SCALE#
 USER NAME = #USER#
 .\BROKER\BROKER.DWG ..\SEC21407.DWG ..\SEC21407.DWG ..\SEC21407.DWG ..\SEC21407.DWG ..\SEC21407.DWG ..\SEC21407.DWG ..\SEC21407.DWG ..\SEC21407.DWG ..\SEC21407.DWG ..\SEC21407.DWG
 4-21-2009 11:11:07

CONTINUED ON NEXT COLUMN