

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) 1-12	WILL	147	5
STA. 610+25.64		TO STA. 767+00.00		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
		S00-02 OF 3		

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	NOISE WALL			
				Sta.610+25.64 to Sta. 767+00.00	Sta.610+25.64 to Sta. 767+00.00	100% State Non-Participating	
				I000	Y220		
* 63000005	STEEL PLATE BEAM GUARDRAIL, TYPE B	FOOT	4,075.0	4,075.0			
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2			
<del>* 63100085</del>	<del>TRAFFIC BARRIER TERMINAL, TYPE 6</del>	<del>EACH</del>	<del>1</del>	<del>1</del>			
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	5	5			
63200310	GUARDRAIL REMOVAL	FOOT	3,723	3,723			
63700805	CONCRETE BARRIER TRANSITION	FOOT	75	75			
66410800	CHAIN LINK GATES REMOVAL	EACH	1	1			
66500105	WOVEN WIRE FENCE, 4'	FOOT	190	190			
66502000	WOVEN WIRE GATES, 4' X 24' DOUBLE	EACH	2	2			
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	10,136	10,136			
67100100	MOBILIZATION	L SUM	1	1			
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1			
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	16	16			
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	3,900	3,900			
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	456	456			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,604	1,604			
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	2	2			
* 72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	1	1			
* 72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	3	3			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	119	119			
* 78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	975	975			
* 78100300	REPLACEMENT REFLECTOR	EACH	86	86			
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	49	49			
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	130	130			
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6	6			
78300100	PAVEMENT MARKING REMOVAL	SQ FT	406	406			
* A2000114	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	10	10			
* A2002020	TREE, AESCULUS GLABRA (OHIO BUCKEYE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5	5			
* A2002920	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5	5			
* A2006514	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	10	10			
* A2006714	TREE, QUERCUS MACROCARPA (BUR OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	30	30			
* C2C06024	SHRUB, RHUS TYPHINA (STAGHORN SUMAC), 2' HEIGHT, CONTAINER	EACH	80	80			
* D2001560	EVERGREEN, JUNIPERUS VIRGINIANA (EASTERN RED CEDAR), 5' HEIGHT, BALLED AND BURLAPPED	EACH	60	60			
* E20200G1	VINE-PARTHENOCISSUS QUINQUEFOLIA (VIRGINIA CREEPER), 1-GALLON POT	EACH	4,822	4,822			
* K0036120	MULCH PLACEMENT 4"	SQ YD	1,540	1,540			
X0301423	NOISE ABATEMENT WALL, GROUND MOUNTED	SQ FT	131,510		131,510		

\* Specialty Items

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 FAI ROUTE 55  
 US 30 (PLAINFIELD ROAD) TO WEBER ROAD  
 SUMMARY OF QUANTITIES

SCALE: NONE  
 DATE: 2-06-09  
 DRAWN BY: MMS  
 CHECKED BY: DM

