

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (I&2) I-12	WILL	147	65
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PIPE SCHEDULE

PIPE NUMBER	SHEET NUMBER	UPSTREAM STRUCTURE	DOWNSTREAM STRUCTURE	TRENCH BACKFILL (CU YD)	STORM SEWER (FEET)			PIPE CULVERT (FEET)	PIPE SLOPE
					CLASS 4		CLASS 3	CLASS A	
					TYPE 1	TYPE 2		TYPE 1	
					12"	12"	18"	12"	
WALL 7									
805	52	805	806	0			11		0.50%
810	52	810	811	0			13		0.50%
815	52	815	816	0			12		0.50%
820	52	820	821	0			12		0.50%
WALL 8									
601	54	601	602	0	7				0.50%
605	54	605	606	0	9				0.78%
WALL 9A									
607	55	607	608	15.5				66	0.74%
WALL 9B									
825	55	825	826	0		15			0.50%
830	55	830	831	0		15			0.50%
835	55	835	836	0		13			0.50%
840	55	840	841	0			14		0.50%
845	57	845	846	0			15		0.50%
850	57	850	851	0			17		0.50%
855	58	855	856	0			12		0.50%
860	58	860	861	0			14		0.50%
865	58	865	870	0		10			0.50%
870	58	870	871	0			15		0.40%
875	58	875	870	0		10			0.50%
WALL 9C									
611	59	611	612	0	6				0.50%
616	59	616	617	0	6				1.00%
621	61	621	622	0	70				0.50%
626	61	626	627	0	70				0.50%
TOTAL				15.5	168	75	123	66	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 FAI ROUTE 55  
 US 30 (PLAINFIELD ROAD) TO WEBER ROAD

DRAINAGE SCHEDULE-  
 PIPES

SCALE: NTS  
 DATE: 2-06-09

DRAWN BY: MMS  
 CHECKED BY: DM



FINAL