

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) I-12	WILL	147	66
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STRUCTURE SCHEDULE

STRUCTURE NUMBER	SHEET NUMBER	LOCATION			CATCH BASIN AND CONVEX GRATE (SPECIAL)	PRECAST F.E.S.			RIM ELEV	INVERT ELEVATIONS			
		STATION	OFFSET (FT)	SIDE		CATCH BASINS				NORTH	SOUTH	EAST	WEST
						TYPE A	TYPE 20 FRAME & GRATE	4 FT					
					12"	18"							
WALL 7													
805	52	622+09.00	66.81	RT				1	616.70			612.20	
806	52	622+09.00	77.81	RT			1					612.15	
810	52	624+46.00	62.63	RT				1	610.78			607.43	
811	52	624+46.00	62.63	RT			1					607.37	
815	52	626+98.00	61.50	RT				1	607.30			603.80	
816	52	626+98.00	61.50	RT			1					603.74	
820	52	628+76.00	61.50	RT				1	605.59			601.12	
821	52	628+76.00	73.50	RT		1						601.06	
WALL 8													
601	54	670+00.00	90.25	RT	1				610.06			608.26	
602	54	670+00.00	82.00	RT		1						608.22	
605	54	676+00.00	90.25	RT	1				610.48			608.27	
606	54	676+00.00	80.00	RT		1						608.20	
WALL 9A													
607	55	686+92.00	90.00	RT		1				613.81			
608	55	686+26.00	90.00	RT		1					613.32		
WALL 9B													
825	55	689+06.00	61.50	RT				1	616.87			614.31	
826	55	689+06.00	76.50	RT		1						614.24	
830	55	691+46.00	61.50	RT				1	617.72			614.78	
831	55	691+46.00	76.50	RT		1						614.71	
835	55	693+98.00	61.50	RT				1	618.65			614.15	
836	55	693+98.00	74.50	RT		1						614.09	
840	55	696+50.00	61.50	RT				1	620.71			616.21	
841	55	696+50.00	61.50	RT			1					616.14	
845	57	699+02.00	61.50	RT				1	623.82			619.32	
846	57	699+02.00	76.50	RT			1					619.25	
850	57	701+42.00	61.50	RT				1	627.91			623.41	
851	57	701+42.00	78.50	RT			1					623.33	
855	58	721+55.00	61.50	RT				1	624.47			619.97	
856	58	721+55.00	73.50	RT			1					619.92	
860	58	724+06.00	61.50	RT				1	621.55			617.05	
861	58	724+06.00	75.50	RT			1					616.99	
865	58	726+34.00	61.50	RT				1	620.55	616.87			
870	58	726+46.00	61.50	RT				1	620.55	616.82	616.82	616.82	
871	58	726+46.00	76.50	RT			1					616.76	
875	58	726+58.00	61.50	RT				1	620.55		616.87		
WALL 9C													
611	59	729+00.00	90.25	RT	1				618.71			616.17	
612	59	729+00.00	83.00	RT		1						616.14	
616	59	733+00.00	90.25	RT	1				619.68			617.78	
617	59	733+00.00	83.00	RT		1						617.72	
621	61	747+00.00	142.25	RT	1				622.91			620.56	
622	61	747+00.00	71.00	RT		1						620.21	
626	61	752+81.00	142.25	RT	1				622.65			621.26	
627	61	752+81.00	71.00	RT		1						621.00	
TOTAL					6	12	9	15					

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI ROUTE 55
 US 30 (PLAINFIELD ROAD) TO WEBER ROAD
 DRAINAGE SCHEDULE -
 STRUCTURES

SCALE: NTS
 DATE: 6-12-09

DRAWN BY: MMS
 CHECKED BY: DM



FINAL