

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

WORK POINTS & ELEVATION

Station	Offset Right	Theoretical Top/wall	Theoretical Bottom/wall	Proposed Grade Elev.	Ultimate Barrier Toe/Elev.	Proposed Barrier Toe/Elev.
611+35.00	67.50	657.92	635.57	637.57	644.19	638.83
611+50.00	67.50	657.85	635.36	637.36	644.11	638.71
612+00.00	67.50	657.60	634.67	636.67	643.83	638.29
612+50.00	67.50	657.35	633.97	635.97	643.35	637.83
613+00.00	67.50	656.67	633.28	635.28	642.87	637.37
613+50.00	67.50	655.99	632.50	634.50	642.19	636.59
614+00.00	67.50	655.31	631.72	633.72	641.51	635.80
614+50.00	67.50	654.63	630.61	632.61	640.63	634.91
615+00.00	67.50	653.49	629.51	631.51	639.74	634.02
615+50.00	67.50	652.35	628.41	630.41	638.69	632.98
616+00.00	67.50	651.21	627.31	629.31	637.63	631.94
616+50.00	67.50	650.07	626.10	628.10	636.07	630.73
617+00.00	67.50	648.87	624.89	626.89	634.50	629.52
617+50.00	67.50	647.66	623.68	625.68	633.42	628.26
618+00.00	67.50	646.46	622.47	624.47	632.34	626.99
618+50.00	67.50	645.25	621.27	623.27	631.25	625.84
619+00.00	67.50	644.13	620.07	622.07	630.17	624.68
619+50.00	67.50	643.01	618.85	620.85	629.07	623.42
620+00.00	67.50	641.88	617.63	619.63	627.97	622.16

WORK POINTS & ELEVATION

Station	Offset Right	Theoretical Top/wall	Theoretical Bottom/wall	Proposed Grade Elev.	Ultimate Barrier Toe/Elev.	Proposed Barrier Toe/Elev.
620+50.00	67.50	640.76	617.02	619.02	626.76	620.83
621+00.00	67.42	639.96	616.41	618.41	625.55	619.50
621+50.00	67.12	638.45	614.78	616.78	624.38	618.10
622+00.00	66.81	637.29	613.15	615.15	623.22	616.70
622+50.00	66.20	636.13	611.77	613.77	622.13	615.38
623+00.00	65.59	635.04	610.38	612.38	621.04	614.05
623+50.00	64.68	633.95	609.33	611.33	619.96	612.87
624+00.00	63.77	632.86	608.27	610.27	618.88	611.68
624+50.00	62.48	631.77	607.54	609.54	617.77	610.10
625+00.00	61.50	630.55	606.80	608.80	616.65	609.88
625+50.00	61.50	629.32	606.02	608.02	615.38	609.10
626+00.00	61.50	628.10	605.24	607.24	614.10	608.32
626+50.00	61.50	626.87	604.61	606.61	612.87	607.81
627+00.00	61.50	625.81	603.99	605.99	611.64	607.30
627+50.00	61.50	624.75	603.70	605.70	610.55	606.97
628+00.00	61.50	623.69	603.41	605.41	609.46	606.63
628+50.00	61.50	622.63	603.16	605.16	608.63	606.28
629+00.00	61.50	621.93	602.90	604.90	607.80	605.93
629+51.00	61.50	621.22	601.28	603.28	607.22	605.92

T:\16817A\Struct\Cadd\Pre-Final\Noise wall\Wall 7\099W024-60B04-003.dgn
12-JUN-2009 16:19

DESIGNED	P. LOPEZ
CHECKED	J. GRAINAWI
DRAWN	D. C. PATEL
CHECKED	J. GRAINAWI

GENERAL DATA
STRUCTURE NO. 099-W024

SHEET NO. 3 7 SHEETS	F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	55	99 (1&2) I-12	WILL	147	85
			CONTRACT NO.	60B04	
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT					

