

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

WORK POINTS & ELEVATION

Station	Offset Right	Theoretical Top/wall	Theoretical Bottom/wall	Proposed Grade Elev.	Ultimate Barrier Toe/Elev.	Proposed Barrier Toe/Elev.
689+00.00	61.50	632.54	614.07	616.07	617.50	616.87
689+50.00	61.50	632.56	614.23	616.23	617.69	617.03
690+00.00	61.50	632.57	614.38	616.38	617.87	617.18
690+50.00	61.50	632.59	614.57	616.57	618.06	617.42
691+00.00	61.50	632.60	614.60	616.60	618.25	617.65
691+50.00	61.50	632.70	614.64	616.64	618.43	617.72
692+00.00	61.50	632.79	614.69	616.69	618.62	617.79
692+50.00	61.50	632.89	614.77	616.77	618.81	617.96
693+00.00	61.50	632.99	614.85	616.85	618.99	618.14
693+50.00	61.50	633.18	615.00	617.00	619.18	618.39
694+00.00	61.50	633.36	615.15	617.15	619.36	618.65
694+50.00	61.50	633.55	615.37	617.37	619.55	619.05
695+00.00	61.50	633.74	615.59	617.59	619.74	619.44
695+50.00	61.50	634.12	616.02	618.02	619.97	619.83
696+00.00	61.50	634.50	616.45	618.45	620.20	620.21
696+50.00	61.50	634.88	616.86	618.86	620.60	620.71
697+00.00	61.50	635.26	617.26	619.26	621.00	621.21
697+50.00	61.50	635.85	617.70	619.70	621.57	621.77
698+00.00	61.50	636.43	618.13	620.13	622.14	622.33
698+50.00	61.50	637.02	618.64	620.64	622.87	623.07
699+00.00	61.50	637.60	619.15	621.15	623.60	623.82
699+50.00	61.50	638.38	619.72	621.72	624.38	624.54
700+00.00	61.50	639.16	620.29	622.29	625.16	625.26
700+50.00	61.50	639.94	621.17	623.17	625.94	626.12
701+00.00	61.50	640.72	622.05	624.05	626.72	626.98
701+50.00	61.50	641.50	622.83	624.83	627.50	627.91
702+00.00	61.50	642.28	623.61	625.61	628.28	628.84
702+50.00	61.50	643.06	624.55	626.55	629.06	629.85
703+00.00	61.50	643.84	625.50	627.50	629.84	630.85
703+50.00	61.50	644.69	626.54	628.54	630.62	631.87
704+00.00	61.50	645.54	627.58	629.58	631.40	632.88
704+50.00	61.50	646.38	628.40	630.40	632.18	633.81
705+00.00	61.50	647.23	629.23	631.23	632.96	634.74
705+50.00	61.50	648.15	630.29	632.29	633.74	635.73
706+00.00	61.50	649.06	631.34	633.34	634.52	636.72
706+50.00	61.50	649.98	632.12	634.12	635.28	637.45
707+00.00	61.50	650.89	632.89	634.89	636.03	638.17
707+50.00	61.50	651.98	633.33	635.33	636.62	638.66
708+00.00	61.50	653.07	633.78	635.78	637.20	639.15
708+20.62	61.50	653.52	634.49	636.49	637.40	639.35
708+50.00	59.55	654.16	635.51	637.51	637.69	639.62
709+00.00	56.22	655.25	637.25	639.25	638.18	640.08

WORK POINTS & ELEVATION

Station	Offset Right	Theoretical Top/wall	Theoretical Bottom/wall	Proposed Grade Elev.	Ultimate Barrier Toe/Elev.	Proposed Barrier Toe/Elev.
712+00.00	58.00	654.15	636.55	638.55	638.07	640.26
712+50.00	61.50	653.02	635.22	637.22	637.60	639.90
713+00.00	61.50	651.89	633.89	635.89	637.13	639.54
713+50.00	61.50	651.34	633.64	635.64	636.55	639.11
714+00.00	61.50	650.78	633.38	635.38	635.98	638.67
714+50.00	61.50	650.23	632.52	634.52	635.38	638.04
715+00.00	61.50	649.67	631.67	633.67	634.78	637.41
715+50.00	61.50	648.85	630.65	632.65	634.19	636.50
716+00.00	61.50	648.03	629.63	631.63	633.59	635.59
716+50.00	61.50	647.21	628.68	630.68	632.99	634.52
717+00.00	61.50	646.39	627.73	629.73	632.39	633.45
717+50.00	61.50	646.29	626.79	628.79	631.80	632.39
718+00.00	61.50	646.19	625.84	627.84	631.20	631.33
718+50.00	61.50	646.10	624.92	626.92	630.60	630.31
719+00.00	61.50	646.00	624.00	626.00	630.00	629.28
719+50.00	61.50	645.40	623.04	625.04	629.40	628.25
720+00.00	61.50	644.81	622.08	624.08	628.81	627.21
720+50.00	61.50	644.21	620.99	622.99	628.21	626.27
721+00.00	61.50	643.61	619.90	621.90	627.61	625.33
721+50.00	61.50	643.01	619.43	621.43	627.01	624.47
722+00.00	61.50	642.41	618.96	620.96	626.41	623.61
722+50.00	61.50	641.82	618.89	620.89	625.82	623.01
723+00.00	61.50	641.22	618.82	620.82	625.22	622.42
723+50.00	61.50	640.63	618.74	620.74	624.62	621.98
724+00.00	61.50	640.03	618.65	620.65	624.02	621.55
724+50.00	61.50	639.44	618.08	620.08	623.43	621.25
725+00.00	61.50	638.84	617.51	619.51	622.84	620.95
725+50.00	61.50	638.54	617.43	619.43	622.42	620.75
726+00.00	61.50	638.24	617.35	619.35	622.00	620.54
726+50.00	61.50	637.93	617.29	619.29	621.82	620.55
727+00.00	61.50	637.63	617.23	619.23	621.63	620.56
727+50.00	61.50	637.77	617.32	619.32	621.34	620.57
728+00.00	61.50	637.91	617.42	619.42	621.06	620.58
728+50.00	61.50	638.04	617.46	619.46	621.62	620.71
729+00.00	61.50	638.18	617.50	619.50	622.18	620.85
729+50.00	61.50	638.41	617.55	619.55	622.41	620.96
730+00.00	61.50	638.64	617.61	619.61	622.64	621.07
730+05.00	61.50	638.66	617.62	619.62	622.66	621.09

T:\16817A\Struct\Cadd\Pre-Final\Noise wall\Wall 9b\099\W025-60B04-007.dgn
06-FEB-2009 18:47

DESIGNED	P. LOPEZ
CHECKED	J. GRAINAWI
DRAWN	D. C. PATEL
CHECKED	J. GRAINAWI

GENERAL DATA
STRUCTURE NO. 099-W025



SHEET NO. 7	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	55	99 (1&2) I-12	WILL	147	93
14 SHEETS	CONTRACT NO. 60B04			FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT	