

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (1&2) I-12	WILL	147	107
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

EARTHWORK SCHEDULE

LOCATION				EARTH EXCAVATION (CU YD)	EXCAVATION TO BE USED IN EMBANKMENT (ADJ. FOR SHRINKAGE 15%) (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE (+) OR SHORTAGE (-) (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS (TOPSOIL EXCAVATION) (CU YD)	TOPSOIL FURNISH AND PLACE (6") (SQ YD)
WALL 7	610+25.64	TO	629+51.00	745	635	0	745	355	2130
WALL 8	654+00.00	TO	682+90.00	105	90	-5	100	965	5790
WALL 9A	685+50.00	TO	690+50.00	10	10	0	10	180	1080
WALL 9B	689+00.00	TO	730+05.00	1200	1020	-75	1125	750	4500
WALL 9C	728+00.00	TO	767+00.00	140	120	-5	135	1260	7560

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAI ROUTE 55
 US 30 (PLAINFIELD ROAD) TO WEBER ROAD

EARTHWORK SCHEDULES



SCALE:
 DATE: 2-06-09

DRAWN BY: MMS
 CHECKED BY: DM

FINAL