

SUMMARY OF QUANTITIES				COOK CO	WILL CO		COOK CO	WILL CO
				IL 43 (HARLEM AVE.) AND ST. FRANCIS	IL 43 (HARLEM AVE.) AND VOLLMER ROAD	IL 43 (HARLEM AVE.) AND BENTON AVE.	IL 43 (HARLEM AVE.) AND OAK PARK	INTERCONNECT
CODE NO.	PAY ITEM	CONSTRUCTION CODE	URBAN	YO31 1F	YO31 1F	YO31 1F	YO31 1F	YO31 1F
		UNIT	TOTAL					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	0.6	0.7	0.7	1.0	0.5 0.5
67100100	MOBILIZATION	L SUM	1	0.20	0.20	0.20	0.20	0.10 0.10
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	0.20	0.20	0.20	0.20	0.10 0.10
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.20	0.20	0.20	0.20	0.10 0.10
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	5290					2645 2645
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	140					70 70
81400200	HEAVY-DUTY HANDHOLE	EACH	8					4 4
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	5290					2645 2645
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	4	1	1	1	1	
85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	2		1	1		
85700505	FULL-ACTUATED CONTROLLER IN EXISTING CABINET, SPECIAL	EACH	2	1			1	
86400100	TRANSCEIVER-FIBER OPTIC	EACH	4	1	1	1	1	
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1891				1891	
87900200	DRILL EXISTING HANDHOLE	EACH	4	1	1	1	1	
88024130	OPTICALLY PROGRAMMED SIGNAL HEAD, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	1				1	
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	6				6	
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	3				3	
88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2				2	
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	7				7	
88500100	INDUCTIVE LOOP DETECTOR	EACH	19		14	5		
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	4	1	1	1	1	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	26			26	
X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	6590					3295 3295
X0325705	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	4	1	1	1	1	
X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	4	1	1	1	1	
X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MMI2F SMI2F	FOOT	6590					3295 3295

FILE NAME =	USER NAME = #USER#	DESIGNED MTM	REVISED -
#FILE#		DRAWN LEW	REVISED -
	PLOT SCALE = #SCALE#	CHECKED DHF	REVISED -
	PLOT DATE = #DATE#	DATE APRIL 2009	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
IL RTE. 43 (HARLEM AVE.) FROM
ST. FRANCIS RD. TO OAK PARK AVE.**

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	2008-068-T5	COOK/WILL	18	2
CONTRACT NO.			60F59	
[ILLINOIS] FED. AID PROJECT				