

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1578	*	WILL	155	26
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* 06-00046-00-PV				

**SEEDING SCHEDULE**

STATION	TO	STATION	LT/RT	AREA	20101700 SUPPLEMENTAL WATERING	21101600 TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	21101625 TOPSOIL FURNISH AND PLACE, 6"	25000210 SEEDING, CLASS 2A	25000400 NITROGEN FERTILIZER NUTRIENT	25000500 PHOSPHORUS FERTILIZER NUTRIENT	25000600 POTASSIUM FERTILIZER NUTRIENT	25100115 MULCH, METHOD 2	25200110 SODDING, SALT TOLERANT
				(SQ FT)	(UNITS)	(SQ YD)	(SQ YD)	(ACRE)	(POUND)	(POUND)	(POUND)	(ACRE)	(SQ YD)
LILY CACHE LANE													
106+64		110+00	LT	3,719			414	0.09	9	9	9	0.09	
106+64		110+00	RT	5,590			622	0.13	12	12	12	0.13	
110+00		116+00	LT	9,871			1,097	0.23	21	21	21	0.23	
110+00		116+00	RT	9,942			1,105	0.23	21	21	21	0.23	
110+86		115+75	MEDIAN	4,078	8	454			6	6	6		503
116+00		121+70	LT	14,235			1,582	0.33	30	30	30	0.33	
116+00		121+70	RT	15,594			1,733	0.36	33	33	33	0.36	
121+70		127+60	LT	8,643			961	0.20	18	18	18	0.20	
121+70		127+60	RT	7,965			885	0.19	18	18	18	0.19	
122+51		125+48	MEDIAN	2,591	5	288			4	4	4		320
126+39		127+60	MEDIAN	1,056	2	118			2	2	2		131
127+60		129+05	MEDIAN	1,262	2	141			2	2	2		156
127+60		133+35	LT	6,242			694	0.15	14	14	14	0.15	
127+60		133+35	RT	7,712			857	0.18	17	17	17	0.18	
133+35		139+35	LT	6,794			755	0.16	15	15	15	0.16	
133+35		139+35	RT	6,993			777	0.17	16	16	16	0.17	
139+35		141+30	LT	2,126			237	0.05	5	5	5	0.05	
139+35		141+30	RT	2,586			288	0.06	6	6	6	0.06	
LILY CACHE LANE (TEMPORARY)													
141+30		142+45	LT	713			80	0.02	2	2	2	0.02	
141+30		142+45	RT	1,517			169	0.04	4	4	4	0.04	
SCHMIDT ROAD													
10+55		11+25	LT	340			38	0.01	1	1	1	0.01	
10+55		11+25	RT	590			66	0.02	2	2	2	0.02	
11+25		14+40	LT	2,204			245	0.06	6	6	6	0.06	
11+25		14+40	RT	1,804			201	0.05	5	5	5	0.05	
TOTALS					17	1,001	12,806	2.73	269	269	269	2.73	1,110.00
USE					17	1,001	12,806	2.8	269	269	269	2.8	1,110

**DETECTABLE WARNINGS SCHEDULE**

STATION	LT/RT	OFFSET	42400800 DETECTABLE WARNINGS
			(SQ FT)
LILY CACHE LANE			
106+75	LT	46'	172
106+71	RT	47'	112
108+09	LT	45'	80
108+79	LT	45'	83
110+32	LT	45'	67
110+66	LT	45'	67
118+17	LT	40'	313
118+80	LT	45'	141
121+03	RT	47'	51
121+43	RT	47'	51
121+93	RT	47'	51
122+37	RT	47'	51
125+78	RT	46'	57
126+28	RT	46'	44
129+36	RT	46'	52
129+88	RT	46'	51
131+94	RT	46'	47
132+25	RT	46'	47
135+33	LT	45'	169
135+38	RT	45'	60
135+92	LT	45'	170
135+83	RT	45'	58
138+42	RT	45'	58
138+96	RT	45'	58
140+49	RT	46'	55
140+95	RT	46'	54
TOTAL			2,219

**BUS SHELTER SCHEDULE**

STATION	LT/RT	OFFSET	XX003688 BUS SHELTER	XX003711 BUS SHELTER REMOVAL
			(EACH)	(EACH)
LILY CACHE LANE				
106+81	LT	41'		1
<del>106+91</del>	<del>LT</del>	<del>45'</del>	1	
<del>127+13</del>	<del>RT</del>	<del>40'</del>	1	
127+13	RT	28'		1
<del>136+25</del>	<del>LT</del>	<del>36'</del>	1	
TOTAL			2	2

△ Revised 7-17-09

**WATER VALVE SCHEDULE**

STATION	LT/RT	OFFSET	56109210 WATER VALVES TO BE ADJUSTED
			(EACH)
LILY CACHE LANE			
106+67	RT	20'	1
106+73	RT	23'	1
110+09	RT	20'	1
122+92	RT	26'	1
125+94	LT	43'	1
138+41	RT	29'	1
LILY CACHE LANE			
20+68	RT	22'	1
TOTAL			7

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**

SCALE: NONE      DRAWN BY: JEB

DATE: APRIL 9, 2009      CHECKED BY: CMS

PLOT DATE = #DATE#  
 FILE NAME = #FILE#  
 PLOT SCALE = #SCALE#  
 USER NAME = #USER#

#FILES#