

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1578	*	WILL	155	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* 06-00046-00-PV				

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

LOCATION OF WORK				CONSTRUCTION TYPE CODE			
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY I000-2A	CULVERT X028-2A	SIGNALS Y031-1F	LIGHTING Y030-1E
40600300	AGGREGATE (PRIME COAT)	TON	52.00	52.00			
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	29.00	29.00			
40600895	CONSTRUCTING TEST STRIP	EACH	1.00	1.00			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,200.00	1,200.00			
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	11,048.00	11,048.00			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,613.00	2,613.00			
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	1,167.00	1,167.00			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	31,765.00	31,765.00			
42400800	DETECTABLE WARNINGS	SQ FT	2,219.00	2,219.00			
44000100	PAVEMENT REMOVAL	SQ YD	19,673.00	19,673.00			
* 44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	2,180.00	2,180.00			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,508.00	1,508.00			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	9,052.00	9,052.00			

* SEE SPECIAL PROVISION
> DENOTES "SPECIAL ITEM"

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: APRIL 9, 2009

DRAWN BY: JEB
CHECKED BY: CMS

PLOT DATE = 4/13/2009
FILE NAME = G:\5656924\CAD\5024SUMSHT
PLOT SCALE = 28.411' / IN.
USER NAME = IE Consultants

5024SUMSHT