

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1578	*	WILL	155	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* 06-00046-00-PV				

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

LOCATION OF WORK				CONSTRUCTION TYPE CODE			
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY I000-2A	CULVERT X028-2A	SIGNALS Y031-1F	LIGHTING Y030-1E
44000600	SIDEWALK REMOVAL	SQ FT	20,852.00	20,852.00			
50200100	STRUCTURE EXCAVATION	CU YD	2,683.00		2,683.00		
* 51205200	TEMPORARY SHEET PILING	SQ FT	663.00		663.00		
51500100	NAME PLATES	EACH	1.00		1.00		
54000900	BOX CULVERT END SECTIONS, SPECIAL	EACH	6.00		6.00		
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2.00	2.00			
54214521	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 36"	EACH	1.00	1.00			
542A5482	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 27"	FOOT	153.00	153.00			
542A5485	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 30"	FOOT	60.00	60.00			
542A5491	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36"	FOOT	42.00	42.00			
* 550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	1,638.00	1,638.00			
* 550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	571.00	571.00			
* 550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	531.00	531.00			

* SEE SPECIAL PROVISION
> DENOTES "SPECIAL ITEM"

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: JEB
DATE: APRIL 9, 2009 CHECKED BY: CMS

PLOT DATE = 4/13/2009
FILE NAME = G:\SR\924\CAD\924SUM.SHT
PLOT SCALE = 28.411 / IN.
USER NAME = IE Consultants

924SUM.SHT