

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1578	*	WILL	155	12
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* 06-00046-00-PV				

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

LOCATION OF WORK				CONSTRUCTION TYPE CODE			
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY I000-2A	CULVERT X028-2A	SIGNALS Y031-1F	LIGHTING Y030-1E
>	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	80.00		80.00	
>	81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1.00		1.00	
>	81603025	UNIT DUCT, 600V, 2-1C NO.4, 1/C NO.4 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	720.00			720.00
>	81603035	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	1,116.00			1,116.00
>	81603055	UNIT DUCT, 600V, 3-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	4,612.00			4,612.00
>	81702415	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 6	FOOT	593.00		593.00	
>	81702440	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 1/0	FOOT	100.00			100.00
>	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	3,365.00		62.00	3,303.00
>	82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	37.00		3.00	34.00
> *	82500505	LIGHTING CONTROLLER, SPECIAL	EACH	2.00			2.00
>	83007400	LIGHT POLE, ALUMINUM, 35 FT. M.H., 10 FT. MAST ARM	EACH	24.00			24.00
>	83007600	LIGHT POLE, ALUMINUM, 35 FT. M.H., 15 FT. MAST ARM	EACH	2.00			2.00
>	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	520.00			520.00

* SEE SPECIAL PROVISION
> DENOTES "SPECIAL ITEM"

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: APRIL 9, 2009

DRAWN BY: JEB
CHECKED BY: CMS

PLOT DATE = 4/13/2009
FILE NAME = D:\S\624\CAD\624\SUM.SHT
PLOT SCALE = 28.411 / IN.
USER NAME = IE Consultants

624\SUM.SHT