

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1578	*	WILL	155	18
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* 06-00046-00-PV				

**DRAINAGE STRUCTURE SCHEDULE**

STRUCTURE NUMBER	STATION	LT/RT	OFFSET	PRECAST REINFORCED CONCRETE FLARED END SECTION 12"	PRECAST REINFORCED CONCRETE FLARED END SECTION EQRS 36"	CATCH BASINS, TYPE D, 3'-DIAMETER, TYPE 3 FRAME & GRATE	CATCH BASINS, TYPE D, 4'-DIAMETER, TYPE 15 FRAME & LID	CATCH BASINS, TYPE D, 4'-DIAMETER, TYPE 23, FRAME & GRATE	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3, FRAME & GRATE	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME-CLID	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 3 FRAME & GRATE	INLETS, TYPE A, TYPE 3 FRAME & GRATE	MANHOLES TO BE ADJUSTED	CATCH BASINS, TYPE D, 5'-DIA, TYPE 15 FRAME & LID	REMOVING MANHOLES	REMOVING CATCH BASINS	REMOVING INLETS	SANITARY MANHOLES TO BE ADJUSTED	INLETS, TYPE A, TYPE 3V FRAME & GRATE	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 15 FRAME & LID	CATCH BASINS, TYPE D, 3'-DIAMETER, TYPE 3V FRAME & GRATE	CATCH BASINS, TYPE D, 4'-DIAMETER, TYPE 3V FRAME & GRATE
				(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)
LILY CACHE LANE																						
	106+95	RT	31'													1						
	107+42	LT	32'												1							
1	107+42	LT	31.66'							1												
	107+52	RT	27'														1					
	107+52	LT	25'														1					
3	107+89	RT	27'			1																
4	107+89	LT	29'				1															
2	108+04	RT	27'									1										
5	108+04	LT	29'				1															
	108+10	LT	41'															1				
6	109+00	RT	27'																1			
7	109+00	LT	29'				1															
	110+88	LT	41'															1				
	111+33	LT	32'												1							
	111+54	RT	18'														1					
	111+54	LT	17'														1					
11	111+55	RT	27'									1										
10	111+55	LT	29'																	1		
	111+64	LT	34'										1									
13	111+75	LT	29'																			
12	111+75	RT	27'			1																
14	112+75	RT	27'																		1	
15	112+75	LT	29'				1															
	112+80	LT	28'																			
	112+98	LT	41'																1			
18	113+94	LT	58'	1																		
16	114+20	RT	27'																		1	
17	114+20	LT	29'																			1
	114+73	RT	38'																			1
	114+79	RT	24'										1									
19	115+75	RT	27'																			1
20	115+75	LT	29'																			1
21	115+87	LT	58.5'	1																		1
	118+01	RT	19'																			1
	118+24	LT	25'																			1
	118+68	LT	41'																			1
	118+79	LT	22'																			1
	119+50	RT	38'																			1
	119+66	LT	28'																			1
22	119+82	LT	29'									1										
24	119+82	RT	27'									1										
25	119+97	RT	27'																			1
23	119+97	LT	29'																			1
26	119+97	RT	71.5'																			1

NOTE: ALL MANHOLES AND CATCH BASINS ARE TO BE RESTRICTED DEPTH. SEE SUMMARY OF QUANTITIES.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**

SCALE: NONE  
 DATE: APRIL 9, 2009  
 DRAWN BY: JEB  
 CHECKED BY: CMS

PLOT DATE = \*DATE\*  
 FILE NAME = \*FILE\*  
 PLOT SCALE = \*SCALE\*  
 USER NAME = \*USER\*

FILE#