

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1578	*	WILL	155	20
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* 06-00046-00-PV				

DRAINAGE STRUCTURE SCHEDULE

STRUCTURE NUMBER	STATION	LT/RT	OFFSET	PRECAST REINFORCED CONCRETE FLARED END SECTION 12"	PRECAST REINFORCED CONCRETE FLARED END SECTION EQRS 36"	CATCH BASINS, TYPE D, 3'-DIAMETER, TYPE 3 FRAME & GRATE	CATCH BASINS, TYPE D, 4'-DIAMETER, TYPE 15 FRAME & LID	CATCH BASINS, TYPE D, 4'-DIAMETER, TYPE 23, FRAME & GRATE	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3, FRAME & GRATE	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME-CLID	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 3 FRAME & GRATE	INLETS, TYPE A, TYPE 3 FRAME & GRATE	MANHOLES TO BE ADJUSTED	CATCH BASINS, TYPE D, 5'-DIA, TYPE 15 FRAME & LID	REMOVING MANHOLES	REMOVING CATCH BASINS	REMOVING INLETS	SANITARY MANHOLES TO BE ADJUSTED	INLETS, TYPE A, TYPE 3V FRAME & GRATE	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 15 FRAME & LID	CATCH BASINS, TYPE D, 3'-DIAMETER, TYPE 3V FRAME & GRATE	CATCH BASINS, TYPE D, 4'-DIAMETER, TYPE 3V FRAME & GRATE	
				(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)
LILY CACHE LANE																							
	135+86	LT	57'																				
	135+87	LT	25'																				
	136+07	LT	35'																				
	136+15	LT	29'																				
	136+20	RT	23'																				
52	138+20	LT	29'																				
53	138+20	RT	27'																				
	139+23	LT	41'																				
56	139+75	LT	29'																				
57	139+75	RT	27'																				
	140+78	RT	18'																				
	140+78	LT	18'																				
59	140+78	LT	29'																				
60	140+78	RT	27'																				
61	140+93	RT	27'																				
58	140+93	LT	29'																				
	141+00	RT	30'																				
	141+17	RT	60'																				
63	141+25	RT	42'																				
62	141+25	RT	27'																				
SUB-TOTAL				2	1	2	12	2	0	2	1	6	13	5	7	4	16	14	13	1	2	1	
CANTERBURY LANE																							
	20+52	RT	26'																				
	20+56	RT	40'																				
	20+57	LT	23'																				
	20+76	LT	24'																				
66	20+76.2	RT	17.42'																				
68	20+76.3	LT	17.42'																				
65	20+87	RT	17.42'																				
67	20+87	LT	17.42'																				
SUB-TOTAL				0	0	0	0	0	2	0	0	2	2	0	0	0	0	2	0	0	0	0	0
TOTALS				2	1	2	12	2	2	2	1	8	15	5	7	4	16	16	13	1	2	1	

NOTE: ALL MANHOLES AND CATCH BASINS ARE TO BE RESTRICTED DEPTH. SEE SUMMARY OF QUANTITIES.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE
DATE: APRIL 9, 2009

DRAWN BY: JEB
CHECKED BY: CMS

PLOT DATE = #DATE#
FILE NAME = #FILE#
USER NAME = #USER#