CONTRACT No. 63093

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1578	*	WILL	155	21
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* 06-00046-00-PV

STORM SEWER SCHEDULE

PIPE NUMBER	STATION FROM	LT/RT	OFFSET	STATION TO	LT/RT	OFFSET	STORM SEWER REMOVAL 8" (FOOT)	10" (FOOT)	12" (FOOT)	15" (FOOT)	18" (FOOT)	21" (FOOT)	24" (FOOT)	30" (FOOT)	STORM SEWERS, CLASS A, TYPE 1 12" (FOOT)	15" (FOOT)	18" (FOOT)	21" (FOOT)	24" (FOOT)	27" (FOOT)	PIPE CULVERTS, CLASS A, TYPE 1 27" ERS (FOOT)	30" ERS (FOOT)	36" ERS (FOOT)
	LILY CACHE LANE																						
	106+95.00	RT	32.00	107+28.00	RT	32.00						33											
	107+42.00	LT	10.00	107+42.00	LT	31.00								21									
	107+51.00	LT	25.00	107+29.00	LT	25.00			22														
	107+52.00	RT	26.00	107+52.00	LT	24.00	49																
3	107+89.00	RT	28.00	107+89.00	LT	29.80									60								
1	107+89.00	LT	29.80	107+42.00	LT	31.66														47			
2	108+04.00	RT	27.83	107+89.00	RT	27.83									15								
4	108+04.00	LT	29.87	107+89.00	LT	29.80											15						
6	109+00.00	RT	27.80	109+00.00	LT	29.80									60								
5	109+00.00	LT	29.80	108+04.00	LT	29.87											96						
	111+31.00	LT	32.00	107+44.00	LT	32.00				387													
	111+54.00	LT	3.00	111+54.00	LT	16.00	14																
	111+54.00	LT	18.00	111+35.00	LT	31.00			23														
11	111+55.00	RT	27.80	111+75.00	RT	27.80									20								
7	111+55.00	LT	29.80	109+00.00	LT	29.80											255						
12	111+75.00	RT	27.80	111+75.00	LT	29.80									60								
10	111+75.00	LT	29.80	111+55.00	LT	29.80										20							
14	112+75.00	RT	27.80	112+75.00	LT	29.80									60								
13	112+75.00	LT	29.80	111+75.00	LT	29.80										100							
15	114+20.00	RT	27.80	114+20.00	LT	29.80									60								
16	114+20.00	LT	29.80	113+94.00	LT	58.00									39								
17	115+75.00	RT	27.83	115+75.00	LT	29.80									60								
18	115+75.00	LT	29.80	115+87.00	LT	58.50									32								
	118+01.00	RT	18.00	118+16.00	RT	3.00		21															
	118+26.00	LT	26.00	188+18.00	LT	18.00							10										
	118+68.00	LT	41.00	118+78.00	LT	23.00			21														
	118+70.00	LT	76.00	118+33.00	LT	77.00					37												
	118+78.00	LT	22.00	118+25.00	LT	25.00						52											
22	119+82.00	LT	29.80	119+97.00	LT	29.80									15								
24	119+82.00	RT	27.80	119+97.00	RT	27.80									15								
23	119+97.00	LT	29.80	119+97.00	RT	27.80																60	
25	119+97.00	RT	27.80	119+97.00	RT	71.50																	42
27	121+50.00	LT	29.92	121+50.00	RT	27.80									60								
26	121+50.00	LT	32.00	119+97.00	LT	32.00															153		
	122+02.00	RT	17.00	122+02.00	LT	17.00		34															
	122+02.00	LT	19.00	121+97.00	LT	23.00			6														
31	123+00.00	LT	29.92	123+00.00	RT	27.80									60								
30	123+00.00	LT	32.00	121+50.00	LT	32.00													150				
32	124+94.00	LT	32.00	123+00.00	LT	32.00													194				
	124+90.00	LT	24.00	118+79.00	LT	22.00					610												
33	124+94.50	LT	29.80	124+90.00	RT	27.80									60								
	125+07.00	LT	61.00	124+93.00	LT	25.00			39														

SIGNING SCHEDULE

STATION	LT/RT	OFFSET	72400500 RELOCATE SIGN PANEL ASSEMBLY, TYPE A (EACH)	XX002133 RELOCATE SIGN AND BASE (EACH)
LILY CACHE LANE				
106+75	RT	37'	1	
106+88	LT	41'	1	
107+28	LT	27'	1	
108+95	RT	23'	1	
109+17	LT	23'	1	
110+83	LT	20'	1	
112+82	LT	20'	1	
113+32	LT	22'	1	
116+18	RT	44'		1
116+51	RT	42'		1
116+94	RT	22'	1	
117+00	LT	20'	1	
117+94	RT	21'	1	
120+87	LT	21'	1	
122+74	LT	21'	1	
125+53	LT	21'	1	
126+26	RT	51'	1	
127+19	RT	25'	1	
127+63	LT	21'	1	
128+11	RT	24'	1	
129+83	RT	32'	1	
132+66	RT	21'	1	
134+36	LT	22'	1	
135+79	RT	32'	1	
136+08	LT	21'	1	
136+23	RT	23'	1	
138+91	RT	54'	1	
138+96	RT	39'	1	
141+29	LT	22'	1	
SCHMIDT ROAD				
11+52	LT	27'	1	
12+86	LT	22'	1	
14+13	LT	21'	1	
CANTERBURY LANE				
20+53	LT	22'	1	
TOTAL			31	2

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE
DATE: APRIL 9, 2009
DRAWN BY: JEB
CHECKED BY: CMS

PLOT DATE = $DATE$
FILE NAME = $FILE$
PLOT SCALE = $SCALE$
USER NAME = $USER$

$FILES$