CONTRACT No. 63093

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1578	*	WILL	155	22
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* 06-00046-00-PV

STORM SEWER SCHEDULE

PIPE NUMBER	STATION	LT/RT	OFFSET	STATION	LT/RT	OFFSET	STORM SEWER REMOVAL								STORM SEWERS, CLASS A, TYPE 1						PIPE CULVERTS, CLASS A, TYPE 1		
							8"	10"	12"	15"	18"	21"	24"	30"	12"	15"	18"	21"	24"	27"	27" ERS	30" ERS	36" ERS
	FROM			TO			(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)
	LILY CACHE LANE																						
	126+41.00	LT	25.00	124+94.00	LT	24.00				148													
	126+50.00	LT	19.00	126+45.00	LT	23.00				7													
	126+52.00	RT	17.00	126+51.00	LT	17.00		34															
35	126+53.00	LT	29.80	126+53.00	RT	27.80									60								
36	127+75.00	LT	27.80	126+53.00	LT	32.00											122						
34	126+53.00	LT	32.00	124+90.00	LT	32.00												158					
	126+93.00	LT	52.00	126+46.00	LT	26.00				54													
41	127+75.00	LT	29.83	127+75.00	RT	27.80									60								
43	130+00.00	RT	29.83	130+00.00	LT	27.80									60								
44	130+00.00	LT	32.00	131+75.00	LT	32.00									175								
42	130+00.00	LT	32.00	127+75.00	LT	32.00										225							
	130+14.00	LT	24.00	126+46.00	LT	25.00			369														
	130+15.00	RT	17.00	130+16.00	LT	17.00		34															
	130+16.00	LT	19.00	130+16.00	LT	21.00			3														
45	131+75.00	LT	29.83	131+75.00	RT	27.80									60								
46	131+75.00	LT	32.00	133+50.00	LT	32.00									175								
	132+24.00	LT	25.00	130+19.00	LT	24.00			206														
	132+38.00	LT	18.00	132+29.00	LT	23.00			11														
	132+39.00	RT	17.00	132+39.00	LT	17.00		34															
50	133+50.00	LT	29.83	133+50.00	RT	27.80									60								
	135+87.00	LT	24.00	135+64.00	LT	29.00			23														
51	138+20.00	LT	29.83	138+20.00	RT	27.80									60								
52	138+20.00	LT	32.00	139+75.00	LT	32.00									155								
56	139+75.00	LT	29.83	139+75.00	RT	27.80									60								
57	139+75.00	LT	32.00	140+78.00	LT	32.00										104							
59	140+78.00	LT	29.80	140+78.00	RT	27.80										60							
60	140+78.00	RT	32.00	140+93.00	RT	27.80										15							
	140+78.00	LT	17.00	140+78.00	RT	17.00		34															
	140+79.00	RT	19.00	140+98.00	RT	29.00				22													
58	140+93.00	LT	32.00	140+78.00	LT	29.80									15								
61	140+93.00	RT	27.80	141+25.00	RT	27.80										32							
	141+00.00	RT	32.00	141+09.00	RT	46.00					16												
62	141+25.00	RT	27.80	141+25.00	RT	42.00										15							
63	141+25.00	RT	42.00	141+23.00	RT	54.50													13				
	SUB-TOTAL						63	191	723	618	663	85	10	21	1616	571	488	158	357	47	153	60	42
	CANTERBURY LANE																						
67	20+76.00	RT	18.26	20+76.00	LT	18.26											37						
69	20+76.00	LT	18.26	20+76.00	LT	24.09											6						
66	20+87.00	RT	18.25	20+76.00	RT	18.26									11								
68	20+87.00	LT	18.25	20+76.00	LT	18.26									11								
	SUB-TOTAL						0	0	0	0	0	0	0	0	22	0	43	0	0	0	0	0	0
	TOTALS						63	191	723	618	663	85	10	21	1638	571	531	158	357	47	153	60	42

ENTRANCE SCHEDULE

STATION	LT/RT	TYPE	42300400 PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	44000200 DRIVEWAY PAVEMENT REMOVAL	60603800 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12
			(SQ YD)	(SQ YD)	(FOOT)
LILY CACHE LANE					
108+43	LT.	CE	142	215	59
110+49	LT.	CE	67	91	48
116+38	RT.	CE	87	94	
121+23	RT.	CE	76	91	48
122+15	RT.	CE	85	115	48
129+63	RT.	CE	166	202	77
132+09	RT.	CE	56	83	46
135+61	RT.	CE	98	127	54
140+72.5	RT.	CE	135	144	74
LILY CACHE LANE					
11+44	RT.	CE	64	94	30
11+90	LT.	CE	38	49	28
12+44.5	LT.	CE	39	53	29
12+49.5	RT.	CE	54	83	29
13+63.5	LT.	CE	60	67	35
TOTAL			1,167	1,508	605

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE

DATE: APRIL 9, 2009

DRAWN BY: JEB

CHECKED BY: CMS

$FILES$

PLOT DATE = $DATE$
FILE NAME = $FILE$
PLOT SCALE = $SCALE$
USER NAME = $USER$