

F.A.U. RT#	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1578	*	WILL	155	23
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* 06-00046-00-PV				

CURB AND GUTTER REMOVAL SCHEDULE				
STATION	TO	STATION	LT/RT	44000500 COMBINATION CURB AND GUTTER REMOVAL (FOOT)
LILY CACHE LANE				
106+56		110+00	LT	513
106+56		110+00	RT	370
110+00		116+00	LT	669
110+00		116+00	RT	600
116+00		121+70	LT	479
116+00		121+70	RT	647
121+70		127+60	LT	590
121+70		127+60	RT	545
127+60		133+35	LT	575
127+60		133+35	RT	716
133+35		139+35	LT	515
133+35		139+35	RT	685
139+35		141+30	LT	195
139+35		141+30	RT	305
SCHMIDT ROAD				
10+65		11+25	LT	59
10+65		11+25	RT	42
11+25		14+40	LT	472
11+25		14+40	RT	399
CANTERBURY LANE				
20+16		21+50	LT	157
20+16		21+50	RT	158
WOODCREEK ROAD				
29+43		29+43	LT	57
29+43		29+43	RT	58
FERNWOOD DRIVE-WEST				
40+16		40+70	LT	69
40+16		40+70	RT	69
QUADRANGLE DRIVE				
49+43		49+83	LT	57
49+43		49+83	RT	51
TOTALS				9,052

SIDEWALK REMOVAL SCHEDULE				
STATION	LT/RT	STATION	LT/RT	44000600 SIDEWALK REMOVAL (SQ FT)
LILY CACHE LANE				
106+59	LT.	108+15	LT.	639
106+60	RT.	106+78	RT.	138
108+74	LT.	110+00	LT.	624
110+00	LT.	110+36	LT.	178
110+62	LT.	116+00	LT.	2,636
114+25	RT.	116+00	RT.	704
116+00	LT.	118+32	LT.	1,325
118+68	LT.	121+70	LT.	1,592
116+00	RT.	121+08	RT.	2,170
121+35	RT.	121+70	RT.	176
121+70	LT.	127+60	LT.	2,904
121+70	RT.	122+00	RT.	147
122+31	RT.	122+42	RT.	53
125+73	RT.	125+86	RT.	63
126+22	RT.	126+33	RT.	49
127+03	RT.	127+20	RT.	218
127+60	LT.	133+35	LT.	2,803
129+31	RT.	129+40	RT.	46
129+79	RT.	129+93	RT.	61
131+89	RT.	132+00	RT.	47
132+19	RT.	132+29	RT.	61
133+35	LT.	135+44	LT.	1,049
135+33	RT.	135+45	RT.	56
135+77	RT.	135+89	RT.	53
135+81	LT.	139+35	LT.	1,786
138+36	RT.	138+50	RT.	61
138+88	RT.	139+09	RT.	175
139+35	LT.	141+30	LT.	957
140+43	RT.	140+59	RT.	81
TOTAL				20,852

SIDEWALK SCHEDULE				
STATION	LT/RT	STATION	LT/RT	42400200 PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH (SQ FT)
LILY CACHE LANE				
106+68	LT.	108+15	LT.	1,373
106+63	RT.	106+78	RT.	112
108+75	LT.	110+00	LT.	1,014
110+00	LT.	110+36	LT.	287
110+62	LT.	116+00	LT.	4,310
114+25	RT.	116+00	RT.	782
116+00	LT.	118+30	LT.	2,090
118+75	LT.	121+70	LT.	2,484
116+00	RT.	121+07	RT.	2,467
121+38	RT.	121+70	RT.	153
121+70	LT.	127+60	LT.	4,720
121+70	RT.	121+98	RT.	132
122+32	RT.	122+42	RT.	52
125+73	RT.	126+33	RT.	104
127+03	RT.	127+20	RT.	168
127+60	LT.	133+35	LT.	4,600
129+31	RT.	129+93	RT.	104
131+90	RT.	132+29	RT.	104
133+35	LT.	135+41	LT.	1,679
135+33	RT.	135+89	RT.	120
135+85	LT.	139+35	LT.	2,976
138+37	RT.	139+04	RT.	123
139+35	LT.	141+30	LT.	1,560
140+44	RT.	141+30	RT.	251
TOTAL				31,765

TEMPORARY PAVEMENT SCHEDULE					
STATION	TO	STATION	LT/RT	X0712400 TEMPORARY PAVEMENT, 8"	44000100 PAVEMENT REMOVAL
				(SQ YD)	(SQ YD)
LILY CACHE LANE					
STAGE 1					
106+78		110+00	RT	207	207
110+00		116+00	RT	667	667
116+00		118+00	RT	147	147
STAGE 2					
106+69		108+09	LT	57	57
108+74		110+00	LT	148	148
110+00		116+00	LT	883	883
116+00		118+32	LT	412	412
118+68		121+70	LT	469	469
121+70		127+60	LT	716	716
127+60		133+35	LT	686	686
133+35		135+53	LT	238	238
135+96		139+35	LT	406	406
139+35		142+45	LT	307	307
TOTALS				5,343	5,343

REMOVAL OF EXISTING LIGHTING UNITS				
STATION	LT/RT	OFFSET	84200600 REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE (EACH)	84200700 LIGHTING FOUNDATION REMOVAL (EACH)
LILY CACHE LANE				
106+62	RT	66'	1	1
107+72	RT	29'	1	1
110+84	RT	23'	1	1
113+83	RT	23'	1	1
116+82	RT	23'	1	1
125+83	RT	40'	1	1
129+54	LT	21'	1	1
132+10	LT	21'	1	1
135+42	LT	59'	1	1
135+79	RT	39'	1	1
135+83	LT	50'	1	1
TOTAL			11	11

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE
DATE: APRIL 9, 2009

DRAWN BY: JEB
CHECKED BY: CMS

PLOT DATE = #DATE#
FILE NAME = #FILE#
PLOT SCALE = #SCALE#
USER NAME = #USER#

#FILES#