

F.A.U. RTE. 1578	SECTION *	COUNTY WILL	TOTAL SHEETS 155	SHEET NO. 24
------------------	-----------	-------------	------------------	--------------

STA.	TO STA.
------	---------

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT
* 06-00046-00-PV

PAVING SCHEDULE

STATION	TO	STATION	35100100 AGGREGATE BASE COURSE, TYPE A	35101400 AGGREGATE BASE COURSE, TYPE B	35600716 HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	40600215 POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	40600300 AGGREGATE (PRIME COAT)	40600837 POLYMERIZED LEVELING BINDER (MM), N70	40603235 POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	40603285 POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-25.0, N70	40603540 POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	44000100 PAVEMENT REMOVAL
			(TON)	(TON)	(SQ YD)	(TON)	(TON)	(TON)	(TON)	(TON)	(TON)	(SQ YD)
LILY CACHE LANE												
106+56.00		110+00.00	1,728	622		5	5		314	847	251	1,630
110+00.00		116+00.00	2,890	950		7	7		433	1,168	346	2,191
116+00.00		121+70.00	3,147	1,025		9	8		519	1,401	416	2,090
121+70.00		127+60.00	2,947	978		8	7		455	1,228	364	2,164
127+60.00		133+35.00	2,771	966		8	7		474	1,278	379	2,197
133+35.00		139+35.00	3,137	1,126		10	9		573	1,546	458	2,204
139+35.00		141+30.00	1,102	339		3	3		170	459	136	718
SCHMIDT ROAD												
10+30.00		11+25.00	17		30	1	1				40	
10+50.00		10+65.00										
10+65.00		11+00.00						0.73				
11+00.00		11+50.00						6.05				
11+25.00		14+40.00	99		189	4	3				160	
11+50.00		12+00.00						8.57				
12+00.00		12+50.00						4.78				
12+50.00		13+00.00						3.99				
13+00.00		13+63.00						3.85				
13+63.00		14+00.00						0.22				
14+00.00		14+40.00										
CANTERBURY LANE												
20+16.00		21+50.00							*	*	*	532
20+59.00		21+50.00	289			1	1		50	133	40	
WOODCREEK ROAD												
29+43.00		29+83.00							*	*	*	184
FERNWOOD DRIVE - WEST												
40+16.00		40+70.00							*	*	*	229
QUADRANGLE DRIVE												
49+43.00		49+83.00							*	*	*	190
TEMPORARY LILY CACHE LANE												
141+30.00		142+45.00	55		199	1	1				23	
TOTALS			18,182	6,006	418	57	52	28.2	2,988	8,060	2,613	14,330

* TO BE CONSTRUCTED AS, AND QUANTITIES INCLUDED WITH, MAINLINE PAVEMENT

CONCRETE CURB AND GUTTER SCHEDULE

STATION	TO	STATION	LT/RT	60604400 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	60605900 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12	60606800 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.18	60620800 CONCRETE MEDIAN, TYPE SB- 9.12
				(FOOT)	(FOOT)	(FOOT)	(SQ FT)
LILY CACHE LANE							
106+56		110+00	LT			350	
106+56		110+00	RT			364	
110+00		116+00	LT & RT			1,200	
110+72		110+87	MEDIAN				114
110+86		115+75	LT & RT		978		
115+75		115+87	MEDIAN				67
116+00		121+70	LT & RT			1,140	
121+70		127+60	LT & RT			1,180	
122+41		122+52	MEDIAN				74
122+51		125+48	LT & RT		594		
125+47		125+58	MEDIAN				74
126+29		126+40	MEDIAN				74
126+39		127+60	LT & RT		242		
127+60		129+05	LT & RT		290		
127+60		133+35	LT & RT			1,150	
129+04		129+15	MEDIAN				74
133+35		139+35	LT & RT			1,200	
139+35		141+30	LT & RT			390	
SCHMIDT ROAD							
10+55		11+25	RT	70			
11+04		11+25	LT	21			
11+25		14+40	LT & RT	630			
CANTERBURY LANE							
20+29		21+50	LT & RT	232			
WOODCREEK ROAD							
29+43		29+73	LT & RT	48			
FERNWOOD DRIVE-WEST							
40+29		40+70	LT & RT			82	
QUADRANGLE DRIVE							
49+43		49+73	30' LT & RT		60		
TEMPORARY - LILY CACHE LANE							
141+30		142+45	LT & RT			232	
TOTALS				1,001	2,164	7,288	477

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE
DATE: APRIL 9, 2009

DRAWN BY: JEB
CHECKED BY: CMS