


# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES				LOCATION OF WORK		WASHINGTON BOULEVARD		JACKSON BOULEVARD		RIDGELAND AVENUE		OAK PARK AVENUE	
CONSTRUCTION CODE				UNIT	TOTAL	TRAFFIC SIGNAL	INTERCONNECT	TRAFFIC SIGNAL	INTERCONNECT	TRAFFIC SIGNAL	INTERCONNECT	TRAFFIC SIGNAL	INTERCONNECT
++		CODE NO.	ITEM			Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F
++		67100100	MOBILIZATION	L SUM	1	0.125	0.125	0.125	0.125	0.125	0.125	0.125	0.125
++	*	70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	0.125	0.125	0.125	0.125	0.125	0.125	0.125	0.125
		81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	5565	2,020	1,621	387	355	531			651
		81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	292	292							
		81400100	HANDHOLE	EACH	16	8		2		2	2		2
		85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	10		3	2		3		2	
		85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1	1							
		86400100	TRANSCIVER - FIBER OPTIC	EACH	7		3		1		2		1
		87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14, 1 PAIR	FOOT	4544	3,099		711		735			
		87800200	CONCRETE FOUNDATION, TYPE D	FOOT	4	4							
		87900200	DRILL EXISTING HANDHOLE	EACH	38	23	3	2	2	2	4		2
		88500100	INDUCTIVE LOOP DETECTOR	EACH	6	4				2			
		88600100	DETECTOR LOOP, TYPE I	FOOT	593	462		64		67			
		89501100	RELOCATE EXISTING TRAFFIC SIGNAL CONTROLLER	EACH	1	1							
		89502200	MODIFY EXISTING CONTROLLER	EACH	6	2		1		2		1	
		89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	947	699		249					
		89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2	2							
++		89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	1	1							
++		X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	205	51		51		51		51	
++		X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO 14/1C	FOOT	7226		2067		826		2901		1432
++		X8780110	MODIFY EXISTING TYPE "D" FOUNDATION	EACH	1	1							
++		XX003660	FIBER OPTIC CABLE IN CONDUIT NO. 62.5/125 MM 24F SM 12F	FOOT	7226		2067		826		2901		1432
++		Z0013798	CONSTRUCTION LAYOUT, SPECIAL	L SUM	1	0.125	0.125	0.125	0.125	0.125	0.125	0.125	0.125

• INDICATES SPECIALTY ITEMS  
 ++ INDICATES SPECIAL PROVISION

FILE NAME = s:\p\6780--6799\678A\087\087\Murphy\Sheets\500.dgn



USER NAME = odamn	DESIGNED -	REVISED -
PLOT SCALE = 20.0000' / IN.	DRAWN -	REVISED -
PLOT DATE = 5/26/2009	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1412	07-00245-00-TL	COOK	64	3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 63112	