

SUMMARY OF QUANTITIES


CODE NO.	SP	ITEM	UNIT	QUANTITY
20100110		TREE REMOVAL (6-15 UNIT DIAMETER)	UNIT DIA.	32
20100210		TREE REMOVAL (OVER 15 UNIT DIAMETER)	UNIT DIA.	216
20101700		SUPPLEMENTAL WATERING	UNIT	5
20200100		EARTH EXCAVATION	CU YD	355
20201200		REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS	CU YD	50
20400800		FURNISHED EXCAVATION	CU YD	100
20700400	*	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	43
20700420	*	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	50
21101505		TOPSOIL EXCAVATION AND PLACEMENT	CU YD	170
25000110	X	SEEDING CLASS 1A	ACRE	0.25
25000400	X	NITROGEN FERTILIZER NUTRIENT	POUND	30
25000500	X	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	30
25000600	X	POTASSIUM FERTILIZER NUTRIENT	POUND	30
25100115	X	MULCH METHOD 2	ACRE	0.25
25100630	X	EROSION CONTROL BLANKET	SQ YD	208
25200100	X	SODDING	SQ YD	1100
28000400		PERIMETER EROSION BARRIER	FT	1530
28100107		STONE RIPRAP, CLASS A4	SQ YD	283
28200200		FILTER FABRIC	SQ YD	283
35101800		AGGREGATE BASE COURSE, TYPE B, 6"	SQ YD	746
40201000		AGGREGATE FOR TEMPORARY ACCESS	TON	30
40600100		BITUMINOUS MATERIALS (PRIME COAT)	GALLON	373
40603310		HOT-MIX ASPHALT SURFACE COURSE, MIX "C" N50	TON	84
42400200		PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	100
44000600		SIDEWALK REMOVAL	SQ FT	460
50100100		REMOVAL OF EXISTING STRUCTURES	EACH	1
50200100		STRUCTURE EXCAVATION	CU YD	92
50300225		CONCRETE STRUCTURES	CU YD	26
50800205		REINFORCEMENT BARS, EPOXY COATED	POUND	1600
59100100	*	GEOCOMPOSITE WALL DRAIN	SQ YD	22
60109580		PIPE UNDERDRAINS FOR STRUCTURES 4"	FT	117
67100100		MOBILIZATION	L SUM	1
70102640		TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1

- * INDICATES SPECIAL PROVISION
- X INDICATES SPECIALITY ITEM

SUMMARY OF QUANTITIES

CODE NO.	SP	ITEM	UNIT	QUANTITY
72000100		SIGN PANEL - TYPE 1	SQ FT	22
72900100		METAL POST, TYPE A	FT	108
78001180	X	PAINT PAVEMENT MARKING - LINE 24"	FOOT	10
80400100	* X	ELECTRIC SERVICE INSTALLATION	EACH	1
80400200	* X	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1
81000600	X	CONDUIT IN TRENCH, 2" DIA, GALVANIZED STEEL	FOOT	16
81603050	* X	UNIT DUCT, 600V, 3-1C NO.6, 1/C NO.8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	324
81900200	* X	TRENCH AND BACKFILL FOR ELECTRIC WORK	FOOT	285
83600200	* X	LIGHT POLE FOUNDATION, 24" DIA.	FT	20
K0038000	* X	PERENNIAL PLANTS, WETLAND EMERGENT TYPE	UNIT	5
K1005421	* X	SEEDING (SPECIAL)	ACRE	0.25
X0322508	*	PEDESTRIAN TRUSS SUPERSTRUCTURE	SQ FT	669
X0350805	*	FOLD DOWN BOLLARDS	EACH	2
XX005912	*	INSTALLATION OF TRASH RECEPTACLES	EACH	2
XX006345	*	TURBIDITY BARRIER	FOOT	235
XX006937	* X	GROUND ROD, 5/8" DIA. X 10 FT	EACH	3
Z0013798	*	CONSTRUCTION LAYOUT	L SUM	1
XX008109	* X	ELECTRIC SERVICE BOX	EACH	1
XX008110	* X	INSTALL EXISTING LIGHT POLE WITH LUMINAIRE	EACH	2
XX008093	* X	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO.6, 1/C NO.8	FOOT	70

FILE NAME = S:\JUL 0520 - 6599\6599\004\Micro\Sheets\06558004 - Summary.dwg



USER NAME = vanesso	DESIGNED - VLF	REVISED -
PLOT SCALE = 20.0000' / IN.	DRAWN - KAS	REVISED -
PLOT DATE = 5/22/2009	CHECKED - JAR	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	06-00069-00-BR	COOK	26	3
CONTRACT NO. 63217				
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				