

SCHEDULE OF QUANTITIES

MOBILIZATION

LOCATION	LSUM
Jobsite - SN.048-0052	1
TOTAL	1

TEMPORARY CONCRETE BARRIER

LOCATION	FOOT
Sta. 1067+25 to 1071+25	400
TOTAL	400

REINFORCEMENT BARS, EPOXY COATED

LOCATION	POUND
E Abutment & NE Parapet Wall	400
TOTAL	400

EPOXY MARKING - LINE, 4"

LOCATION	FOOT
Sta. 1067+84.5 to 1071+84.0	800
TOTAL	800

TRAFFIC CONTROL & PROTECTION STANDARD 701402

LOCATION	LSUM
Jobsite - SN.048-0052	1
TOTAL	1

PAVEMENT MARKING TAPE TYPE III, 4"

LOCATION	FOOT
☉ along Barrier & Tapers	3150
TOTAL	3150

CONCRETE SUPERSTRUCTURE

LOCATION	CUYD
E Abutment & NE Parapet Wall	4.2
TOTAL	4.2

EROSION CONTROL BLANKET

LOCATION	SQYD
East Abutment & Parapet Wall Shoulder & Shoulder Slope	166.7
TOTAL	166.7

IMPACT ATTENUATORS, TEMPORARY NRD, TEST LEVEL 3

LOCATION	EACH
West end of Temp. Conc. Barrier	1
TOTAL	1

BRIDGE APPROACH PAVEMENT REMOVAL

LOCATION	SQYD
Sta. 1070+85.5 Lt. to 1071+15.5 Lt.	17.2
TOTAL	17.2

BRIDGE APPROACH PAVEMENT

LOCATION	SQYD
Sta. 1070+85.5 Lt. to 1071+15.5 Lt.	17.2
TOTAL	17.2

PAVEMENT MARKING REMOVAL

LOCATION	FOOT
☉ along Barrier & Tapers	800
TOTAL	800

CONCRETE REMOVAL

LOCATION	CUYD
E Abutment & NE Parapet Wall	3.2
TOTAL	3.2

WORKZONE PAVEMENT MARKING REMOVAL

LOCATION	SQFT
Sta. 1067+84.5 to 1071+84	1050
TOTAL	1050

SN.048-0052 I-74
over Spoon Riv.