

SUMMARY OF QUANTITIES

CODE	ITEM	UNIT	100% STATE 1000
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4.2
40600300	AGGREGATE (PRIME COAT)	TON	21
40600990	TEMPORARY RAMP	SQ YD	740
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	780
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	11,100
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	121
48203100	HOT-MIX ASPHALT SHOULDERS	TON	463
64200105	SHOULDER RUMBLE STRIP	FOOT	4,500
67100100	MOBILIZATION	L SUM	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	864
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	5,400
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	440
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	144
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	64
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	64
* X7800620	URETHANE PAVEMENT MARKING - LINE 5"	FOOT	5,400
* X7800640	URETHANE PAVEMENT MARKING - LINE 8"	FOOT	440

***SPECIALTY ITEMS**

FILE NAME =	USER NAME = coxte	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
c:\pwwork\pwwork\COXTE\0134303\06720	S-shr-500.dgn	DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	55	54-4 INT-RS	LOGAN	6	3
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -		CONTRACT NO. 72C95										
	PLOT DATE = May-19-2009 09:22:50AM	DATE -	REVISED -		ILLINOIS FED. AID PROJECT										