

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY J000 80% FED 20% STATE
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	2365	2365
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	2139	2139
20101000	TEMPORARY FENCE	FOOT	517	517
20101100	TREE TRUNK PROTECTION	EACH	100	100
20200100	EARTH EXCAVATION	CU YD	34025	34025
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	239	239
20400800	FURNISHED EXCAVATION	CU YD	3885	3885
20800150	TRENCH BACKFILL	CU YD	432	432
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	36841	36841
* 25000100	SEEDING, CLASS 1	ACRE	0.25	0.25
* 25000210	SEEDING, CLASS 2A	ACRE	4.00	4.00
* 25000310	SEEDING, CLASS 4	ACRE	0.75	0.75
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	595	595
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	595	595
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	595	595
;) 25000750	MOWING	ACRE	15.25	15.25
25000775	SELECTIVE MOWING STAKES	EACH	102	102
* 25100115	MULCH, METHOD 2	ACRE	4.75	4.75
* 25100630	EROSION CONTROL BLANKET	SQ YD	6486	6486
* 25100900	TURF REINFORCEMENT MAT	SQ YD	1705	1705
* 25200110	SODDING, SALT TOLERANT	SQ YD	14531	14531
* 25200200	SUPPLEMENTAL WATERING	UNIT	130.8	130.8
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	12518	12518
28000300	TEMPORARY DITCH CHECKS	EACH	88	88
28000400	PERIMETER EROSION BARRIER	FOOT	10588	10588
28000500	INLET AND PIPE PROTECTION	EACH	55	55
28100107	STONE RIPRAP, CLASS A4	SQ YD	380	380
28100111	STONE RIPRAP, CLASS A6	SQ YD	813	813
28200200	FILTER FABRIC	SQ YD	1194	1194
28500400	ARTICULATED BLOCK REVETMENT MAT	SQ YD	198	198
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	47729	47729
31100920	SUB-BASE GRANULAR MATERIAL, TYPE A 15"	SQ YD	450	450
31100935	SUB-BASE GRANULAR MATERIAL, TYPE A 18"	SQ YD	2474	2474

* SPECIALITY ITEM

;) NON-PARTICIPATING (100% same)

FILE NAME =	USER NAME = cushmanbw	DESIGNED -	REVISED -
or\pwork\PWIDOT\CUSHMANBW\dms34123\d3486cvt.dgn		DRAWN -	REVISED -
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = Fri May 01 12:05:13 2009	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	37R-3	OGLE	345	3
CONTRACT NO. 84788				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				