

SUMMARY OF QUANTITIES

80% FED. 20% STATE
TOTAL
FOOD

ITEM NO.	DESCRIPTION	UNIT	TOTAL	FOOD
31100965	SUB-BASE GRANULAR MATERIAL, TYPE A 24"	SQ YD	611	611
35101400	AGGREGATE BASE COURSE, TYPE B	TON	6943	6943
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	34.5	34.5
40600300	AGGREGATE (PRIME COAT)	TON	29	29
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	342	342
40600990	TEMPORARY RAMP	SQ YD	347	347
40702700	FURNISH PROFILOGRAPH	L SUM	1	1
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	3,384	3,384
42000411	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	SQ YD	37576	37576
42001300	PROTECTIVE COAT	SQ YD	6037	6037
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	196	196
44000100	PAVEMENT REMOVAL	SQ YD	23602	23602
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	132	132
44000300	CURB REMOVAL	FOOT	67	67
44000400	GUTTER REMOVAL	FOOT	831	831
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	122	122
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	426	426
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	305	305
48300410	PORTLAND CEMENT CONCRETE SHOULDERS 9 1/2"	SQ YD	12898	12898
48301000	PROTECTIVE COAT	SQ YD	905	905
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1	1
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1	1
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	EACH	1	1
50100800	REMOVAL OF EXISTING STRUCTURES NO. 6	EACH	1	1
50100900	REMOVAL OF EXISTING STRUCTURES NO. 7	EACH	1	1
50101000	REMOVAL OF EXISTING STRUCTURES NO. 8	EACH	1	1
50200100	STRUCTURE EXCAVATION	CU YD	327	327
50300225	CONCRETE STRUCTURES	CU YD	43.2	43.2
50800105	REINFORCEMENT BARS	POUND	40480	40480
50800515	BAR SPLICERS	EACH	85	85
51202210	FURNISHING SOLDIER PILES (HP SECTION)	FOOT	1629	1629
51202230	FURNISHING SOLDIER PILES (W SECTION)	FOOT	1377	1377
51205200	TEMPORARY SHEET PILING	SQ FT	2168	2168
51500100	NAME PLATES	EACH	7	7

* SPECIALITY ITEM :) NON-PARTICIPATING

FILE NAME =	USER NAME = cushmanbw	DESIGNED -	REVISED -
o:\pwork\PWIDOT\CUSHMANBW\dms34123\d	6486crr.dgn	DRAWN -	REVISED -
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = Fri May 01 12:05:24 2009	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
742	37R-3	OGLE	345	4
CONTRACT NO. 84788				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				