# SUMMARY OF QUANTITIES

80% FED. 20% STATE

| | | | | TOTAL | J000 |
|---|---|---|---|---|---|
| * | 78008200 | POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS | SQ FT | 1080 | 1080 |
| * | 78008210 | POLYUREA PAVEMENT MARKING TYPE I - LINE 4" | FOOT | 18081 | 18081 |
| * | 78008240 | POLYUREA PAVEMENT MARKING TYPE I - LINE 8" | FOOT | 1218 | 1218 |
| * | 78008250 | POLYUREA PAVEMENT MARKING TYPE I - LINE 12" | FOOT | 2069 | 2069 |
| * | 78008270 | POLYUREA PAVEMENT MARKING TYPE I - LINE 24" | FOOT | 158 | 158 |
| * | 78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 602 | 602 |
| | 78200410 | GUARDRAIL MARKERS, TYPE A | EACH | 34 | 34 |
| | 78201000 | TERMINAL MARKER - DIRECT APPLIED | EACH | 5 | 5 |
| * | 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 5743 | 5743 |
| | Z0005400 | BREAKER-RUN CRUSHED STONE | TON | 1506 | 1506 |
| | Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1 | 1 |
| | Z0025500 | FURNISHING AND INSTALLING PROPERTY MARKERS | EACH | 60 | 60 |
| | Z0030250 | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 5 | 5 |
| | Z0030350 | IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 9 | 9 |
| | Z0073400 | TEMPORARY SUPPORT SYSTEM | EACH | 2 | 2 |
| ⊙ | Z0076600 | TRAINEES | HOUR | 1,500 | 1,500 |
| * | A2C022G3 | TREE, CARYA ILLINOINENSIS (PECAN), CONTAINER GROWN, 3-GALLON | EACH | 50 | 50 |
| * | A2C040G3 | TREE, PLATANUS OCCIDENTALIS (SYCAMORE), CONTAINER GROWN, 3-GALLON | EACH | 50 | 50 |
| * | A2C050G3 | TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), CONTAINER GROWN, 3-GALLON | EACH | 50 | 50 |
| * | A2C060G3 | TREE, QUERCUS PALUSTRIS (PIN OAK), CONTAINER GROWN, 3-GALLON | EACH | 75 | 75 |
| * | A2001714 | TREE, ACER SACCHARUM (SUGAR MAPLE), 1-3/4" CALIPER, BALLED AND BURLAPPED | EACH | 26 | 26 |
| * | A2001724 | TREE, ACER SACCHARUM (SUGAR MAPLE), 3" CALIPER, BALLED AND BURLAPPED | EACH | 8 | 8 |
| * | A2006720 | TREE, QUERCUS MACROCARPA (BUR OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED | EACH | 3 | 3 |
| * | A2007114 | TREE, QUERCUS RUBRA (RED OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED | EACH | 25 | 25 |
| * | B2001116 | TREE, CERCIS CANADENSIS (EASTERN REDBUD), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED | EACH | 3 | 3 |
| * | B2004114 | TREE, MALUS PRAIRIFIRE (PRAIRIFIRE CRABAPPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED | EACH | 3 | 3 |
| * | D2002272 | EVERGREEN, PICEA PUNGENS GLAUCA (COLORADO BLUE SPRUCE), 6' HEIGHT, BALLED AND BURLAPPED | EACH | 4 | 4 |
| * | D2003872 | EVERGREEN, THUJA OCCIDENTALIS TECHNY (TECHNY ARBORVITAE), 6' HEIGHT, BALLED AND BURLAPPED | EACH | 50 | 50 |
| | X0321461 | PILLAR REMOVAL | EACH | 4 | 4 |
| * | X0322352 | SEEDING MOBILIZATION | EACH | 3 | 3 |
| | X0323660 | DROP BOX NO. 1 | EACH | 1 | 1 |
| | X0323661 | DROP BOX NO.2 | EACH | 1 | 1 |
| | X0323662 | DROP BOX NO. 3 | EACH | 1 | 1 |
| | X0323663 | DROP BOX NO.4 | EACH | 1 | 1 |
| | X0323664 | DROP BOX NO.5 | EACH | 1 | 1 |

* SPECIALITY ITEM  ⊡) NON-PARTICIPATING  ⊙Y080

| | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| FILE NAME = c:\pw_work\PWIDOT\CUSHMANBW\dms34123\d06486cvr.dgn | USER NAME = cushmanbw | DESIGNED - | REVISED - | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | SUMMARY OF QUANTITIES | F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| | | DRAWN - | REVISED - | | | 742 | 37R-3 | OGLE | 345 | 7 |
| | PLOT SCALE = 50.0000 ' / IN. | CHECKED - | REVISED - | | | | | CONTRACT NO. 84788 | | |
| | PLOT DATE = Fri May 01 12:05:58 2009 | DATE - | REVISED - | | SCALE: SHEET NO. OF SHEETS STA. TO STA. | FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |