

SUMMARY OF QUANTITIES

80% FED 20% STATE

		TOTAL		1000	
*	X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	7000	7000
	X0324548	PRECAST CONCRETE BOX CULVERT END SECTIONS 6' X 3'	EACH	2	2
	X0325519	DRAIN FOR AGGREGATE BASE COURSE	SQ YD	9	9
	X0325666	CORRUGATED STEEL PIPE MULTIPLE END SECTIONS EQUIVALENT DOUBLE ROUND-SIZE 30"	EACH	4	4
	X0325751	DRIVING SOLDIER PILES	F00T	1222	1222
	X0325919	PRECAST CONCRETE BOX CULVERT 7' X 3' (SPECIAL)	F00T	125	125
	X0712400	TEMPORARY PAVEMENT	SQ YD	6638	6638
	X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	6121	6121
	X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1	1
*	X7800610	URETHANE PAVEMENT MARKING-LINE 4"	F00T	20246	20246
*	X7800640	URETHANE PAVEMENT MARKING-LINE 8"	F00T	3437	3437
	XX002030	FLAGSTONE WALL REMOVAL	F00T	23	23
	XX006040	STONE PILLARS TO BE RELOCATED	EACH	2	2
	XX006807	TIMBER RETAINING WALL MODIFICATION	F00T	13	13
	XX007023	STAINING CONCRETE STRUCTURES	SQ YD	181	181
	XX006084	REMOVE EXISTING MONUMENT	EACH	1	1
	XX001607	RETAINING WALL, SPECIAL	SQ FT	4285	4285
	X5400602	PRECAST CONCRETE BOX CULVERT 6' X 2' (SPECIAL)	F00T	77	77