

# SCHEDULE OF QUANTITIES

25100630 EROSION CONTROL BLANKET

20101000 TEMPORARY FENCE

EQDT	LOCATION	REMARKS
122	LT. STA. 633 + 18 TO 634 + 40	Along Harrod property line
217	LT. STA. 666 + 64 TO 667 + 84	Along wetland boundary & construction limits within Existing R.O.W.
178	RT. STA. 37 + 37 TO 39 + 34	Cartwright Ln. - Along Harrod construction limits and temporary easement
517	TOTAL	

20101100 TREE TRUNK PROTECTION

EACH	LOCATION	REMARKS
1	608 + 93 @ 40.1' LT	
1	611 + 0 @ 52.2' LT	
1	611 + 11 @ 52.4' LT	
1	618 + 43 @ 60.4' LT	
1	618 + 53 @ 72.6' LT	
1	637 + 97 @ 68.2' RT	
1	637 + 94 @ 65.6' RT	
1	662 + 20 @ 79.2' LT	
1	662 + 23 @ 100.7' LT	
1	662 + 30 @ 101.5' LT	
1	662 + 31 @ 77.0' LT	
1	662 + 35 @ 84.7' LT	
1	Margaret Fuller Dr. 17 + 54 @ 38.7' LT	
1	Cartwright Ln. 38 + 90 @ 57.4' RT	
1	39 + 26 @ 58.4' RT	
1	Access Rd. "A" 47 + 40 @ 18.49' RT	
1	47 + 55 @ 29.8' RT	
1	48 + 56 @ 44.7' LT	
1	Cultra Rd. 60 + 65 @ 44.3' LT	
1	60 + 65 @ 40.3' LT	
1	60 + 67 @ 47.8' LT	
1	60 + 67 @ 58.1' LT	
1	60 + 76 @ 34.3' LT	
77	Various Locations on Jobsite	Determined by the IDOT Landscape Architect
100	TOTAL	

25000775 SELECTIVE MOWING STAKES

EACH	LOCATION	REMARKS
30	654 + 50 TO 662 + 0	
48	663 + 50 TO 675 + 50	
24	678 + 0 TO 684 + 0	
102	TOTAL	

SO_YD	LOCATION	REMARKS
2	RT. STA. 603 + 8	Concrete Headwall for Pipe Drains
2	RT. STA. 604 + 50	Concrete Headwall for Pipe Drains
2	RT. STA. 607 + 50	Concrete Headwall for Pipe Drains
2	RT. STA. 610 + 50	Concrete Headwall for Pipe Drains
2	LT. STA. 613 + 50	Concrete Headwall for Pipe Drains
772	LT. STA. 615 + 22 TO 622 + 0	Ditch ( 12'x579' )
2	LT. STA. 616 + 0	Concrete Headwall for Pipe Drains
2	LT. STA. 618 + 0	Concrete Headwall for Pipe Drains
2	LT. STA. 620 + 50	Concrete Headwall for Pipe Drains
2	LT. STA. 622 + 0	Concrete Headwall for Pipe Drains
2	RT. STA. 620 + 50	Concrete Headwall for Pipe Drains
420	LT. STA. 623 + 0 TO 626 + 61	Ditch ( 12'x315' )
373	LT. STA. 626 + 61 TO 630 + 50	Ditch ( 12'x280' )
2	RT. STA. 629 + 50	Concrete Headwall for Pipe Drains
2	RT. STA. 631 + 75	Concrete Headwall for Pipe Drains
2	RT. STA. 633 + 0	Concrete Headwall for Pipe Drains
2	LT. STA. 628 + 0	Concrete Headwall for Pipe Drains
2	LT. STA. 629 + 50	Concrete Headwall for Pipe Drains
2	LT. STA. 632 + 0	Concrete Headwall for Pipe Drains
365	LT. STA. 632 + 0 TO 635 + 64	Ditch ( 12'x274' )
2	LT. STA. 634 + 50	Concrete Headwall for Pipe Drains
1341	LT. STA. 635 + 64 TO 647 + 0	Ditch ( 12'x1006' )
2	LT. STA. 636 + 89	Concrete Headwall for Pipe Drains
2	LT. STA. 638 + 89	Concrete Headwall for Pipe Drains
2	RT. STA. 643 + 0	Concrete Headwall for Pipe Drains
2	RT. STA. 646 + 0	Concrete Headwall for Pipe Drains
2	RT. STA. 649 + 0	Concrete Headwall for Pipe Drains
2	RT. STA. 652 + 0	Concrete Headwall for Pipe Drains
2	RT. STA. 654 + 0	Concrete Headwall for Pipe Drains
2	RT. STA. 657 + 0	Concrete Headwall for Pipe Drains
2	RT. STA. 660 + 0	Concrete Headwall for Pipe Drains
2	RT. STA. 663 + 0	Concrete Headwall for Pipe Drains
2	RT. STA. 666 + 0	Concrete Headwall for Pipe Drains
2	RT. STA. 669 + 0	Concrete Headwall for Pipe Drains
2	RT. STA. 672 + 0	Concrete Headwall for Pipe Drains
2	RT. STA. 675 + 0	Concrete Headwall for Pipe Drains
2	RT. STA. 677 + 50	Concrete Headwall for Pipe Drains
496	LT. STA. 655 + 50 TO 659 + 22	Ditch ( 12'x372' )
2	LT. STA. 656 + 50	Concrete Headwall for Pipe Drains
371	LT. STA. 659 + 22 TO 662 + 0	Ditch ( 12'x278' )
2	LT. STA. 659 + 50	Concrete Headwall for Pipe Drains
2	LT. STA. 662 + 50	Concrete Headwall for Pipe Drains
280	LT. STA. 663 + 0 TO 667 + 20	Ditch ( 6'x420' )
287	LT. STA. 667 + 20 TO 671 + 50	Ditch ( 6'x430' )
49	LT. STA. 675 + 50 TO 676 + 23	Ditch ( 6'x73' )
2	LT. STA. 677 + 50	Concrete Headwall for Pipe Drains
600	LT. STA. 679 + 0 TO 683 + 50	Ditch ( 12'x450' )
2	LT. STA. 679 + 39	Concrete Headwall for Pipe Drains
256	RT. STA. 682 + 50 TO 683 + 50	Foreslope ( 23'x100' )
101	RT. STA. 48 + 74 TO 49 + 50	Access Rd. "A" Ditch ( 12'x76' )
109	LT. STA. 48 + 18 TO 49 + 0	Access Rd. "A" Ditch ( 12'x82' )
600	WINTER SHUTDOWN	
6486	TOTAL	

25100900 TURF REINFORCEMENT MAT

SO_YD	LOCATION	REMARKS
28.0	RT. STA. 603 + 74 TO 603 + 97	Outlet of CC&G ( 12'x21' )
276.0	LT. STA. 613 + 15 TO 615 + 22	Outlet of CC&G to AR Culvert 615+22 ( 12'x207' )
52.9	LT. STA. 615 + 22	Drop Box No.1 ( 17'x28' )
64.0	LT. STA. 626 + 61	Drop Box No.2 ( 24'x24' )
60.0	LT. STA. 654 + 30	Drop Box No.4 ( 18'x30' )
50.7	LT. STA. 667 + 20	Drop Box No.5 ( 24'x19' )
249.3	RT. STA. 17 + 63 TO 19 + 50	Margaret Fuller Rd. Ditch ( 12'x187' )
249.3	LT. STA. 17 + 63 TO 19 + 50	Margaret Fuller Rd. Ditch ( 12'x187' )
266.7	RT. STA. 27 + 50 TO 29 + 50	Blackhawk Vista Ditch ( 12'x200' )
200.0	LT. STA. 27 + 50 TO 29 + 50	Blackhawk Vista Ditch ( 12'x150' )
208.0	RT. STA. 37 + 42 TO 39 + 50	Cartwright Ln. ( 12'x156' )
1704.9	TOTAL	