

SCHEDULE OF QUANTITIES

28000400 PERIMETER EROSION BARRIER

EQOT	LOCATION	REMARKS
3644	RT. STA. 603 + 8 TO 638 + 0	
651	RT. STA. 638 + 0 TO 643 + 30	
2134	RT. STA. 643 + 84 TO 661 + 95	
211	LT. STA. 647 + 0 TO 649 + 0	
207	LT. STA. 649 + 51 TO 651 + 42	
103	LT. STA. 651 + 52 TO 652 + 33	
2538	RT. STA. 662 + 27 TO 684 + 50	
200	FOR USE AT CONTRACTOR'S BORROW/WASTE/USE SITE	
900	WINTER SHUTDOWN	
10588	TOTAL	

28000500 INLET AND PIPE PROTECTION

EACH	LOCATION	REMARKS
1	LT. STA. 603 + 37	Inlet
1	LT. STA. 603 + 96	Inlet
1	LT. STA. 604 + 75	Inlet
1	LT. STA. 606 + 50	Inlet
1	LT. STA. 609 + 0	Inlet
1	LT. STA. 611 + 50	Inlet
1	LT. STA. 615 + 22	AR Culvert
1	LT. STA. 616 + 75	Entrance
1	LT. STA. 618 + 81	Entrance
1	LT. STA. 625 + 2	Entrance
1	LT. STA. 626 + 61	AR Culvert
1	LT. STA. 635 + 63	AR Culvert
1	RT. STA. 635 + 64	Inlet
1	LT. STA. 641 + 75	Entrance
1	LT. STA. 651 + 74	Entrance
1	LT. STA. 654 + 30	AR Culvert
1	LT. STA. 659 + 22	AR Culvert
2	LT. STA. 664 + 50	Open back Inlet
2	LT. STA. 666 + 0	Open back Inlet
1	LT. STA. 667 + 20	Inlet
1	LT. STA. 667 + 20	AR Culvert
2	LT. STA. 668 + 50	Open back Inlet
2	LT. STA. 670 + 0	Open back Inlet
2	LT. STA. 671 + 50	Open back Inlet
1	LT. STA. 673 + 50	Inlet
1	LT. STA. 673 + 50	Inlet
2	LT. STA. 675 + 50	Open back Inlet
2	LT. STA. 676 + 23	Open back Inlet
1	LT. STA. 678 + 70	AR Culvert
1	RT. STA. 17 + 3	Margaret Fuller Dr.
1	LT. STA. 17 + 13	Margaret Fuller Dr.
1	LT. STA. 19 + 3	AR Culvert - Margaret Fuller Dr.
1	LT. STA. 28 + 39	Blackhawk Vista
1	RT. STA. 38 + 36	Cartwright Ln.
1	RT. STA. 39 + 51	AR Culvert - Cartwright Ln.
1	RT. STA. 47 + 50	Access Road "A"
1	LT. STA. 47 + 53	Access Road "A"
1	LT. STA. 49 + 0	AR Culvert - Access Road "A"
10	Locations determined by Resident Engineer	Winter Shutdown/ Maintenance Qty.
55	TOTAL	

28100107 STONE RIPRAP, CLASS A4

SQ YD	LOCATION	REMARKS
42.0	RT. STA. 654 + 30	AR Culvert Outlet (18'x21')
47.5	RT. STA. 659 + 22	AR Culvert Outlet (19'x22.5')
45.0	RT. STA. 667 + 20	AR Culvert Outlet (15'x27')
245.9	RT. STA. 678 + 70	AR Culvert Outlet (32'x70') • Quantity duplicated on Culvert Detail Sheet
380.4	TOTAL	

28100111 STONE RIPRAP, CLASS A6

SQ YD	LOCATION	REMARKS
59.7	RT. STA. 615 + 22	AR Culvert Outlet (25'x21.5')
45.4	RT. STA. 626 + 61	AR Culvert Outlet (19'x21.5')
708.3	RT. STA. 634 + 70 TO 637 + 5	Retaining Wall (24.6'x259.6')
813.4	TOTAL	

28200200 FILTER FABRIC

SQ YD	LOCATION	REMARKS
42.0	RT. STA. 654 + 30	AR Culvert Outlet (18'x21')
47.5	RT. STA. 659 + 22	AR Culvert Outlet (19'x22.5')
45.0	RT. STA. 667 + 20	AR Culvert Outlet (15'x27')
245.9	RT. STA. 678 + 70	AR Culvert Outlet (32'x70') • Quantity duplicated on Culvert Detail Sheet
59.7	RT. STA. 615 + 22	AR Culvert Outlet (25'x21.5')
45.4	RT. STA. 626 + 61	AR Culvert Outlet (19'x21.5')
708.3	RT. STA. 634 + 70 TO 637 + 5	Retaining Wall (24.6'x259.6')
1193.8	TOTAL	

28500400 ARTICULATED BLOCK REVETMENT MAT

SQ YD	LOCATION	REMARKS
11.7	LT. STA. 613 + 0 TO 613 + 15	Outlet of CC&G to AR Culvert 615+22 (7'x15')
186.7	LT. STA. 635 + 63	Drop Box No.3 (70'x24')
198.3	TOTAL	

35101400 AGGREGATE BASE COURSE, TYPE B

TON	LOCATION	REMARKS
129	LT. STA. 626 + 61	Temp. Runaround for Staging of AR Culvert 626+61 - STAGE 1
53	LT. STA. 635 + 63	Temp. Runaround for Staging of AR Culvert 635+63 - STAGE 1
90	RT. STA. 635 + 63	Temp. Runaround for Staging of AR Culvert 635+63 - STAGE 1
8	LT/RT 654 + 30	Used to build up existing 3' aggregate shoulders (both sides) for staging
8	LT/RT 659 + 22	Used to build up existing 3' aggregate shoulders (both sides) for staging
6	LT/RT 667 + 20	Used to build up existing 3' aggregate shoulders (both sides) for staging
24	LT/RT 626 + 61 TO 667 + 20	Incidental Quantity for Temporary Patching at the Culverts
317	TOTAL	

40600300 AGGREGATE (PRIME COAT)

TON	LOCATION	REMARKS
19	LT/RT 664 + 0 TO 712 + 36	
9	LT/RT 729 + 37 TO 752 + 50	
29	TOTAL	

40600982 HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT

SQ YD	LOCATION	REMARKS
67	LT/RT 664 + 0 TO 664 + 25	(24'W x 25' L) STAGE 1 SMART Resurfacing
75	LT/RT 682 + 75 TO 683 + 0	(27'W x 25' L) STAGE 3 COMPLETED
67	LT/RT 712 + 11 TO 712 + 36	(24'W x 25' L) STAGE 1 SMART Resurfacing
67	LT/RT 729 + 37 TO 729 + 62	(24'W x 25' L) STAGE 1 SMART Resurfacing
67	LT/RT 752 + 25 TO 752 + 50	(24'W x 25' L) STAGE 1 SMART Resurfacing
342	TOTAL	

40600990 TEMPORARY RAMP

SQ YD	LOCATION	REMARKS
13	LT/RT 664 + 0	STAGE 1
41	LT 676 + 41	STAGE 1 Stronghold Entrance
20	LT 704 + 35	STAGE 1 CE
21	LT 705 + 81	STAGE 1 CE
13	LT/RT 712 + 36	STAGE 1
13	LT/RT 729 + 37	STAGE 1
162	RT 750 + 11	STAGE 1 MB
50	LT 750 + 69	STAGE 1 PE
13	LT/RT 752 + 50	STAGE 1
347	TOTAL	

42001300 PROTECTIVE COAT

SQ YD	LOCATION	REMARKS
1412	618 + 0 TO 628 + 29	STAGE 9 - MAINLINE
4626	628 + 29 TO 673 + 0	STAGE 10 - TEMPORARY PAVEMENT
6037	TOTAL	