

SCHEDULE OF QUANTITIES

ITEM NO.	DESCRIPTION	SQ. YD.	LOCATION	REMARKS
42001300	PROTECTIVE COAT			
		1412	618 + 0 TO	628 + 29
		4626	628 + 29 TO	673 + 0
		6037	TOTAL	
44000100	PAVEMENT REMOVAL			
		23602	LT/RT 603 + 8 TO	680 + 0
		23602	TOTAL	
44000300	CURB REMOVAL			
		67	LT. STA. 603 + 44 TO	249 + 0
		67	TOTAL	
44000400	GUTTER REMOVAL			
		831	LT. STA. 604 + 10 TO	612 + 41
		831	TOTAL	
44000500	COMBINATION CURB AND GUTTER REMOVAL			
		49	LT. STA. 603 + 8 TO	603 + 44
		73	RT. STA. 603 + 8 TO	603 + 80
		122	TOTAL	
44201759	CLASS D PATCHES, TYPE IV, 9 INCH			
		94	CL 626 + 61	AR Culvert at Sta. 626+61 (done under flaggers)
		91	CL 635 + 63	AR Culvert at Sta. 635+63 (done under flaggers)
		81	CL 654 + 30	AR Culvert at Sta. 654+30 (done under flaggers)
		97	CL 659 + 22	AR Culvert at Sta. 659+22 (done under flaggers)
		62	CL 667 + 20	AR Culvert at Sta. 667+20 (done under flaggers)
		426	TOTAL	
48301000	PROTECTIVE COAT			
		905	LT/RT 618 + 0 TO	628 + 29
		905	TOTAL	
50100300	REMOVAL OF EXISTING STRUCTURES NO.1			
		1	LT/RT 615 + 22	4x4 Concrete Box Culvert • Quantity duplicated on Culvert Detail Sheet
		1	TOTAL	
50100400	REMOVAL OF EXISTING STRUCTURES NO.2			
		1	LT/RT 626 + 61	10x6 Concrete Box Culvert • Quantity duplicated on Culvert Detail Sheet
		1	TOTAL	

ITEM NO.	DESCRIPTION	EACH	LOCATION	REMARKS
50100500	REMOVAL OF EXISTING STRUCTURES NO.3			
		1	LT/RT 635 + 63	5x4 Concrete Box Culvert • Quantity duplicated on Culvert Detail Sheet
		1	TOTAL	
50100600	REMOVAL OF EXISTING STRUCTURES NO.4			
		1	LT/RT 654 + 30	7x2.5 Concrete Box Culvert
		1	TOTAL	
50100700	REMOVAL OF EXISTING STRUCTURES NO.5			
		1	LT/RT 659 + 22	4x2 Concrete Box Culvert • Quantity duplicated on Culvert Detail Sheet
		1	TOTAL	
50100800	REMOVAL OF EXISTING STRUCTURES NO.6			
		1	LT/RT 667 + 20	30" Round Concrete Pipe Culvert
		1	TOTAL	
50100900	REMOVAL OF EXISTING STRUCTURES NO.7			
		1	LT/RT 677 + 98	12x3 Concrete Box Culvert • Quantity duplicated on Culvert Detail Sheet
		1	TOTAL	
50101000	REMOVAL OF EXISTING STRUCTURES NO.8			
		1	LT/RT 618 + 62	24" CMP w/ Drop Structure
		1	TOTAL	
51205200	TEMPORARY SHEET PILING			
		578.4	615 + 22	AR Culvert
		268.2	677 + 98	AR Culvert - Removal of Existing
		1321.8	678 + 70	AR Culvert
		2168.4	TOTAL	
51500100	NAME PLATES			
		1	615 + 22	• Quantity duplicated on Culvert Detail Sheet
		1	626 + 61	
		1	635 + 63	
		1	654 + 30	
		1	659 + 22	
		1	667 + 20	
		1	678 + 70	
		7	TOTAL	
54205305	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL, EQUIVALENT ROUND SIZE 30"			
		146	LT/RT 19 + 44	Margaret Fuller Rd. Cartwright Ln. Access Road A (AR Culvert)
		101	LT/RT 39 + 44	
		184	LT/RT 49 + 25	
		431	TOTAL	