

# SCHEDULE OF QUANTITIES

SO	ET	LOCATION	REMARKS
Stage 2 (Sta. 673+00 - 680+00)			
437.2	LT. STA.	670 + 94 TO 684 + 6	Edge Line
109.3	CL	670 + 94 TO 684 + 6	Skips
338.2	CL	670 + 94 TO 681 + 9	No passing Line
198.1	CL	681 + 9 TO 684 + 6	Centerline Dbl. Yellow
68.6	RT. STA.	670 + 94 TO 673 + 0	Edge Line
135.3	RT. STA.	680 + 0 TO 684 + 6	Edge Line
Stage 3 (Sta. 673+00 - 680+00)			
15.7	CL	669 + 6 TO 670 + 94	Skips
62.7	CL	669 + 6 TO 670 + 94	No passing Line
62.7	RT. STA.	669 + 6 TO 670 + 94	Edge Line
Stage 4 (Sta. 603+08 - 611+00)			
92.8	LT. STA.	600 + 54 TO 603 + 32	Edge Line
327.8	LT. STA.	604 + 10 TO 613 + 93	Edge Line
42.4	CL	600 + 54 TO 603 + 8	Centerline Dbl. Yellow
48.9	CL	611 + 0 TO 613 + 93	Centerline Dbl. Yellow
Stage 5 (Sta. 603+08 - 611+00)			
84.8	RT. STA.	600 + 54 TO 603 + 8	Edge Line
97.8	RT. STA.	611 + 0 TO 613 + 93	Edge Line
Stage 6 (Sta. 611+00 - 618+00)			
135.6	RT. STA.	613 + 93 TO 618 + 0	Edge Line
89.2	RT. STA.	618 + 0 TO 620 + 68	Edge Line
56.0	CL	613 + 93 TO 615 + 61	No passing Line
33.9	CL	613 + 93 TO 618 + 0	Skips
22.3	CL	618 + 0 TO 620 + 68	Skips
Stage 7 (Sta. 611+00 - 618+00)			
102.2	LT. STA.	618 + 0 TO 621 + 6	Edge Line
3.2	CL	620 + 68 TO 621 + 6	Skips
13.0	RT. STA.	620 + 68 TO 621 + 6	Edge Line
Stage 8 (Sta. 618+00 - 628+29)			
412.4	LT. STA.	621 + 6 TO 633 + 44	Edge Line
106.3	CL	620 + 68 TO 633 + 44	Skips
412.4	RT. STA.	621 + 6 TO 633 + 44	Edge Line
Stage 11 (Sta. 628+29 - 673+00)			
485.4	LT. STA.	633 + 44 TO 648 + 0	Edge Line
329.7	CL	633 + 44 TO 673 + 0	Skips
100.3	CL	669 + 99 TO 673 + 0	No passing Line
1318.8	RT. STA.	633 + 44 TO 673 + 0	Edge Line
5743.0	TOTAL		

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION	REMARKS
1	RT. STA. 680 + 0	Stage #1 (Sta. 603+08 to 683+00)
1	RT. STA. 681 + 88	Stage #2 (Sta. 673+00 to 680+00)
1	RT. STA. 675 + 63	Stage #3 (Sta. 673+00 to 680+00) --- Narrow Setup
1	RT. STA. 677 + 25	Stage #3 (Sta. 673+00 to 680+00) --- Narrow Setup
1	LT. STA. 614 + 20	Stage #7 (Sta. 611+00 to 618+00) --- Narrow Setup
5	TOTAL	

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION	REMARKS
1	LT. STA. 672 + 50	Stage #2 (Sta. 673+00 to 680+00)
1	LT. STA. 671 + 0	Stage #3 (Sta. 673+00 to 680+00)
1	LT. STA. 680 + 99	Stage #3 (Sta. 673+00 to 680+00)
1	RT. STA. 608 + 50	Stage #4 (Sta. 603+08 TO 611+00) --- Narrow Setup
1	RT. STA. 614 + 20	Stage #6 (Sta. 611+00 to 618+00)
1	RT. STA. 616 + 20	Stage #6 (Sta. 611+00 to 618+00)
1	RT. STA. 615 + 50	Stage #7 (Sta. 611+00 to 618+00) --- Narrow Setup
1	LT. STA. 616 + 20	Stage #7 (Sta. 611+00 to 618+00) --- Narrow Setup
1	RT. STA. 627 + 0	Stage #9 (Sta. 618+00 to 628+29) --- Narrow Setup
9	TOTAL	

Z0073400 TEMPORARY SUPPORT SYSTEM

EACH	LOCATION	REMARKS
1	LT. STA. 626 + 61	Stage #1 (If needed per Inspection)
1	LT. STA. 677 + 98	Stage #2 for Sta. 678+03
2	TOTAL	

X0321461 PILLAR REMOVAL

EACH	LOCATION	REMARKS
1	LT. STA. 618 + 71	22' LT Pillar at Property Corner
1	LT. STA. 622 + 40	23' LT Pillar at PE with light
1	LT. STA. 622 + 63	23' LT Pillar at PE with light
1	LT. STA. 624 + 69	21' LT Pillar at Property Corner
4	TOTAL	

X0325519 DRAIN FOR AGGREGATE BASE COURSE

SO	YD	LOCATION	REMARKS
0.67	LT. STA.	626 + 89	See District Std. (96.4)
2.33	RT. STA.	626 + 89	See District Std. (96.4)
0.67	LT. STA.	635 + 89	See District Std. (96.4)
1.00	LT. STA.	640 + 89	See District Std. (96.4)
0.67	LT. STA.	642 + 25	See District Std. (96.4)
3.33	LT. STA.	680 + 0	See District Std. (96.4)
0.06	LT. STA.	18 + 76	Margaret Fuller Rd.
0.06	RT. STA.	18 + 76	Margaret Fuller Rd.
0.06	LT. STA.	28 + 92	Blackhawk Vista
0.06	RT. STA.	28 + 92	Blackhawk Vista
0.06	LT. STA.	38 + 87	Cartwright Ln.
0.06	RT. STA.	38 + 87	Cartwright Ln.
9.05	TOTAL		

X0325666 CORRUGATED STEEL PIPE MULTIPLE END SECTIONS, EQUIVALENT, DOUBLE, ROUND SIZE 30"

EACH	LOCATION	REMARKS
2	LT/RT 49 + 25	Access Rd. A (AR culvert)
2	TOTAL	

FLAGSTONE WALL REMOVAL

EQOT	LOCATION	REMARKS
23	LT. STA. 654 + 17	52' LT The Silo
23	TOTAL	

STONE PILLARS TO BE RELOCATED

EACH	LOCATION	REMARKS
1	LT. STA. 618 + 45	Cemetery Entrance (Concrete & Block) Pillars at PE
1	LT. STA. 618 + 63	Cemetery Entrance (Concrete & Block) Pillars at PE
2	TOTAL	

TIMBER RETAINING WALL MODIFICATION

EQOT	LOCATION	REMARKS
13	LT. STA. 611 + 91	20.9' LT Along South side of Private Entrance 612+05 LT
13	TOTAL	

REMOVE EXISTING MONUMENT

EACH	LOCATION	REMARKS
1	LT. STA. 618 + 95	19' LT Honor Monument for Ogle County Soldiers & Sailors
1	TOTAL	