

ENTRANCE SCHEDULE

Location	Remarks	Existing Surface past R.O.W.	Throat Width	Area	40600200	40800050	44000200	42300300	35101400	35101400			54205905	X0325666	54200220	54213450
					Bituminous Materials Prime Coat	Incidental Hot-Mix Asphalt Surfacing	Driveway Pavement Removal	PCC Driveway PAVT 7"	Aggregate Base Course Type B	Aggregate Base Course Type B (Temp Access)			Pipe Culverts, Type 1, Corrugated Steel, EQRS 30"	CSPMES Equiv. Double Round Size 30"	Pipe Culverts, Class D, Type 1 15"	End Sections 15"
					Ton	Ton	SQ YD	SQ YD	Ton	(PE) Ton	(CE) Ton	(FE) Ton	Foot	Each	Foot	Each
					Foot	SQ YD	Ton	Ton	Ton	Ton	Ton	Ton	Foot	Each	Foot	Each
IL 2																
Lt Sta 610 + 73 PE		Concrete	19	66.7			66.7	66.7			30.5					
Lt Sta 612 + 5 PE		HMA	20	22.6	0.01	3.2		30.9	10.3	24.5						
Lt Sta 616 + 50 FE		Aggregate	24	97.4	0.06	13.6			44.6			44.6			52	2
Lt Sta 618 + 56 PE		Conc.w/ HMA Overlay	12	65.2	0.04	9.1	65.2		29.9	29.9					46	2
Lt Sta 622 + 53 PE		HMA	13	65.7	0.04	9.2			30.1	30.1						
Rt Sta 637 + 93 PE		HMA	10	132.0	0.08	18.5			60.4	60.4						
Lt Sta 641 + 57 PE		HMA	12	241.7	0.14	33.8			110.6	110.6			76		2	
Lt Sta 649 + 25 CE		HMA	24	257.3	0.15	36.0			117.8		117.8					
Lt Sta 651 + 36 PE		Aggregate	13	84.1	0.05	11.8			38.5	38.5					58	2
Lt Sta 652 + 37 PE		Aggregate	12	56.0	0.03	7.8			25.6	25.6						
Lt Sta 652 + 76 CE		HMA	30	92.1	0.05	12.9			42.2		42.2					
Lt Sta 653 + 91 CE		HMA	32	100.8	0.06	14.1			46.1		46.1					
Lt Sta 654 + 98 PE		Aggregate	12	62.1	0.04	8.7			28.4	28.4						
Lt Sta 662 + 71 PE		Aggregate	16	159.6	0.09	22.3			73.0	73.0						
Rt Sta 670 + 56 FE	Prop HMA to ExROW	Grass	24	280.0	0.05	13.1			128.2			128.2				
Slideroad Entrances																
Rt Sta 17 + 33 PE	Margaret Fuller Dr.	HMA	29	109.6	0.06	15.3			50.2	50.2					56	2
Lt Sta 17 + 38 PE	Margaret Fuller Dr.	HMA	15	88.8	0.05	12.4			40.6	40.6					124	2
Lt Sta 18 + 00 PE	Margaret Fuller Dr.	Concrete	24	98.0				98.0		44.9						
Lt Sta 28 + 64 PE	Blackhawk Vista	HMA	18	127.2	0.07	17.8			58.2	58.2					50	2
Lt Sta 37 + 93 PE	Cartwright Ln.	HMA	12	82.3	0.05	11.5			37.7	37.7						
Rt Sta 38 + 60 PE	Cartwright Ln.	HMA	18	144.1	0.08	20.2			66.0	66.0					52	2
Rt Sta 47 + 75 PE	Access Road A	Aggregate	11	57.9	0.03	8.1			26.5	26.5						
Lt Sta 47 + 86 CE	Access Road A	Aggregate	35	118.6	0.07	16.6			54.3		54.3				66	2
Rt Sta 48 + 12 PE	Access Road A	HMA	31	83.2	0.05	11.7			38.1	38.1					124	2
Sta 70 + 83 PE	Proposed Boat Ramp	Grass	20	214.3					98.1	98.1						
Subtotal				2907.2	1.3	327.9	131.9	195.6	1255.6	912.0	260.4	172.8				
Total				2907.2	1.3	327.9	131.9	195.6	2600.8				76	2	628	18