

PAVEMENT MARKING SCHEDULE

LOCATION	LT / RT	REMARKS	LENGTH (FT)	78008210	78008210	78008240	78008250	78008250	78008270	78008200	X7800610	X7800610	X7800640	70300625	70300660	70300610
				POLYUREA PVT. MARKING TYPE 1 - LINE 4" (WHITE) (FT)	POLYUREA PVT. MARKING TYPE 1 - LINE 4" (YELLOW) (FT)	POLYUREA PVT. MARKING TYPE 1 - LINE 8" (WHITE) (FT)	POLYUREA PVT. MARKING TYPE 1 - LINE 12" (YELLOW) (FT)	POLYUREA PVT. MARKING TYPE 1 - LINE 12" (WHITE) (FT)	POLYUREA PVT. MARKING TYPE 1 - LINE 24" (WHITE) (FT)	POLYUREA PVT. MARKING TYPE 1 - LINE 24" (WHITE) (FT)	POLYUREA PVT. MARKING TYPE 1 - LINE 24" (WHITE) (FT)	POLYUREA PVT. MARKING TYPE 1 - LINE 24" (WHITE) (FT)	POLYUREA PVT. MARKING TYPE 1 - LETTERS & SYMBOLS (SQ FT)	URETHANE PVT. MARKING, LINE 4" (WHITE) (FT)	URETHANE PVT. MARKING, LINE 4" (YELLOW) (FT)	URETHANE PVT. MARKING, LINE 8" (WHITE) (FT)
WINTER SHUTDOWN QUANTITIES																
662 + 59 to 665 + 9	LT	MEDIAN OUTSIDE LINES	500										500			
665 + 9 to 673 + 21	LT	MEDIAN OUTSIDE LINES	1628		1628											
673 + 21 to 675 + 83	LT	MEDIAN OUTSIDE LINES	525										525			
	LT	MEDIAN INSIDE LINES	1358		1358											
	LT	MEDIAN DIAGONALS	310				310									
662 + 59 to 665 + 9	LT	TURN BAY LINE (CULTRA RD.)	250										250			
662 + 79	LT	LT. TURN ARROWS	-							15.6						
663 + 49	LT	LT. TURN ARROWS	-							15.6						
664 + 19	LT	LT. TURN ARROWS	-							15.6						
664 + 89	LT	LT. TURN ARROWS	-							15.6						
673 + 21 to 675 + 83	LT	TURN BAY LINE (STRONGHOLD)	262										262	262		
673 + 41	LT	LT. TURN ARROWS	-							15.6						15.6
674 + 11	LT	LT. TURN ARROWS	-							15.6						15.6
674 + 81	LT	LT. TURN ARROWS	-							15.6						15.6
675 + 51	LT	LT. TURN ARROWS	-							15.6						15.6
673 + 21 to 675 + 83	RT	TURN BAY LINE (BOAT RAMP)	262										262	262		
673 + 41	RT	RT. TURN ARROWS	-							15.6						15.6
674 + 11	RT	RT. TURN ARROWS	-							15.6						15.6
674 + 81	RT	RT. TURN ARROWS	-							15.6						15.6
675 + 51	RT	RT. TURN ARROWS	-							15.6						15.6
677 + 5 to 680 + 00	LT	DOUBLE YELLOW	295										590		590	
677 + 5 to 679 + 85	LT	TURN BAY LINE (F. BOAT RAMP)	280										280	280		
679 + 85 to 680 + 00	LT	TURKEY TRACKS	15										4	4		
677 + 29	LT	LT. TURN ARROWS	-							15.6						15.6
678 + 5	LT	LT. TURN ARROWS	-							15.6						15.6
678 + 96	LT	LT. TURN ARROWS	-							15.6						15.6
679 + 66	LT	LT. TURN ARROWS	-							15.6						15.6
677 + 5 to 679 + 85	LT	TURN BAY LINE (STRONGHOLD)	280										280	280		
679 + 85 to 680 + 00	LT	TURKEY TRACKS	15										4	4		
677 + 29	LT	RT. TURN ARROWS	-							15.6						15.6
678 + 5	LT	RT. TURN ARROWS	-							15.6						15.6
678 + 96	LT	RT. TURN ARROWS	-							15.6						15.6
679 + 66	LT	RT. TURN ARROWS	-							15.6						15.6
680 + 00 to 684 + 6	LT	DOUBLE YELLOW	406												1624	
680 + 00 to 682 + 24	LT	TURKEY TRACKS	224												116	
680 + 00 to 681 + 38	LT	TURKEY TRACKS	138												72	
Subtotal				4,469	13,612		1,296	773			13,670	6,576				
TOTAL				18,081		1,218	2,069		158	1,080	20,246	3,437	49,410	70		343

FILE NAME =	USER NAME = perkinsdr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT MARKING SCHEDULE	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -			742	37R-3	OGLE	345	48	
	PLOT SCALE = 50,0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 84788					
	PLOT DATE = Mon Jun 08 11:19:09 2009	DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.