


STATION TO STATION	SIDEWALK REMOVAL SQ. FT.	PORTLAND CEMENT CONCRETE SIDEWALK 4" SQ. FT.	DETECTABLE WARNINGS SQ. FT.	COMBINATION CURB AND GUTTER REMOVAL FOOT	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.18 FOOT	MANHOLES TO BE ADJUSTED EACH
ASH STREET - LT 22+57 - 25+80	1425	1425	6	7	7	
LT 25+80 - 28+72	1270	1270				
LT 28+72 - 32+04	1336	1420				
LT 32+04 - 35+07		580				
LT 35+07 - 40+31	975	2325	30	38	38	
LT 40+31 - 44+54	1270	2107	12	14	14	1
LT 44+54 - 45+04	100	175	6	10	10	
ASH STREET - RT 21+76 - 29+62	3625	3625				
RT 29+62 - 32+95	1678	1546	12	17	17	
RT 32+95 - 36+48	1590	1590	6	7	7	
RT 36+48 - 38+09	558	620	6	7	7	
RT 38+09 - 44+54	650	2820	6	10	10	1
RT 44+54 - 44+90	112	140	12	17	17	
MISC ENTRANCES/CONTINGENCIES	200	200		23	23	
<b>TOTAL</b>	<b>14789</b>	<b>19843</b>	<b>96</b>	<b>150</b>	<b>150</b>	<b>2</b>

TRAFFIC CONTROL AND PROTECTION	
LOCATION	L. SUM
ASH STREET	
STANDARD 701501	1.0
ASH STREET	
STANDARD 701801	1.0

MOBILIZATION	
LOCATION	L. SUM
ASH STREET PROJECT	1
<b>TOTAL</b>	<b>1</b>

DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	
LOCATION	SQ YD
LT. STA 42+42	30
RT. STA 42+73	30
<b>TOTAL</b>	<b>60</b>

		1670 EAST ASH STREET CANTON, ILLINOIS 61520 PH. (309) 647-7851 FAX (309) 647-6155
<b>TABULATIONS</b>		
FOR: <b>CITY OF CANTON, ILLINOIS</b>		
REVISIONS	DATE <u>04/30/09</u>	PROJECT NO. <u>247-09001</u>
DESIGNED <u>GBM</u>	CHECKED <u>-</u>	DRAWING NO.
CHECKED <u>-</u>	DRAWN <u>NDP</u>	
FIELD BK.	CHECKED <u>GBM</u>	SHEET <u>4</u> OF <u>6</u>