

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT			40600982	
LOCATION	OFFSET FEET	WIDTH FEET	AREA SQ FT	AREA SQ YDS
MARIETTA AVE, LT	62.00	VAR	1683.0	187.0
MARIETTA AVE, RT	59.00	VAR	482.8	53.6
KELLY AVE, LT	41.50	VAR	621.3	69.0
KELLY AVE, RT	52.00	VAR	1183.8	131.5
SIEBERLING AVE, LT	48.00	VAR	1122.3	124.7
SIEBERLING AVE, RT	39.30	VAR	523.7	58.2
DURYEA AVE, LT	53.30	VAR	868.0	96.4
DURYEA AVE, RT	50.30	VAR	784.0	87.1
SAMUEL AVE, LT	53.30	VAR	904.4	100.5
SAMUEL AVE, RT	51.00	VAR	806.4	89.6
ALLEY	50.00	VAR	346.7	38.5
GLEN AVE, LT	91.00	VAR	3191.3	354.6
GLEN AVE, RT	57.00	VAR	1248.2	138.7
KINGMAN AVE	48.00	VAR	827.8	92.0
GRANDVIEW DR	58.00	VAR	1345.0	149.4
TOTAL			15938.7	1771.0

TEMPORARY RAMP			40600990	
LOCATION	LENGTH FEET	WIDTH FEET	AREA SQ FT	AREA SQ YDS
PROSPECT SOUTH	67	5	337.2	
MARIETTA AVE. WEST	40	5	22.2	
MARIETTA AVE. EAST	27	5	15.0	
KELLY AVE. WEST	50	5	27.8	
KELLY AVE. EAST	35	5	19.4	
SEIBERLING AVE. WEST	38	5	21.1	
SEIBERLING AVE. EAST	34	5	18.9	
DURYEA AVE. WEST	30	5	16.7	
DURYEA AVE. EAST	28	5	15.6	
SAMUEL AVE. WEST	30	5	16.7	
SAMUEL AVE. EAST	28	5	15.6	
ALLEY STA. 36+75	12	5	6.7	
GLEN AVE. WEST	40	5	22.2	
GLEN AVE. EAST	33	5	18.3	
KINGMAN AVE.	28	5	15.6	
GRANDVIEW DR.	28	5	15.6	
PROSPECT NORTH	42	5	23.3	
TOTAL		TOTAL	327.8	

TEMPORARY RUBBER RAMPS FOR DRAINAGE AND UTILITY CASTINGS		X0325675
LOCATION STATION	ITEM EACH	
24+81, 0' RT	1	
35+03, 37' RT	1	
40+27, 32' RT	1	
TOTAL	3.0	

PCC SURFACE REM. - BUTT JOINT		40600985
LOCATION	SQ. YDS.	
SEIBERLING AVE. WEST END	133.2	
TOTAL	133.2	

DETECTOR LOOP, TYPE 1		88600100
LOCATION	AREA FEET	
KELLY AVE (SOUTH APPROACH)	200.0	
KELLY AVE (EAST APPROACH)	180.0	
KELLY AVE (NORTH APPROACH)	200.0	
SEIBERLING AVE (SOUTH APPROACH)	100.0	
GLEN AVE (SOUTH APPROACH)	200.0	
GLEN AVE (EAST APPROACH)	185.0	
GLEN AVE (WEST APPROACH)	250.0	
TOTAL	1315.0	

PARTIAL DEPTH PATCHING		X0556100
LOCATION	SQ. YDS.	
SEIBERLING AVE. WEST END	122.4	
TOTAL	122.4	

MANHOLE ADJUSTING RING		60257700
LOCATION	EACH	
SEIBERLING AVE. WEST END	1.0	
TOTAL	1.0	

BITUMINOUS PAVING SCHEDULE					40603535	40600115	40600300
					POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D" N50	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIMECOAT)
LOCATION	LENGTH FEET	WIDTH FEET	AREA SQ FT	AREA SQ YDS	WEIGHT TONS	VOLUME GALLONS	WEIGHT TONS
STA. 21+71.00 TO STA. 22+63.92	133.37	VAR	6229.0	692.1	58.1	69.2	0.7
STA. 22+63.92 TO STA. 24+67.20	203.28	63	12806.6	1423.0	119.5	142.3	1.4
STA. 24+67.20 TO STA. 25+90.81	123.61	VAR	7516.0	835.1	70.1	83.5	0.8
STA. 25+90.81 TO STA. 28+02.78	211.97	73	15473.8	1719.3	144.4	171.9	1.7
STA. 28+02.78 TO STA. 29+17.58	114.80	VAR	6202.0	689.1	57.9	68.9	0.7
STA. 29+17.58 TO STA. 31+45.21	227.63	64	14568.3	1618.7	136.0	161.9	1.6
STA. 31+45.21 TO STA. 32+25.43	80.22	VAR	4423.0	491.4	41.3	49.1	0.5
STA. 32+25.43 TO STA. 34+66.40	240.97	64	15422.1	1713.6	143.9	171.4	1.7
STA. 34+66.40 TO STA. 35+61.47	95.07	VAR	5301.0	589.0	49.5	58.9	0.6
STA. 35+61.47 TO STA. 36+41.84	80.37	72	5786.6	643.0	54.0	64.3	0.6
STA. 36+41.84 TO STA. 36+97.68	55.84	VAR	3764.0	418.2	35.1	41.8	0.4
STA. 36+97.68 TO STA. 37+88.28	90.60	65	5889.0	654.3	55.0	65.4	0.7
STA. 37+88.28 TO STA. 39+03.81	115.53	VAR	7228.2	803.1	67.5	80.3	0.8
STA. 39+03.81 TO STA. 41+50.78	246.97	74	18275.8	2030.6	170.6	203.1	2.0
STA. 41+50.78 TO STA. 42+34.10	83.32	VAR	4475.0	497.2	41.8	49.7	0.5
MARIETTA AVE, LT (BUTT JT)	VAR.	VAR.	1683.0	187.0	15.7	18.7	0.2
MARIETTA AVE, RT (BUTT JT)	VAR.	VAR.	482.8	53.6	4.5	5.4	0.1
KELLY AVE, LT (BUTT JT)	VAR.	VAR.	621.3	69.0	5.8	6.9	0.1
KELLY AVE, RT (BUTT JT)	VAR.	VAR.	1183.8	131.5	11.0	13.2	0.1
SIEBERLING AVE, LT (BUTT JT)	VAR.	VAR.	1122.3	124.7	10.5	12.5	0.1
SEIBERLING AVE, LT (PCC)	125.00	40	5000.0	555.6	46.7	55.6	0.6
SIEBERLING AVE, RT (BUTT JT)	VAR.	VAR.	523.7	58.2	4.9	5.8	0.1
DURYEA AVE, LT (BUTT JT)	VAR.	VAR.	868.0	96.4	8.1	9.6	0.1
DURYEA AVE, RT (BUTT JT)	VAR.	VAR.	784.0	87.1	7.3	8.7	0.1
SAMUEL AVE, LT (BUTT JT)	VAR.	VAR.	904.4	100.5	8.4	10.0	0.1
SAMUEL AVE, RT (BUTT JT)	VAR.	VAR.	806.4	89.6	7.5	9.0	0.1
ALLEY	VAR.	VAR.	346.7	38.5	3.2	3.9	0.0
GLEN AVE, LT (BUTT JT)	VAR.	VAR.	3191.3	354.6	29.8	35.5	0.4
GLEN AVE, RT (BUTT JT)	VAR.	VAR.	1248.2	138.7	11.6	13.9	0.1
KINGMAN AVE	VAR.	VAR.	827.8	92.0	7.7	9.2	0.1
GRANDVIEW DR	VAR.	VAR.	1345.0	149.4	12.6	14.9	0.1
TOTAL			17144.3	1440.1		1714.4	17.1

HOT-MIX ASPHALT SURFACE REMOVAL - 1.5"				
STATION TO STATION	LENGTH FEET	WIDTH FEET	AREA SQ FT	AREA SQ YDS
STA. 21+71.00 TO STA. 22+63.92	133.37	VAR	6229.0	692.1
STA. 22+63.92 TO STA. 24+67.20	203.28	63	12806.6	1423.0
STA. 24+67.20 TO STA. 25+90.81	123.61	VAR	7516.0	835.1
STA. 25+90.81 TO STA. 28+02.78	211.97	73	15473.8	1719.3
STA. 28+02.78 TO STA. 29+17.58	114.80	VAR	6202.0	689.1
STA. 29+17.58 TO STA. 31+45.21	227.63	64	14568.3	1618.7
STA. 31+45.21 TO STA. 32+25.43	80.22	VAR	4423.0	491.4
STA. 32+25.43 TO STA. 34+66.40	240.97	64	15422.1	1713.6
STA. 34+66.40 TO STA. 35+61.47	95.07	VAR	5301.0	589.0
STA. 35+61.47 TO STA. 36+41.84	80.37	72	5786.6	643.0
STA. 36+41.84 TO STA. 36+97.68	55.84	VAR	3764.0	418.2
STA. 36+97.68 TO STA. 37+88.28	90.60	65	5889.0	654.3
STA. 37+88.28 TO STA. 39+03.81	115.53	VAR	7228.2	803.1
STA. 39+03.81 TO STA. 41+50.78	246.97	74	18275.8	2030.6
STA. 41+50.78 TO STA. 42+34.10	83.32	VAR	4475.0	497.2
TOTAL			14817.83	


CLASS D PATCHING, 10 INCH			
THE FOLLOWING QUANTITIES ARE CONTINGENT QUANTITIES			
44201761	44201765	44201769	44201771
CLASS D PATCHES, TYPE I, 10 INCH	CLASS D PATCHES, TYPE II, 10 INCH	CLASS D PATCHES, TYPE III, 10 INCH	CLASS D PATCHES, TYPE IV, 10 INCH
SQ YD	SQ YD	SQ YD	SQ YD
50.0	50.0	50.0	50.0
50.0	50.0	50.0	50.0

STAMPED ASPHALT CROSSWALK		PAY ITEM XX005972	
		AREA	
LOCATION		SQ FT	SQ YDS
MARIETTA AVE		1169.0	129.9
KELLY AVE		1930.0	214.4
SIEBERLING AVE		1574.0	174.9
DURYEA AVE		1395.0	155.0
SAMUEL AVE		1520.0	168.9
GLEN AVE		2112.0	234.7
TOTAL		9700.0	1077.8

LOCATION	THERMOPLASTIC PAVEMENT MARKING										TEMPORARY	
	4" WHITE SKIP DASH (FEET)	4" SOLID WHITE (FEET)	4" WHITE LONGITUDINAL PARKING STRIPE (FEET)	4" WHITE TRANSVERSE PARKING STRIPE (FEET)	4" WHITE "NO PARKING" STRIPE (FEET)	4" DUAL YELLOW (FEET)	6" WHITE (FEET)	8" WHITE (FEET)	24" WHITE (FEET)	LETTERS AND SYMBOLS WHITE (FEET)	TEMPORARY PAVEMENT MARKING LINE, 4" (FEET)	WORKZONE PAVEMENT MARKING REMOVAL (SQ FT)
STA. 21+71 TO STA. 26+60	210		56	126	40	670	315	775	136	142.2	77	26
STA. 26+60 TO STA. 32+00	220		128	288	80	1160	125	615	116	34.8	77	26
STA. 32+00 TO STA. 37+40	240		132	288	121	845	278	492	30	66.0	77	26
STA. 37+40 TO STA. 42+34	170	70	56	153	148	840	476	476	120	152.6	69	22
TOTAL	840	70	372	855	389	3515	1194	2358	402	396	300	100

REVISIONS		
NUMBER	BY	DATE

VILLAGE OF PEORIA HEIGHTS
 PROSPECT ROAD MILL & OVERLAY
 QUANTITY SCHEDULES



HERMANN & ASSOCIATES, LLC
 CONSULTING ENGINEERS
 5835 NORTH GALENA ROAD
 PEORIA, ILLINOIS 61614
 P: (309) 687-5566
 F: (309) 687-0571

TRANSPORTATION • MUNICIPAL ENGINEERING
 LAND DEVELOPMENT • ASBESTOS INSPECTION
 CONSTRUCTION OBSERVATION

DESIGN BY: JLH
 DRAWN BY: JLH/SNP
 CHECKED BY: JLH
 APPROVED BY:
 DATE: MAY, 2009
 JOB No: 28.023.09

SHEET 3 OF 14 SHEETS