



PROPOSED HMA SURFACE COURSE, MIX "C", N70, 2"
 & PROPOSED HMA SURFACE REMOVAL 3/4"
 SEE TYPICAL SECTION SHEET 2 OF 6

STA. 11+89 TO STA. 15+00
 HMA SURFACE COURSE REMOVAL 3/4" = 1129 SQ. YD.
 HMA SURFACE COURSE, MIX "C", N70, 2" = 130 TONS
 BITUMINOUS MATERIALS (PRIME COAT) = 113 GALLONS
 AGGREGATE (PRIME COAT) = 3 TONS

PAINT PAVEMENT MARKING LINES
 (4" YELLOW) CENTERLINE STRIPE STA. 0+21 TO STA. 7+69 = 190 FOOT
 STA. 11+89 TO STA. 38+35 = 660 FOOT
 TOTAL = 850 FOOT
 (24" WHITE) STOP BARS LT. STA. 0+23 = 24 FOOT
 LT. STA. 22+72 = 18 FOOT
 TOTAL = 42 FOOT

PAVEMENT PATCHING SCHEDULE

CLASS A PATCH 8"					CLASS D PATCH 11"				
STA.	TYPE I	TYPE II	TYPE III	TYPE IV	STA.	TYPE I	TYPE II	TYPE III	TYPE IV
LT.1+40		13.3 SQ.YD.			LT.12+00		6.7 SQ.YD.		
LT.3+15			24.0 SQ.YD.		RT.12+25			22.2 SQ.YD.	
LT.3+90	1.3 SQ.YD.				RT.13+10			33.3 SQ.YD.	
RT.5+05	1.3 SQ.YD.				RT.14+30			27.8 SQ.YD.	
TOTALS	2.6 SQ.YD.	13.3 SQ.YD.	24.0 SQ.YD.		TOTALS		6.7 SQ.YD.	83.3 SQ.YD.	