



DITCH CHECK SPACING		
SLOPE (%)	HEIGHT AT CENTER OF DITCH CHECK (OVERFLOW PT) (INCHES)	SPACING OF DITCH CHECK (FEET)
8.0	12"	10
	18"	20
	24"	25
7.0	12"	15
	18"	20
	24"	30
6.0	12"	15
	18"	25
	24"	35
5.0	12"	20
	18"	30
	24"	40
4.0	12"	25
	18"	35
	24"	50
3.0	12"	35
	18"	50
	24"	65
2.0	12"	50
	18"	75
	24"	100
1.0	12"	100
	18"	150
& UNDER	24"	195

LEGEND

- INLET CHECK
- DITCH CHECK
- SILT FENCE

FILE NAME = 519SWPPP01.DWG	USER NAME = SAM WRIGLEY	DESIGNED - TLC	REVISED -
		DRAWN - SW3	REVISED -
	PLOT SCALE = 1' = 1'	CHECKED - AJG	REVISED -
	PLOT DATE = 2009-05-07	DATE - 2009-03-04	REVISED -



EROSION CONTROL PLANS	
SCALE:	SHEET NO. ___ OF ___ SHEETS
STA. _____ TO STA. _____	

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-00005-00-RP	MADISON	42	16
CONTRACT NO. 91384				
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		